

RIIMPO321B Conduct civil construction wheeled front end loader operations

Release: 1



RIIMPO321B Conduct civil construction wheeled front end loader operations

Modification History

Not applicable.

Unit Descriptor

This unit covers conducting wheeled front end loader operations in the civil construction industry. It includes: planning and preparing; conducting machine pre-operational checks; operating front end loaders; attaching, securing, lifting, carrying and placing materials; selecting, removing and fitting attachments; relocating the front end loader; carrying out machine operator maintenance; and cleaning up.

Application of the Unit

This unit is appropriate for those working in mobile plant operator roles, at worksites within:

Civil construction

Operator licence issued by OHS authority may be required in some states or territories and wheeled loaders must be registered to drive and operate on public roads.

Licensing/Regulatory Information

Refer to Unit Descriptor.

Pre-Requisites

Not applicable.

Employability Skills Information

This unit contains employability skills.

Approved Page 2 of 14

Elements and Performance Criteria Pre-Content

Elements describe the essential outcomes of a unit of competency.

Performance criteria describe the performance needed to demonstrate achievement of the element. Where bold italicised text is used, further information is detailed in the required skills and knowledge section and the range statement. Assessment of performance is to be consistent with the evidence guide.

Page 3 of 14 Approved SkillsDMC

Elements and Performance Criteria

ELEMENT	PERFORMANCE CRITERIA
1. Plan and prepare	1.1. Access, interpret and apply compliance documentation relevant to wheeled front end loader tasks 1.2. Obtain, confirm and apply work instructions to the allotted task 1.3. Obtain, confirm and apply safety requirements to the allotted task 1.4. Obtain, identify and implement signage requirements from the project traffic management plan 1.5. Select plant, tools and equipment to carry out tasks that are consistent with the requirements of the job, check them for serviceability and rectify or report any faults 1.6. Identify, confirm and apply environmental protection requirements from the project environmental management plan to the allotted task
Conduct machine pre- operational checks	2.1. Carry our pre-start, start-up, park and shutdown procedures 2.2. Check front end loader controls and functions, including implements or other attachments, brakes and manoeuvrability for serviceability, and rectify or report any faults
3. Operate front end loader	3.1.Identify site hazards associated with front end loader operations and use safe operating techniques to minimise risk 3.2.Identify and apply operating techniques for front end loader to achieve optimum output in accordance with design specifications while achieving specified tolerances 3.3.Operate front end loader to work instructions
4. Attach, secure, lift, carry and place materials	 4.1.Conduct <i>communication</i> practices associated with transportation and lifting of <i>materials</i> 4.2.Establish weight of load 4.3.Select, attach and use slings and lifting gear in accordance with safe working load requirements 4.4.Position machinery to ensure stability and

Page 4 of 14 SkillsDMC

		locate to effectively shift materials according to job specifications 4.5. Shift load safely and effectively 4.6. Move load in accordance with conventional hand and audible signals
5.	Select, remove and fit attachments	5.1. Select <i>attachment</i> for the task 5.2. Remove and fit attachment 5.3. Test attachment to ensure correct fitting and operation 5.4. Use attachment in accordance with recommendations and design limits 5.5. Clean and store removed attachments in designated location
6.	Relocate the front end loader	6.1.Move front end loader safely between worksites, observing relevant codes and traffic management requirements6.2.Prepare front end loader for relocation
7.	Carry out machine operator maintenance	 7.1. Safely park, shutdown and prepare machine for <i>maintenance</i> 7.2. Conduct inspection and fault finding 7.3. Remove and replace defective parts safely and effectively 7.4. Carry out regular programmed maintenance tasks
8.	Clean up	8.1.Clear work area and dispose of or recycle materials in accordance with project environmental management plan 8.2.Clean, check, maintain and store plant tools and equipment

Approved Page 5 of 14

Required Skills and Knowledge

This section describes the skills and knowledge required for this unit.

Required skills

Specific skills are required to achieve the performance criteria in this unit, particularly for the application in the various circumstances in which this unit may be applied. This includes the ability to carry out the following as required to conduct civil construction wheeled front end loader operations:

- apply legislative, organisation and site requirements and procedures
- apply site and equipment safety requirements
- apply techniques for calculating safe working loads
- apply front end loader and attachment operating techniques related to essential tasks
- interpret drawings and sketches
- apply operational, maintenance and basic diagnostic procedures
- apply site isolation and traffic control responsibilities and authorities
- interpret materials safety data sheets and apply materials handling methods
- apply project quality requirements
- use civil construction terminology
- apply methods of changing machine attachments
- apply safe operating techniques in all terrain
- carry out basic earthworks calculations
- apply levelling techniques
- apply JSAs/Safe work method statement

Required knowledge

Specific knowledge is required to achieve the performance criteria of this unit, particularly its application in a variety of circumstances in which the unit may be used. This includes knowledge of the following as required to conduct civil construction wheeled front end loader operations:

- front end loader types, characteristics, technical capabilities and limitations
- basic principles of soil technology for civil works
- site and equipment safety requirements
- techniques for calculating safe working loads
- front end loader and attachment operating techniques related to essential tasks
- processes for interpreting drawings and sketches
- operational, maintenance and basic diagnostic procedures
- site isolation and traffic control responsibilities and authorities
- materials safety data sheets and materials handling methods
- project quality requirements
- civil construction terminology

Approved Page 6 of 14

- methods of changing machine attachments
- safe operating techniques in all terrain
- basic earthworks calculations
- civil construction activity sequences of road construction, earthworks and drainage
- levelling techniques
- JSAs/Safe work method statement

Approved Page 7 of 14

Evidence Guide

The evidence guide provides advice on assessment and must be read in conjunction with the performance criteria, required skills and knowledge, range statement and the Assessment Guidelines for the Training Package.

Overview of assessment		
Critical aspects for assessment and evidence required to demonstrate competency in this unit	The evidence required to demonstrate competency in this unit must be relevant to worksite operations and satisfy all of the requirements of the performance criteria, required skills and knowledge and the range statement of this unit and include evidence of the following:	
	knowledge of the requirements, procedures and instructions for conducting civil construction wheeled front end loader operations	
	implementation of requirements, procedures and techniques for the safe, effective and efficient completion of civil construction wheeled front end loader operations, including:	
	in a minimum of two different soil types; and	
	to include the mandatory tasks of mixing materials, stripping/spreading topsoil and materials, loading, cutting/boxing, backfilling, lifting and carrying materials	
	working with others to undertake and complete civil construction wheeled front end loader operations that meet all of the required outcomes	
	consistent timely completion of civil construction wheeled front end loader operations that safely, effectively and efficiently meet the required outcomes	
Context of and specific resources for assessment	This unit must be assessed in the context of the work environment. Where personal safety or environmental damage are limiting factors, assessment may occur in a simulated environment provided it is realistic and sufficiently rigorous to cover all aspects of workplace performance, including task skills, task management skills, contingency management skills and job role environment skills. The assessment environment should not	

Approved Page 8 of 14

- disadvantage the participant. For example, language, literacy and numeracy demands of assessment should not be greater than those required on the job.
- Customisation of assessment and delivery environment to sensitively accommodate cultural diversity.
- Aboriginal people and other people from a non English speaking background may have second language issues.
- Assessment of this competency requires typical resources normally used in the work environment. Selection and use of resources for particular worksites may differ due to site circumstances.
- Where applicable, physical resources should include equipment modified for people with disabilities.
- Access must be provided to appropriate learning and/or assessment support when required.

Approved Page 9 of 14

Method of assessment	This unit may be assessed in a holistic way with other units of competency. The assessment strategy for this unit must verify required knowledge and skill and practical application using more than one of the following assessment methods: • written and/or oral assessment of the candidate's required knowledge • observed, documented and/or first hand testimonial evidence of the candidate's: • implementation of appropriate requirement, procedures and techniques for the safe, effective and efficient achievement of required outcomes, including: • in a minimum of two different soil types; and
	 types; and to include the mandatory tasks of mixing materials, stripping/spreading topsoil and materials, loading, cutting/boxing, backfilling, lifting and carrying materials consistently achieving the required outcomes first hand testimonial evidence of the candidate's: working with others to undertake and complete civil construction wheeled front end loader operations
Guidance information for assessment	Consult the SkillsDMC User Guide for further information on assessment including access and equity issues.

Page 10 of 14 Approved SkillsDMC

Range Statement

The range statement relates to the unit of competency as a whole. It allows for different work environments and situations that may affect performance. Bold italicised wording, if used in the performance criteria, is detailed below. Essential operating conditions that may be present with training and assessment (depending on the work situation, needs of the candidate, accessibility of the item, and local industry and regional contexts) may also be included.

,		
Relevant compliance documentation may include:	•	legislative, organisation and site requirements and procedures
	•	manufacturer's guidelines and specifications Australian standards
	•	codes of practice
		Employment and Workplace Relations
		legislation
	•	Equal Employment Opportunity and Disability Discrimination legislation
A wheeled front end loader is:	•	a self-propelled wheeled machine with an integral front-mounted bucket-supporting structure and linkage with integral quick coupler
	•	it loads or excavates through forward motion of the machine, and lifts, transports and discharges material
Front end loader tasks are to include:	•	mixing materials, stripping/spreading topsoil and materials, loading, cutting/boxing, backfilling, lifting and carrying materials
Work instructions may include:	•	plans, specifications, quality requirements and operational details
	•	quality requirements may include but not be limited to dimensions, tolerances, standards of work and material standards as detailed in the project drawings, specifications and project documentation to meet client satisfaction
Safety requirements are to be:	•	in accordance with state or territory legislation and regulations, organisational safety policies and procedures, and project safety plan
Safety requirements may include:	•	protective clothing and equipment, use of tools and equipment, workplace environment and safety, handling of materials, use of fire fighting equipment, use of First Aid equipment, hazard control and hazardous materials and substances
	•	personal protective equipment is to include that prescribed under legislation, regulation

Approved Page 11 of 14

- and workplace policies and practices
 safe operating procedures which are to include but not be limited to recognising and preventing hazards associated with underground and overhead services, other machines, personnel, restricted access barriers, traffic control, working at heights, working in proximity to others, worksite visitors and the public
- safe parking practices which is to include but not be limited to ensuring access ways are clear, equipment/machinery is away from overhangs and refuelling sites, safe distance from excavations, and secured from unauthorised access or movement
- hazards and risks may include but not be limited to uneven/unstable terrain, trees, fires, overhead and underground services, bridges, buildings, excavations, traffic, embankments, cuttings, structures and hazardous materials
- emergency procedures related to this unit are to include but may not be limited to emergency shutdown and stopping, extinguishing fires, organisational First Aid requirements and evacuation

Approved Page 12 of 14

Tools and equipment are to include:	hand tools and maintenance equipment relevant to the particular loader
Environmental requirements are to include:	organisational/project environmental management plan, waste management, water quality protection, noise, vibration, dust and clean-up management
Communications practices are to include:	 verbal instructions and fault reporting and may include two way radio, hand signals, mobile phone, site specific instructions, written instructions or instructions related to job/task on site meeting processes may include notification/ scheduling (time, place, purpose), task discussions and local coordination of procedural and operational issues
Materials may include:	 clays, silts, stone, gravel, mud, rock, sand, topsoil, blended materials, organic materials, typical construction site materials/waste and bituminous mixes rock types may include metamorphic, igneous and sedimentary
Attachments are to include:	a bucket (general purpose or multipurpose)
Attachments may include:	 rippers/scarifiers and/or other attachments approved by the manufacturer
Operator maintenance is to include:	cleaning, authorised servicing and the monitoring, recording and reporting of faults
	It may also include the conduct of authorised minor replacements and the provision of assistance to maintenance personnel during maintenance and repair activities

Unit Sector(s)

Mobile Plant Operations

Competency field

Refer to Unit Sector(s).

Approved Page 13 of 14

Co-requisite units

Not applicable.

Approved Page 14 of 14