

# **UEPMNT367A Install and commission stationary gas fuelled reciprocating engines**

Release: 1



# **UEPMNT367A** Install and commission stationary gas fuelled reciprocating engines

## **Modification History**

Not applicable.

## **Unit Descriptor**

#### **Unit Descriptor**

1) Scope:

#### 1.1) Descriptor

This unit covers the installation and commissioning of stationary gas fuelled reciprocating engines for approval where required. It encompasses working safely and to installation standards matching the plant/equipment, location, components and fuel train pipe-work to given specifications. Commissioning the plant and equipment including: pre commissioning tests, start up, adjusting components and controls to safe and efficient operation. Completing all necessary installation and commissioning documentation.

## **Application of the Unit**

#### **Application of the Unit** 2)

## **General Application** 2.1)

This competency standard unit is suitable for employment-based programs under an approved contract of training at the AQF level of the qualification in which the unit is first packaged or higher.

The unit may be selected as an elective (see qualification packaging rules) provided that all prerequisite units are undertaken or addressed through recognition processes. This unit may be included in a skill set.

#### **Importation** 2.2)

RTOs wishing to import this unit into any qualification under the flexibility provisions of NQC/NSSC Training Package Policy should ensure all pre-requiste units are also imported into the relevant Training Package and

Approved Page 2 of 15

#### qualification.

## **Licensing/Regulatory Information**

#### License to practice

3)

During Training: Competency development activities are subject to regulations directly related to licensing, occupational health and safety and where applicable contracts of training such as apprenticeships. In the workplace: The application of the skills and knowledge described in this unit in some States/Territories requires an authority to practice in the workplace. Other conditions may apply under State and Territory legislative and regulatory requirements.

## **Pre-Requisites**

**Prerequisite Unit(s)** 

**Competencies** 

4.1)

4)

Granting of competency in this unit shall be made only after competency in the following unit(s) has/have been confirmed.

Where pre-requisite pathways have been identified. All competencies in the Common Unit Group must be have been completed.

Common Unit Group

Unit Code Unit Title

UEENEEE101A Apply Occupational Health and

Safety regulations, codes and practices in the workplace

CPCCOHS1001A Work safely in the construction

industry

HLTCPR201A Perform CPR

Approved Page 3 of 15

# Literacy and numeracy 4.2) skills

Participants are best equipped to achieve this unit if they have reading, writing and numeracy skills indicated by the following levels. A description of what each level entails is provided in Section 2.3.1 Language, Literacy and Numeracy.

Reading 4 Writing 4 Numerac 4

## **Employability Skills Information**

#### **Employability Skills** 5)

This unit contains Employability Skills
The required outcomes described in this unit of
competency contain applicable facets of Employability
Skills. The Employability Skills Summary of the
qualification in which this unit of competency is packaged
will assist in identifying Employability Skill requirements.

## **Elements and Performance Criteria Pre-Content**

6) Elements describe the essential outcomes of a competency standard unit

Performance Criteria describe the required performance needed to demonstrate achievement of the element. Assessment of performance is to be consistent with the Evidence Guide.

#### **Elements and Performance Criteria**

#### ELEMENT PERFORMANCE CRITERIA

- 1 Prepare to install and commission stationary gas fuelled reciprocating engine
- 1.1 OHS procedures for a given work area are identified, obtained and understood.
- 1.2 Health and safety risks are identified and established risk control measures and procedures in preparation for the work are followed.

Approved Page 4 of 15

#### ELEMENT PERFORMANCE CRITERIA

- 1.3 Safety hazards that have not previously been identified are noted and established risk control measures are implemented.
- 1.4 Design specification for gas fuelled reciprocating engines to be installed and commissioned is accessed, analysed, interpreted and confirmed through a detailed site inspection.
- 1.5 Design specification matters requiring clarification are resolved through liaison with designer and gas authorities.
- 1.6 Formal authority to proceed with installation and commissioning is obtained before commencing work, in accordance with regulatory and code of practice requirements.
- 1.7 Installation is prepared in consultation with others affected by the work and sequenced appropriately in line with quality assurance requirements.
- 1.8 The nature and location of the work is determined from documentation or appropriate person to establish the scope of work to be undertaken.
- 1.9 Plant, equipment and component specifications and manufacturer manuals are obtained for planned work activity.
- 1.10 Locations of plant, equipment, fuel train pipe-work and components are planned within the constraints of work site, significants and requirements.
- 1.11 Materials needed for the installation work are obtained in accordance with design specification and established procedures
- 1.12 Tools, equipment, including personal protective equipment, and testing devices needed to for the installation and commissioning work are obtained in accordance with established procedures and checked for correct operation and safety.
- 1.13 Work area is prepared to support efficient installation and commissioning of the plant and equipment.

Approved Page 5 of 15

#### **ELEMENT**

#### PERFORMANCE CRITERIA

- 1.14 Preparatory work is checked to ensure no damage has occurred and complies with requirements.
- 2 Install stationary gas fuelled reciprocating engine
- 2.1 OHS risk control measures and procedures for carrying out the work are followed.
- 2.2 Regulatory and code of practice recording and reporting requirements are satisfied at appropriate times throughout the work sequence.
- 2.3 Gas and electrical circuits/machines/plant are checked as being isolated where necessary in strict accordance OHS requirements and procedures.
- 2.4 Stationary gas fuelled reciprocating engine components, including fuel train and associated pipe-work and flue/exhaust systems are installed in accordance with approved design specification and comply with technical standards and regulatory requirements, with sufficient access to affect terminations, adjustment and maintenance.
- 2.5 Ventilation systems are installed in accordance with approved design specifications
- 2.6 Electrical components, wiring enclosures and wiring, including terminations are installed in accordance with design and manufacturer's specifications, and functional and regulatory requirements.
- 2.7 Ongoing compliance and safety inspections of the installed reciprocating engine, equipment, pipework, components and accessories are undertaken and defects are rectified
- 2.8 Installation is carried out efficiently without unnecessary waste of materials or damage to plant, equipment, pipe-work, components, accessories, the surrounding environment or services and using sustainable energy principles.
- 2.9 Unexpected situations are dealt with safely and with the approval of an authorised person.

Approved Page 6 of 15

#### **ELEMENT**

#### PERFORMANCE CRITERIA

- 3 Commission stationary gas fuelled reciprocating engine
- 3.1 OHS risk control measures and procedures for carrying out the work are followed.
- 3.2 Regulatory and code of practice recording and reporting requirements are satisfied at appropriate times throughout the work sequence.
- 3.3 Gas and electrical safety checks and isolation procedures, including purging are completed and recorded to manufacturer and other authority requirements before testing and commissioning are commenced.
- 3.4 Operational parameters of individual components are tested and adjusted to conform to specifications
- 3.5 The reciprocating engine operations are tested first without and then with fuel, adjustments are completed as necessary and results recorded in accordance with approving authority requirements.
- 3.6 Exhaust gases are analysed in accordance with recognised industry practice and other authority requirements.
- 3.7 Unexpected situations are dealt with safely and with the approval of an authorised person
- 3.8 Commissioning is conducted efficiently without waste of materials or damage to apparatus and the surrounding environment or services and using sustainable energy practices
- 4 Completion and report installation and commissioning activities.
- 4.1 OHS work completion risk control measures and procedures are followed.
- 4.2 Final check of the installed reciprocating engine is made to verify that it complies with all requirements, including any certification required by local authorities.
- 4.3 Work area is cleared and materials disposed of or recycled in accordance with federal, state and territory legislation and workplace procedures.
- 4.4 Tools and equipment are cleaned, checked,

Approved Page 7 of 15

#### ELEMENT

#### PERFORMANCE CRITERIA

serviced and stored in accordance with manufacturer recommendations and workplace procedures

- 4.5 Work site is cleaned and made safe in accordance with established procedures.
- 4.6 'As-installed' reciprocating engine equipment components, pipe-work, flue/exhaust systems and accessories are documented, accessed and an appropriate person or persons notified in accordance with established procedures.

Approved Page 8 of 15

## Required Skills and Knowledge

#### REQUIRED SKILLS AND KNOWLEDGE

**8**) This describes the essential skills and knowledge and their level, required for this unit.

Evidence shall show that knowledge has been acquired of safe working practices and installing and commissioning of gas fuelled reciprocating engine

All knowledge and skills detailed in this unit should be contextualised to current industry standards, technologies and practices

The extent of the essential knowledge and associated skills (EKAS) required is given below. It forms an integral part of this unit.

KS01-PM367A Installation and commissioning of gas fuelled plant and equipment

Evidence shall show an understanding of installation and commissioning techniques for stationary gas fuelled reciprocating engines, applying safe working practices and relevant Standards, Codes and Regulations to an extent indicated by the following aspects:

- T1. Gas fuels encompassing:
- Types, properties and applications
- Safety
- Hazards
- Combustion
- Ignition types
- T2. Gas fuelled reciprocating engine overview encompassing:
- Types
- Major components
- Operating principles
- Manufacturer's specifications and diagrams
- T3. Fuel train requirements encompassing:
- Pipe-work and connections
- Valves
- Metering devices
- Regulating valves
- Electrical controls
- T4. Exhaust/flue requirements encompassing:
- Materials
- Terminations
- Sizing
- T5. Location ventilation requirements encompassing:
- Materials
- Calculations

Approved Page 9 of 15

#### REQUIRED SKILLS AND KNOWLEDGE

- Interlocks
- Locations
- T6. Hazardous area requirements encompassing:
- Locations
- Housing requirements
- Distances
- T7. Codes, regulations and standards encompassing:
- AS 3814
- AS 5601
- T8. Design specifications encompassing:
- Accessing
- Analysis and interpretation
- Calculations
- T9. Required authority to proceed encompassing:
- Regulatory requirements (Scope and restrictions)
- Standards and code of practice requirements.
- Required documentation and submissions
- T10. Site Arrangements encompassing:
- Location and environment
- Piping requirements for gas fuel train pipe-work
- Suitable equipment/equipment plant locations
- T11. Site Safety encompassing:
- Hazards
- Checklists
- Reports
- T12. Plant/equipment diagrams encompassing:
- Mechanical layouts
- Gas pipe-work drawings
- Electrical circuits
- T13. Installation encompassing:
- Reciprocating engines plant and equipment
- Gas train pipe-work and components
- Exhaust/flue system
- Ventilation system
- Pressure testing and purging
- Authorisations and certification requirements and procedures

Approved Page 10 of 15

#### REQUIRED SKILLS AND KNOWLEDGE

#### T14. Commissioning encompassing:

- Inspection of the installed reciprocating engines, pipe-work, components and accessories
- Testing reciprocating engine operation first without and then with fuel
- Testing and adjusting regulator, operation and safety controls
- Exhaust gases analysis throughout operating parameters including bifuel applications
- Compliance with design specification, regulations, codes, standards and manufacturers specifications
- Documentation and reports
  - As-installed' reciprocating engine components, pipe-work, flue/exhaust systems and accessories are documented and reported

### **Evidence Guide**

#### **EVIDENCE GUIDE**

9) The evidence guide provides advice on assessment and must be read in conjunction with the Performance Criteria, Required Skills and Knowledge, the Range Statement and the Assessment Guidelines for this Training Package.

The Evidence Guide forms an integral part of this unit. It must be used in conjunction with all parts of this unit and performed in accordance with the Assessment Guidelines of this Training Package.

# Overview of Assessment

9.1)

Longitudinal competency development approaches to assessment, such as Profiling, require data to be reliably gathered in a form that can be consistently interpreted over time. This approach is best utilised in Apprenticeship programs and reduces assessment intervention. It is the Industry's preferred model for apprenticeships. However, where summative (or final) assessment is used it is to include the application of the competency in the normal work environment or, at a minimum, the application of the competency in a realistically simulated work environment. It is recognised that, in some circumstances, assessment in part or full can occur outside the workplace. However, it must be in accordance with industry and regulatory policy.

Methods chosen for a particular assessment will be influenced by

Methods chosen for a particular assessment will be influenced by various factors. These include the extent of the assessment, the most effective locations for the assessment activities to take place,

Approved Page 11 of 15

access to physical resources, additional safety measures that may be required and the critical nature of the competencies being assessed.

The critical safety nature of working with electricity, electrical equipment, gas or any other hazardous substance/material carries risk in deeming a person competent. Sources of evidence need to be 'rich' in nature to minimise error in judgment.

Activities associated with normal every day work have a bearing on the decision as to how much and how detailed the data gathered will contribute to its 'richness'. Some skills are more critical to safety and operational requirements while the same skills may be more or less frequently practised. These points are raised for the assessors to consider when choosing an assessment method and developing assessment instruments. Sample assessment instruments are included for Assessors in the Assessment Guidelines of this Training Package.

Critical aspects of evidence required to demonstrate competency in this unit 9.2)

Before the critical aspects of evidence are considered all prerequisites shall be met.

Evidence for competence in this unit shall be considered holistically. Each element and associated performance criteria shall be demonstrated on at least two occasions in accordance with the 'Assessment Guidelines – UEP12'. Evidence shall also comprise:

- A representative body of work performance demonstrated within the timeframes typically expected of the discipline, work function and industrial environment. In particular this shall incorporate evidence that shows a candidate is able to:
  - Implement Occupational Health and Safety workplace procedures and practices including the use of risk control measures as specified in the performance criteria and range statement
  - Apply sustainable energy principles and practices as specified in the performance criteria and range statement
  - Demonstrate an understanding of the essential knowledge and associated skills as described in this unit. It may be required by some jurisdictions that RTOs provide a percentile graded result for the purpose of regulatory or licensing requirements.

Approved Page 12 of 15

- Demonstrate an appropriate level of employability skills
- Conduct work observing the relevant Anti-Discrimination legislation, regulations, polices and workplace procedures
- Demonstrated consistent performance across a representative range of contexts from the prescribed items below:
  - Install and commission gas fuelled plant and equipment as described as described in 8) and including:
    - A Obtaining formal authority to proceed with installation and commissioning before commencing work, in accordance with regulatory and code of practice requirements.
    - B Reading and interpreting drawings related to plant/equipment locations and pipe-work connections
    - C Installing, securing, aligning and connecting plant, equipment, pipe-work, components and accessories accurately in their planned location and in compliance with codes and standards.
    - D Undertaking on-going compliance and safety inspections
    - E Rectifying any defects revealed through on-going inspections
    - F Pressure testing, repairing leaks and purging the fuel train system entire system to the appropriate design test pressures.
    - G Commissioning plant and equipment operation as necessary and results recorded in accordance with approving authority requirements
    - H Correctly documenting 'as-installed' plant, equipment, pipe-work, components and accessories
    - I Dealing with unplanned events

Approved Page 13 of 15

# Context of and specific resources for assessment

#### 9.3)

This unit should be assessed as it relates to normal work practice using procedures, information and resources typical of a workplace. This should include:

- OHS policy and work procedures and instructions.
- Suitable work environment, facilities, equipment and materials to undertake actual work as prescribed by this unit.

These should be part of the formal learning/assessment environment.

Note:

Where simulation is considered a suitable strategy for assessment, conditions must be authentic and as far as possible reproduce and replicate the workplace and be consistent with the approved industry simulation policy.

The resources used for assessment should reflect current industry practices in relation to installing low voltage electrical apparatus and associated equipment.

# Method of assessment

9.4)

This unit shall be assessed by methods given in Section 1.3.00 Assessment Guidelines.

Note:

Competent performance with inherent safe working practices is expected in the industry to which this unit applies. This requires assessment in a structured environment which is primarily intended for learning/assessment and incorporates all necessary equipment and facilities for learners to develop and demonstrate the essential knowledge and skills described in this unit.

#### Concurrent assessment and relationship with other units

9.5)

There are no concurrent assessment recommendations for this unit. The critical aspects of occupational health and safety covered in either UEENEEE101A or CPCCOHS1001A and HLTCPR201A

Approved Page 14 of 15

and other discipline specific occupational health and safety units shall be incorporated in relation to this unit.

## **Range Statement**

#### RANGE STATEMENT

10) This relates to the unit as a whole providing the range of contexts and conditions to which the performance criteria apply. It allows for different work environments and situations that will affect performance.

This unit shall be demonstrated in relation to installation and commissioning of stationary gas fuelled reciprocating engines as follows: Each of the following:

- Installing and connecting gas fuel train pipe-work, regulators, valves, metering and protective devices from gas pipeline to the reciprocating engine.
- Installing and connecting flue/exhaust system
- Pressure testing and purging gas fuel train
- Commissioning gas fuelled reciprocating engine, adjusting components and controls to safe and efficient operation.

The gas fuel can be from gas gathering lines, gas transmission pipelines, distribution pipeline, and consumer gas installations. Gas Fuels can be natural gas, LPG, SNG, bio-gas, waste gas or sewage gas, used as a single gas fuel or part of a duel fuel system.

Generic terms used throughout this Vocational Standard shall be regarded as part of the Range Statement in which competency is demonstrated. The definition of these and other terms that apply are given in Section 2.1.00 Preliminary Information and Glossaries.

## **Unit Sector(s)**

Not applicable.

## **Competency Field**

Competency Field 11)

Maintenance

Approved Page 15 of 15