



Australian Government

CPCCCA3011 Refurbish timber sashes to window frames

Release: 1

CPCCCA3011 Refurbish timber sashes to window frames

Modification History

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and is equivalent to CPCCCA3011A Refurbish timber sashes to window frames. Updated to meet the Standards for Training Packages 2012.

Application

This unit of competency specifies the skills and knowledge required to refurbish timber sashes to window frames to rectify operation of external windows, meeting all relevant requirements of the National Construction Code (NCC), Australian Standards, work health and safety (WHS), and Commonwealth and state or territory legislation.

Completion of the general construction induction training program specified by the model Code of Practice for Construction Work is required for any person who is to carry out construction work. Achievement of *CPCCWHS1001 Prepare to work safely in the construction industry* meets this requirement.

No licensing, legislative or certification requirements apply to this unit at the time of publication.

Pre-requisite Unit

CPCCWHS2001 Apply WHS requirements, policies and procedures in the construction industry.

Unit Sector

Carpentry and Joinery

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

- | | |
|---------------------|--|
| 1 Plan and prepare. | 1.1 Read and interpret work instructions and plan sequence of work. |
| | 1.2 Plan all work to comply with laws and regulations, the National Construction Code (NCC), Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' |

- specifications, workplace requirements, drawings and specifications.
- 1.3 Select tools and equipment, check for serviceability and report any faults.
 - 1.4 Select and use personal protective equipment (PPE) for each part of the task.
 - 1.5 Inspect work site, assess hazards and apply risk controls, including required signage and barricades.
 - 1.6 Select materials required for task, calculate quantities, handle safely and prepare and position ready for use.
- 2 Refurbish casement/awning windows.
 - 2.1 Remove sash and hardware.
 - 2.2 Refurbish, fit and hang sash to correct margins.
 - 2.3 Fit window hardware.
- 3 Refurbish double hung windows.
 - 3.1 Remove sashes from frame in correct sequence.
 - 3.2 Refurbish and fit sashes to correct margins.
 - 3.3 Fit sash cords and weights or spiral balances or spring balances, check and adjust.
 - 3.4 Fit window hardware and mouldings.
- 4 Refurbish double hung windows.
 - 4.1 Clean up, meeting all legislative and workplace requirements for safety, waste disposal and materials handling.
 - 4.2 Check, maintain and store tools and equipment and report any faults.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

Supersedes and is equivalent to CPCCCA3011A Refurbish timber sashes to window frames.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>