



Australian Government

CPCCCA3014 Construct and install bulkheads

Release: 1

CPCCCA3014 Construct and install bulkheads

Modification History

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and is equivalent to CPCCCA3014A Construct bulkheads. Title change. Updated to meet the Standards for Training Packages 2012.

Application

This unit of competency specifies the skills and knowledge required to construct bulkheads for decorative purposes, to contain fittings, such as range hoods and cupboards, to conceal services, and to help facilitate changes in ceiling heights, meeting all relevant requirements of the National Construction Code (NCC), Australian Standards, work health and safety (WHS), and Commonwealth and state or territory legislation.

The unit includes preparing for sheeting bulkheads with plasterboard, lining boards, reconstituted timber products and metal or plastic decorative panels; and installation of bulkheads which may be hung from, incorporated into, or fastened onto a structure in situ.

Completion of the general construction induction training program specified by the model Code of Practice for Construction Work is required for any person who is to carry out construction work. Achievement of *CPCCWHS1001 Prepare to work safely in the construction industry* meets this requirement.

No licensing, legislative or certification requirements apply to this unit at the time of publication.

Pre-requisite Unit

CPCCWHS2001 Apply WHS requirements, policies and procedures in the construction industry.

Unit Sector

Carpentry and Joinery

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

- | | |
|---------------------|---|
| 1 Plan and prepare. | 1.1 Read and interpret work instructions and plan sequence of work. |
|---------------------|---|

- 1.2 Plan all work to comply with laws and regulations, the National Construction Code (NCC), Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, workplace requirements, drawings and specifications.
 - 1.3 Select tools and equipment, check for serviceability and report any faults.
 - 1.4 Select and use personal protective equipment (PPE) for each part of the task.
 - 1.5 Inspect work site, locate services, assess hazards and apply risk controls, including required signage and barricades.
 - 1.6 Identify materials required for task, calculate quantities, handle safely and prepare and position ready for use.
- 2 Fabricate bulkhead components.
- 2.1 Set out bulkhead.
 - 2.2 Cut bulkhead trimmers and plates to set out.
- 3 Install bulkhead components.
- 3.1 Select fasteners to support the weight of the bulkhead.
 - 3.2 Assemble bulkhead, fix to position and specification.
- 4 Install pre-manufactured bulkheads.
- 4.1 Set out pre-manufactured bulkhead sections.
 - 4.2 Use fasteners as specified by frame manufacturer.
 - 4.3 Fix to position and specification.
- 5 Clean up
- 5.1 Clean up, meeting all legislative and workplace requirements for safety, waste disposal and materials handling.
 - 5.2 Check, maintain and store tools and equipment and report any faults.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

Supersedes and is equivalent to CPCCCA3014A Construct bulkheads.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>