



Australian Government

CPCCCA3024 Install lining, panelling and moulding

Release: 2

CPCCCA3024 Install lining, panelling and moulding

Modification History

- Release 2 Updated reference to general construction induction training program.
- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.
- New unit

Application

This unit of competency specifies the skills and knowledge required to prepare, set out and install lining and panelling to masonry and timber and/or metal framed walls, meeting all relevant requirements of the National Construction Code (NCC), Australian Standards, work health and safety (WHS), and Commonwealth and state or territory legislation.

The unit includes installation of mouldings to provide decorative finishes.

Completion of the general construction induction training program specified by the model Code of Practice for Construction Work is required for any person who is to carry out construction work. Achievement of *CPCWHS1001 Prepare to work safely in the construction industry* meets this requirement.

No licensing, legislative or certification requirements apply to this unit at the time of publication.

Pre-requisite Unit

CPCCWHS2001 Apply WHS requirements, policies and procedures in the construction industry

Unit Sector

Carpentry and Joinery

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

- | | |
|---------------------|---|
| 1 Plan and prepare. | 1.1 Read and interpret work instructions and plan sequence of work. |
| | 1.2 Plan all work to comply with laws and regulations, the |

- National Construction Code (NCC), Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, workplace requirements, drawings and specifications.
- 1.3 Select tools and equipment, check for serviceability and report any faults.
 - 1.4 Select and use personal protective equipment (PPE) as required for each stage of the task.
 - 1.5 Inspect work site, locate services, assess hazards and apply risk controls, including required signage and barricades.
 - 1.6 Select materials required for task, calculate quantities, handle safely and prepare and position ready for use.
- 2 Prepare surface for lining/panelling.
 - 2.1 Select fixing procedures for lining materials.
 - 2.2 Set out surface to provide a balanced panel or board effect to width and height.
- 3 Install lining/panelling.
 - 3.1 Mark lining materials and cut to length and/or shape, fit and position.
 - 3.2 Secure and fix panelling/lining.
 - 3.3 Install panelling/lining to plumb, level and uniform plane.
- 4 Cut and fix profiled architrave mouldings.
 - 4.1 Mark standard architraves for edging and cut to length, position and fit.
 - 4.2 Mark skirtings and cut to length, position and fit.
 - 4.3 Mark mitre joints, cut to length, position and fit flush to face and true without gaps.
 - 4.4 Mark scribed joints and cut to length, position and fit.
 - 4.5 Cut scotia return end to profile shape and length.

- 4.6 Mark standard pelmet moulding to length and cut, fit, assemble and fix with mitres true without gaps.
 - 4.7 Set out raked moulding to position and shape mould to pattern for each position.
- 5 Clean up.
 - 5.1 Clean up meeting all legislative and workplace requirements for safety, waste disposal and materials handling.
 - 5.2 Check, maintain and store tools and equipment and report any faults.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

No equivalent unit.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>