

# CPCCPB3002 Fix standard plasterboard ceiling sheets

Release: 1

# CPCCPB3002 Fix standard plasterboard ceiling sheets

## **Modification History**

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and equivalent to CPCCPB3002A Fix standard plasterboard ceiling sheets. Updated to meet the Standards for Training Packages 2012.

### **Application**

This unit of competency specifies the skills and knowledge required to hang and fix standard plasterboard ceiling sheets.

A person working at this level would be expected to take responsibility for organising and completing tasks assigned to them without close supervision.

Completion of the general construction induction training program specified by the model Code of Practice for Construction Work is required for any person who is to carry out construction work. Achievement of unit *CPCCWHS1001* Prepare to work safely in the construction industry meets this requirement.

No licensing, legislative or certification requirements apply to this unit at the time of publication.

# Pre-requisite Unit

CPCCWHS2001 Apply WHS requirements, policies and procedures in the construction industry.

#### **Unit Sector**

Plasterboard

#### **Elements and Performance Criteria**

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

- 1 Plan and prepare.
- 1.1 Read and interpret work instructions, determine sign-off requirements for plaster-ready background, plan sequence of work and complete notifications.
- 1.2 Plan all work to comply with laws and regulations, the National Construction Code (NCC), Australian

Approved Page 2 of 4

Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, and workplace requirements.

- 1.3 Select and use personal protective equipment (PPE) for each stage of the task.
- 1.4 Inspect work site, locate services, assess hazards and apply risk controls, including required signage and barricades.
- 1.5 Collect evidence that the carpenter has completed the substrate to be plaster ready.
- 1.6 Select tools and equipment, check for serviceability and report any faults that may affect the safe operation of the equipment, tag equipment and set aside.
- 1.7 Select materials required for task, including insulation, calculate quantities, handle safely and prepare and position ready for use.
- 2 Plan and cut ceiling sheets.
- 2.1 Check framing is suitable for fixing the ceiling sheets.
- 2.2 Match sheet size to ceiling dimensions and plan cuts to minimise waste and joints while maximising board use.
- 2.3 Select screw types to suit metal or timber ceiling frame, or furring channel.
- 2.4 Plan cuts to locate joints where the effect of glancing light highlighting jointing is minimised.
- 2.5 Follow manufacturers' specifications for cutting process and provision for penetrations.
- 2.6 Cut sheets, minimising dust exposure to others, and drilling or sawing openings as required.
- 3 Fix standard ceiling sheets to frames and furring channel.
- 3.1 Hang and fix sheets using manual handling techniques and following manufacturers' specifications.
- 3.2 Check completed work to ensure stop-up activities can be easily completed.

Approved Page 3 of 4

- 4 Clean up.
- 4.1 Clear work area and dispose of, reuse or recycle materials.
- 4.2 Clean, check, maintain and store plant, tools and equipment in accordance with manufacturers' specifications.

#### **Foundation Skills**

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

# **Unit Mapping Information**

Supersedes and equivalent to CPCCPB3002A Fix standard plasterboard ceiling sheets

#### Links

Companion volumes to this training package are available at the VETNet website - https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad

Approved Page 4 of 4