

# Assessment Requirements for CPCCPB3004 Fix wet area sheets

Release: 1

# Assessment Requirements for CPCCPB3004 Fix wet area sheets

### **Modification History**

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and equivalent to CPCCPB3004A Fix wet area sheets. Updated to meet the Standards for Training Packages 2012.

#### **Performance Evidence**

To demonstrate competency, a candidate must satisfy all of the elements, performance criteria and foundation skills of this unit by hanging and fixing 15 square metres of wet area sheets.

All work must be performed to the standard required in the workplace and must comply with Commonwealth and state/territory laws and regulations, the National Construction Code, Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, and workplace requirements.

## **Knowledge Evidence**

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of the National Construction Code and Australian Standards for fixing wet area sheets, including AS/NZS2589 Gypsum linings - application and finishing
- quality policies and standards for fixing wet area sheets
- requirements for wet areas that will be tiled, and for wet areas that will be non-tiled
- safety requirements for fixing wet area sheets, including personal protective equipment (PPE), job safety analyses, safe work method statements and safety data sheets
- processes for safe handling and lifting of wet area sheets
- environmental requirements for fixing wet area sheets
- manufacturers' specifications for fixing wet area sheets
- types and uses of adhesives and fasteners for fixing wet area plasterboard sheets
- wet area plasterboard materials
- · installing flashings to specification
- materials storage and environmentally friendly waste management
- plans, drawings and specifications for fixing wet area plasterboard sheets
- plasterboard fixing techniques for wet area plasterboard sheets
- processes for the calculation of material requirements for fixing wet area plasterboard sheets
- types of tools and equipment for fixing wet area plasterboard sheets.

Approved Page 2 of 3

#### **Assessment Conditions**

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

This unit must be assessed:

- in the workplace or a close simulation of the workplace environment, provided that simulated or project-based assessment techniques replicate construction workplace conditions, materials, activities, responsibilities and procedures
- using realistic tasks or simulated tasks, relevant specifications and work instructions, standard work practices, safety requirements and environmental constraints.

#### Links

Companion volumes to this training package are available at the VETNet website - <a href="https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad">https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad</a>

Approved Page 3 of 3