



Australian Government

CPCCPB3004 Fix wet area sheets

Release: 2

CPCCPB3004 Fix wet area sheets

Modification History

Release 2 Updated reference to general construction induction training program.

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and equivalent to CPCCPB3004A Fix wet area sheets. Updated to meet the Standards for Training Packages 2012.

Application

This unit of competency specifies the skills and knowledge required to fix wet area sheets to comply with manufacturer and job specifications.

A person working at this level would be expected to take responsibility for organising and completing tasks assigned to them without close supervision.

Completion of the general construction induction training program specified by the model Code of Practice for Construction Work is required for any person who is to carry out construction work. Achievement of *CPCWHS1001 Prepare to work safely in the construction industry* meets this requirement.

No licensing, legislative or certification requirements apply to this unit at the time of publication.

Pre-requisite Unit

CPCCWHS2001 Apply WHS requirements, policies and procedures in the construction industry.

Unit Sector

Plasterboard

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

1 Plan and prepare.

1.1 Read and interpret work instructions and plan sequence of work.

1.2 Plan all work to comply with laws and regulations, the

- National Construction Code (NCC), Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, and workplace requirements.
- 1.3 Select and use personal protective equipment (PPE) for each stage of the task.
 - 1.4 Inspect work site, assess hazards and apply risk controls, including required signage and barricades.
 - 1.5 Select tools and equipment, check for serviceability and report any faults that may affect the safe operation of the equipment, tag equipment and set aside.
 - 1.6 Select materials required for task, calculate quantities, handle safely and prepare and position ready for use.
- 2 Plan and cut wet area sheets.
- 2.1 Determine work sequences, fixing processes from manufacturers' specifications and AS/NZS2589 Gypsum linings - application and finishing.
 - 2.2 Match sheet size to wall dimensions.
 - 2.3 Plan cutting process to minimise dust exposure for others.
 - 2.4 Follow manufacturers' specifications for cutting process and provision for penetrations.
 - 2.5 Cut sheets to minimise waste and number of joints and maximise board use.
- 3 Fix wet area sheets.
- 3.1 Hang and fix sheets using manual handling techniques and following manufacturer's specifications, ensuring the sheets have appropriate gap from the floor and flashing are installed to specification.
 - 3.2 Check completed work to ensure stop-up activities can be easily completed.
- 4 Clean up.
- 4.1 Clear work area and dispose of, reuse or recycle materials.

- 4.2 Clean, check, maintain and store tools and equipment in accordance with manufacturers' specifications

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

Supersedes and equivalent to CPCCPB3004A Fix wet area sheets

Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>