

CPCCWC3004 Install suspended ceilings

Release: 3

CPCCWC3004 Install suspended ceilings

Modification History

Release 3 This version first released with CPC Construction, Plumbing and Services Training Package Release 6.2.

Correction to prerequisite unit code from *CPPWHS2001 Apply WHS* requirements, policies and procedures in the construction industry to *CPCCWHS2001 Apply WHS requirements, policies and procedures in the construction industry.*

Release 2 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Updated to reflect current industry terminology, tools and equipment.

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 2.0.

Application

This unit of competency specifies the skills and knowledge required to install exposed and concealed suspended ceilings.

It includes setting out and installing ceiling suspension systems and installing lining material.

A person working at this level would be expected to take responsibility for organising and completing tasks assigned to them without close supervision.

Completion of the general construction induction training program specified by the model Code of Practice for Construction Work is required for any person who is to carry out construction work. Achievement of *CPCCWHS1001 Prepare to work safely in the construction industry* meets this requirement.

No licensing, legislative or certification requirements apply to this unit at the time of publication.

Pre-requisite Unit

CPCCWHS2001 Apply WHS requirements, policies and procedures in the construction industry.

Unit Sector

Construction

Approved Page 2 of 4

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

- 1 Plan and prepare.
- 1.1 Read and interpret work instructions and plan sequence of work.
- 1.2 Plan all work to comply with laws and regulations, the National Construction Code (NCC), Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, and workplace requirements.
- 1.3 Select and use personal protective equipment (PPE) for each stage of the task.
- 1.4 Inspect work site, assess hazards and apply risk controls, including required signage and barricades.
- 1.5 Select tools and equipment, check for serviceability and report any faults that may affect the safe operation of the equipment, tag equipment and set aside.
- 1.6 Select materials required for task, calculate quantities, handle safely and prepare and position ready for use.
- 2 Install suspension system.
- 2.1 Set out ceiling grid and alignment levels for ceiling.
- 2.2 Fix suspension rods to underside of soffit and structural members with masonry anchors, bolts and screws at prescribed centres.
- 2.3 Assemble suspended framework and connect to suspension rods.
- 2.4 Fasten suspension system, check for looseness and rattles, and secure as required.
- 2.5 Fix bridging framework to both sides of service ducts to support suspension system.
- 3 Install lining materials.
- 3.1 Install lining materials according to design pattern set out in job drawings.
- 3.2 Cut edges of lining materials and conceal to match

Approved Page 3 of 4

pre-finished edges.

- 3.3 Provide openings and penetrations as shown in job drawings.
- Fix trims and beads at junctions with other building elements and surfaces.
- 4 Clean up.
- 4.1 Clear work area and dispose of, reuse or recycle materials.
- 4.2 Clean, check, maintain and store tools and equipment in accordance with manufacturers' specifications.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

Supersedes and equivalent to CPCCWC3004A Install suspended ceilings

Links

Companion Volume implementation guides are found in VETNet - https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad

Approved Page 4 of 4