



Australian Government

**CPCPGS3060 Install LPG storage of
aggregate storage capacity exceeding 500
litres and less than 8 kl**

Release: 2

CPCPGS3060 Install LPG storage of aggregate storage capacity exceeding 500 litres and less than 8 kl

Modification History

Release 2	This version first released with CPC Construction, Plumbing and Services Training Package Release 5.1. Change to Pre-requisite unit.
Release 1	This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0. Supersedes and is equivalent to CPCPGS3060A Install LPG storage of aggregate storage capacity exceeding 500 litres and less than 8 KL. Updated to meet the Standards for Training Packages 2012.

Application

This unit specifies the skills and knowledge required to select, locate and install liquefied petroleum gas (LPG) storage of 500 to 8000 litres aggregate capacity.

In some jurisdictions, this unit of competency may form part of accreditation, licensing, legislative, regulatory or certification requirements.

Pre-requisite Unit

CPCPCM2043 Carry out WHS requirements

Unit Sector

Plumbing

Elements and Performance Criteria

Elements describe the essential outcomes.	Performance criteria describe what needs to be done to demonstrate achievement of the element.
1 Plan the work.	1.1 Access, read and determine LPG system installation requirements from relevant job plans and specifications, codes, Australian standards, manufacturer’s specifications and jurisdictional requirements. 1.2 Identify and apply workplace policies and procedure and work health and safety (WHS) and environmental

- requirements.
- 1.3 Determine gas load and design requirements.
 - 1.4 Check storage capacity for compliance with relevant job plans and specifications, codes, Australian standards, manufacturer's specifications and jurisdictional requirements.
 - 1.5 Determine appropriate regulators to meet capacity and load of the system.
 - 1.6 Select the location of LPG cylinders or tank according to relevant job plans and specifications, codes, relevant Australian standards, manufacturer's specifications and jurisdictional requirements.
- 2 Prepare for work.
- 2.1 Create a materials list and collect materials.
 - 2.2 Select appropriate tools and equipment, including personal protective equipment (PPE).
 - 2.3 Select appropriate testing equipment.
 - 2.4 Prepare work area and materials to support installation.
- 3 Install and test LPG storage system.
- 3.1 Install LPG storage container/s, piping, fittings and components in compliance with relevant job plans and specifications, codes, Australian standards, manufacturer's specifications and jurisdictional requirements.
 - 3.2 Install regulators and associated pipework, in compliance with relevant job plans and specifications, codes, Australian standards, manufacturer's specifications and jurisdictional requirements.
 - 3.3 Test and purge installation.
 - 3.4 Commission installation, including checking regulator working and lockup pressure.
 - 3.5 Complete documentation according to installation requirements and/or workplace procedures.

- 4 Clean up.
 - 4.1 Clear the work area, and dispose of, reuse or recycle materials in accordance with state and territory legislation and workplace policies and procedures.
 - 4.2 Clean tools and equipment, check for serviceability and report any damage, and store and secure.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

Supersedes and is equivalent to CPCPGS3060A Install LPG storage of aggregate storage capacity exceeding 500 litres and less than 8 KL.

Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>