



Australian Government

CPCPMS3038 Install air conditioning control equipment

Release: 2

CPCPMS3038 Install air conditioning control equipment

Modification History

Release 2 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.1.

Typographical error corrected in Element 2.1.

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and is equivalent to CPCPMS3038A Install air conditioning control equipment. Updated to meet the Standards for Training Packages 2012.

Application

This unit specifies the skills and knowledge required to install air conditioning control equipment for the control of pressure, temperature, flow rate, humidity and density.

Site location for work application may be either domestic or commercial and may be a new work site or an existing structure being renovated, extended, restored or maintained

In some jurisdictions, this unit of competency may form part of accreditation, licensing, legislative, regulatory or certification requirements.

Pre-requisite Unit

CPCPCM2043 Carry out WHS requirements

Unit Sector

Plumbing

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

- | | |
|---------------------|--|
| 1 Prepare for work. | 1.1 Access and read job plans and specifications. |
| | 1.2 Identify and apply workplace policies and procedures, work health and safety (WHS) and environmental requirements. |

- 1.3 Apply quality assurance requirements in accordance with workplace requirements.
 - 1.4 Plan and sequence tasks in conjunction with others.
 - 1.5 Prepare work area to support efficient installation of air conditioning control equipment.
 - 1.6 Select appropriate tools and equipment including personal protective equipment (PPE) and check for serviceability.
 - 1.7 Identify materials and equipment required to complete the task.
- 2 Identify system requirements.
 - 2.1 Create a materials list and collect materials.
 - 2.2 Identify fabrication requirements from job plans, specifications and relevant information.
 - 2.3 Calculate quantity and type of materials and components.
- 3 Install control equipment.
 - 3.1 Shut down and isolate air conditioning system according to appropriate codes of practice and WHS requirements.
 - 3.2 Install control equipment to job specification or manufacturer's instructions and report faults, as required.
 - 3.3 Position control equipment in specified location without damage or distortion to surrounding environment or other services.
 - 3.4 Calibrate control equipment according to manufacturer recommendations and job specifications.
 - 3.5 Check correct operation of system control equipment against operational specification.
- 4 Clean up.
 - 4.1 Clear the work area, and dispose of, reuse or recycle materials in accordance with state and territory legislation and workplace policies and procedures.
 - 4.2 Clean tools and equipment, check for serviceability reporting any damage, store and secure.

- 4.3 Complete documentation according to workplace requirements.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

Supersedes and is equivalent to CPCPMS3038A Install air conditioning control equipment.

Links

Companion volumes to this training package are available at the VETNet website -
<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>