



**Australian Government**

# **CPCSHP3008 Install internal shop walls and fixtures**

**Release: 2**

# CPCSHP3008 Install internal shop walls and fixtures

## Modification History

|           |                                                                                                                                                                                                          |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Release 2 | Updated reference to general construction induction training program.                                                                                                                                    |
| Release 1 | <p>This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0</p> <p>Supersedes and is equivalent to CPCCSH3008 Install internal shop walls and fixtures.</p> |

## Application

This unit of competency specifies the skills and knowledge required to prepare, set out and install wall frames, partitions and wall linings to areas such as fitting or treatment rooms in internal shop areas. It includes fitting doors and windows, fixing mouldings and installing fixtures.

It applies to shopfitters engaged in creating new shops or renovating existing shops. The work is completed onsite concurrently with other shopfitting work that must be scheduled to accommodate client requirements, the shop when it is operational, and the requirements of other shopfitters and associated contractors.

Individuals at this level take responsibility for organising and completing these tasks with a high degree of self-direction.

No licensing, legislative or certification requirements apply to this unit of competency at the time of publication.

Completion of the general construction induction training program, specified in the Safe Work Australia model *Code of Practice: Construction Work*, is required by anyone carrying out construction work. Achievement of *CPCWHS1001 Prepare to work safely in the construction industry* meets this requirement.

## Pre-requisite Unit

Nil.

## Unit Sector

Shopfitting

## Elements and Performance Criteria

Elements describe the      Performance criteria describe what needs to be done to

|                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-----------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| essential outcomes.                                             | demonstrate achievement of the element.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| 1 Plan and prepare to install internal shop walls and fixtures. | <ul style="list-style-type: none"><li>1.1 Read and interpret plans and specifications to confirm job requirements.</li><li>1.2 Interpret and apply organisational quality assurance requirements appropriate for the project.</li><li>1.3 Determine material type and calculate quantities to complete the task.</li><li>1.4 Determine job priorities and sequence job tasks in consultation with others in the workplace to ensure timeframes are met.</li><li>1.5 Inspect worksite conditions, identify hazards and implement risk control measures following work health and safety requirements and environmental practices.</li><li>1.6 Select, fit and use personal protective equipment (PPE) for the task.</li><li>1.7 Select tools and equipment for the task.</li><li>1.8 Check for serviceability and rectify and report faults.</li><li>1.9 Receive and check delivered materials for completeness and conformity with job requirements and identify and report any discrepancies or damage.</li><li>1.10 Place materials in a safe and secure position ready for use.</li></ul> |
| 2 Install internal wall framing and lining.                     | <ul style="list-style-type: none"><li>2.1 Set out Internal wall framing parallel and square to existing structure.</li><li>2.2 Set out frame with door and window openings, cut frame members and assemble ready to erect.</li><li>2.3 Stand frame into position, level, square and plumb and use appropriate fixing method and fastenings appropriate for the existing structure.</li><li>2.4 Mark and cut lining material to length, and shape and fix to frame to meet job requirements.</li></ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |

- |   |                                   |     |                                                                                                                       |
|---|-----------------------------------|-----|-----------------------------------------------------------------------------------------------------------------------|
| 3 | Install partitions.               | 3.1 | Set out and mark position of pre-assembled or onsite assembled partitions to plan dimensions.                         |
|   |                                   | 3.2 | Cut partition components accurately to size and locate connection points.                                             |
|   |                                   | 3.3 | Install and secure each component junction tight together and flush with face using specified fixings and fastenings. |
|   |                                   | 3.4 | Secure, square and plumb assembled partitions within accepted industry tolerances.                                    |
|   |                                   |     |                                                                                                                       |
| 4 | Cut and fix decorative mouldings. | 4.1 | Mark, cut to length, fit and fix specified mouldings.                                                                 |
|   |                                   | 4.2 | Fit and fix mitre joints flush to face and true.                                                                      |
|   |                                   | 4.3 | Mark and cut to length scribed joints.                                                                                |
|   |                                   | 4.4 | Set out, mark and fix specified fixtures.                                                                             |
|   |                                   |     |                                                                                                                       |
| 5 | Clean up.                         | 5.1 | Clear work area and dispose of, reuse or recycle materials following workplace and environmental requirements.        |
|   |                                   | 5.2 | Clean tools and equipment, check for serviceability and report damage or faults.                                      |
|   |                                   | 5.3 | Store and secure tools and equipment following workplace procedures.                                                  |

## Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

## Unit Mapping Information

Supersedes and is equivalent to CPCCSH3008 Install internal shop walls and fixtures.

## Links

Companion volumes to this training package are available at the VETNet website -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>