



Australian Government

Department of Education, Employment and Workplace Relations

CPCCCA3022A Install curtain walling

Release: 1

CPCCCA3022A Install curtain walling

Modification History

Not Applicable

Unit Descriptor

Unit descriptor

This unit of competency specifies the outcomes required to fit and fix curtain walling facades to multi-storey structures to provide external cladding of structural steel or reinforced concrete. It includes fabricated frameworks with metal cladding, fabricated framework with glass panels, pre-cast concrete panels, and manufactured and natural stone products in or on the structure.

Application of the Unit

Application of the unit

This unit of competency supports achievement of skills fabricating and installing curtain walling framework to facilitate cladding a building surface with a variety of cladding materials, such as metal, glass, pre-cast concrete and stone. Work is to be carried out with others and as a member of a team situation working with other trades, including carpenters, riggers, crane operators, concreters and steel fixers.

Licensing/Regulatory Information

Not Applicable

Pre-Requisites

Prerequisite units CPCCOHS2001A Apply OHS requirements, policies and procedures in the construction industry

Employability Skills Information

Employability skills This unit contains employability skills.

Elements and Performance Criteria Pre-Content

Elements describe the essential outcomes of a unit of competency.

Performance criteria describe the performance needed to demonstrate achievement of the element. Where bold italicised text is used, further information is detailed in the required skills and knowledge section and the range statement. Assessment of performance is to be consistent with the evidence guide.

Elements and Performance Criteria

ELEMENT	PERFORMANCE CRITERIA
1. Plan and prepare.	<p>1.1. Work instructions, including plans, specifications, quality requirements and operational details, are obtained, confirmed and applied from relevant information for planning and preparation purposes.</p> <p>1.2. Safety (OHS) requirements are followed in accordance with safety plans and policies.</p> <p>1.3. Signage and barricade requirements are identified and implemented.</p> <p>1.4. Tools and equipment selected to carry out tasks are consistent with job requirements, checked for serviceability, and any faults are rectified or reported prior to commencement.</p> <p>1.5. Material quantity requirements are calculated in accordance with plans, specifications and quality requirements.</p> <p>1.6. Materials appropriate to the work application are identified, obtained, prepared, safely handled and located ready for use.</p> <p>1.7. Environmental requirements are identified for the project in accordance with environmental plans and statutory and regulatory authority obligations, and are applied.</p>
2. Prepare site for installation.	<p>2.1. Location of curtain wall installation connections are set out to job drawings and specifications.</p> <p>2.2. Area below construction face is cleared and isolated with designed barricade to OHS regulations and job work plans allowing for support plant and equipment.</p> <p>2.3. Surface of structure to receive curtain walling is inspected for conformity and surface is prepared to receive fixings according to job drawings and specifications.</p>
3. Install curtain walling.	<p>3.1. Curtain wall fixing brackets are checked or installed to set out points in accordance with manufacturer specifications and site structural drawings.</p> <p>3.2. Curtain walling is located and fixed into correct position in accordance with job drawings, after being raised to location by crane operations.</p> <p>3.3. Curtain walling is installed plumb and level and aligned and finally fixed into position in accordance with specifications.</p>

ELEMENT	PERFORMANCE CRITERIA
	<p>3.4. Junctions between placed sections of curtain walling are fitted and secured to fixing specifications.</p> <p>3.5. Curtain wall trims are installed in accordance with manufacturer specifications and detail drawings, where applicable.</p>
4. Seal curtain walling.	<p>4.1. Surface areas are cleaned in preparation for application of caulking sealants.</p> <p>4.2. Sealants are applied to curtain walling and trims, where specified, in accordance with job specifications.</p>
5. Clean up.	<p>5.1. Work area is cleared and materials disposed of, reused or recycled in accordance with legislation, regulations, codes of practice and job specification.</p> <p>5.2. Tools and equipment are cleaned, checked, maintained and stored in accordance with manufacturer recommendations and standard work practices.</p>

Required Skills and Knowledge

REQUIRED SKILLS AND KNOWLEDGE

This section describes the skills and knowledge required for this unit.

Required skills

Required skills for this unit are:

- communication skills to:
 - determine requirements
 - enable clear and direct communication, using questioning to identify and confirm requirements, share information, listen and understand
 - follow instructions
 - read and interpret:
 - documentation from a variety of sources
 - plans, specifications and drawings
 - report faults
 - use language and concepts appropriate to cultural differences
 - use and interpret non-verbal communication, such as hand signals
- numeracy skills to apply measurements and make calculations

REQUIRED SKILLS AND KNOWLEDGE

- organisational skills, including the ability to plan and set out work
- teamwork skills to work with others to action tasks and relate to people from a range of cultural and ethnic backgrounds and with varying physical and mental abilities
- technological skills to:
 - use a range of mobile technology, such as two-way radio and mobile phones
 - voice and hand signals to access and understand site-specific instructions.

Required knowledge

Required knowledge for this unit is:

- construction terminology
- curtain walling materials, systems and techniques
- fall arrest system
- job safety analysis (JSA) and safe work method statements
- material safety data sheets (MSDS)
- materials storage and environmentally friendly waste management
- plans, specifications and drawings
- processes for the calculation of material requirements
- purpose and safe use of swing scaffolding
- quality requirements for curtain walling
- slings, clutches and other applicable lifting equipment
- tools and equipment types, characteristics, uses and limitation
- workplace and equipment safety requirements.

Evidence Guide

EVIDENCE GUIDE

The evidence guide provides advice on assessment and must be read in conjunction with the performance criteria, required skills and knowledge, range statement and the Assessment Guidelines for the Training Package.

Overview of assessment

This unit of competency could be assessed in the workplace or a close simulation of the workplace environment, provided that simulated or project-based assessment techniques fully replicate construction workplace conditions, materials, activities, responsibilities and procedures.

Critical aspects for assessment and evidence required to demonstrate competency in this unit

A person who demonstrates competency in this unit must be able to provide evidence of the ability to:

- locate, interpret and apply relevant information, standards and specifications
- comply with site safety plan, OHS regulations and state and territory legislation applicable to workplace operations
- comply with organisational policies and procedures, including quality requirements
- safely and effectively use tools and equipment
- communicate and work effectively and safely with others
- complete external surface preparation to receive fixings that are checked for conformity with tolerances for plumb and line
- install check, place, fix and seal sections of curtain walling for a multi-storey project.

Context of and specific resources for assessment

This competency is to be assessed using standard and authorised work practices, safety requirements and environmental constraints.

Assessment of essential underpinning knowledge will usually be conducted in an off-site context.

Assessment is to comply with relevant regulatory or Australian standards' requirements.

Resource implications for assessment include:

- an induction procedure and requirement
- realistic tasks or simulated tasks covering the mandatory task requirements

EVIDENCE GUIDE

- relevant specifications and work instructions
- tools and equipment appropriate to applying safe work practices
- support materials appropriate to activity
- workplace instructions relating to safe work practices and addressing hazards and emergencies
- material safety data sheets
- research resources, including industry related systems information.

Reasonable adjustments for people with disabilities must be made to assessment processes where required. This could include access to modified equipment and other physical resources, and the provision of appropriate assessment support.

Method of assessment

Assessment methods must:

- satisfy the endorsed Assessment Guidelines of the Construction, Plumbing and Services Training Package
- include direct observation of tasks in real or simulated work conditions, with questioning to confirm the ability to consistently identify and correctly interpret the essential underpinning knowledge required for practical application
- reinforce the integration of employability skills with workplace tasks and job roles
- confirm that competency is verified and able to be transferred to other circumstances and environments.

Validity and sufficiency of evidence requires that:

- competency will need to be demonstrated over a period of time reflecting the scope of the role and the practical requirements of the workplace
- where the assessment is part of a structured learning experience the evidence collected must relate to a number of performances assessed at different points in time and separated by further learning and practice, with a decision on competency only taken at the point when the assessor has complete

EVIDENCE GUIDE

confidence in the person's demonstrated ability and applied knowledge

- all assessment that is part of a structured learning experience must include a combination of direct, indirect and supplementary evidence.

Assessment processes and techniques should as far as is practical take into account the language, literacy and numeracy capacity of the candidate in relation to the competency being assessed.

Supplementary evidence of competency may be obtained from relevant authenticated documentation from third parties, such as existing supervisors, team leaders or specialist training staff.

Range Statement

RANGE STATEMENT

The range statement relates to the unit of competency as a whole. It allows for different work environments and situations that may affect performance. Bold italicised wording, if used in the performance criteria, is detailed below. Essential operating conditions that may be present with training and assessment (depending on the work situation, needs of the candidate, accessibility of the item, and local industry and regional contexts) may also be included.

Information includes:

- diagrams or sketches
- instructions issued by authorised organisational or external personnel
- manufacturer specifications and instructions where specified
- memos
- MSDS
- organisation work specifications and requirements
- plans and specifications
- regulatory and legislative requirements pertaining to installing curtain walling
- relevant Australian standards
- safe work procedures related to installing

RANGE STATEMENT

	curtain walling
	<ul style="list-style-type: none"> • signage • verbal or written and graphical instructions • work bulletins • work schedules.
<i>Planning and preparation</i> include:	<ul style="list-style-type: none"> • work site inspection • equipment defect identification • assessment of conditions and hazards • determination of work requirements.
<i>Safety (OHS)</i> is to be in accordance with state or territory legislation, regulations, codes of practice, organisational safety policies and procedures, and project safety plan and may include:	<ul style="list-style-type: none"> • emergency procedures, including extinguishing fires, organisational first aid requirements and evacuation • handling of materials • hazard control • hazardous materials and substances • safe operating procedures, including the conduct of operational risk assessment and treatments associated with: <ul style="list-style-type: none"> • earth leakage boxes • lighting • personnel • power cables, including overhead service trays, cables and conduits • restricted access barriers • surrounding structures • traffic control • trip hazards • work site visitors and the public • working at heights • working in confined spaces • working with dangerous materials • organisational first aid • personal protective clothing and equipment prescribed under legislation, regulations and workplace policies and practices • use of firefighting equipment • use of tools and equipment • workplace environment and safety.
<i>Tools and equipment</i> include:	<ul style="list-style-type: none"> • caulking guns • explosive power tools

RANGE STATEMENT

	<ul style="list-style-type: none"> • fall arrest systems • hammers • levelling equipment • measuring tapes and rules • power drills • power grinders • power leads • spanners • spirit levels • squares (combination/tri) • wedges.
<i>Quality requirements</i> include relevant regulations, including:	<ul style="list-style-type: none"> • Australian standards • internal company quality policy and standards • manufacturer specifications, where specified • workplace operations and procedures.
<i>Materials</i> include:	<ul style="list-style-type: none"> • curtain wall components and combinations thereof.
<i>Environmental requirements</i> include:	<ul style="list-style-type: none"> • clean-up protection • noise and dust • vibration • waste management.
<i>Statutory and regulatory authorities</i> include:	<ul style="list-style-type: none"> • federal, state and local authorities administering applicable Acts, regulations and codes of practice.
<i>Curtain wall installation</i> includes:	<ul style="list-style-type: none"> • fabricated framework with glass panels • fabricated framework with metal cladding • manufactured and natural stone products • pre-cast concrete panels • types of structural frames, including structural steel, in situ reinforced concrete and pre-cast concrete.
<i>Support plant and equipment</i> includes:	<ul style="list-style-type: none"> • compressors • cranes • elevated work platforms • hoses and fittings • scaffolding • welding equipment • winches.
<i>Curtain wall fixing</i> includes:	<ul style="list-style-type: none"> • drilling holes • fixing brackets to steelwork

RANGE STATEMENT

- installing masonry anchors
- trimming concrete surfaces for flatness.

Unit Sector(s)

Unit sector Construction

Co-requisite units

Co-requisite units Nil

Functional area

Functional area