



Australian Government

Assessment Requirements for MSFFL3017

Install resilient sheet to walls

Release: 1

Assessment Requirements for MSFFL3017 Install resilient sheet to walls

Modification History

Release 1 - New unit of competency

Performance Evidence

- Interpret work order and locate and apply relevant information
- Apply safe handling requirements for equipment, products and materials, including use of personal protective equipment
- Identify materials used in the work process
- Follow work instructions, operating procedures and inspection processes to:
 - minimise the risk of injury to self or others
 - prevent damage to goods, equipment and products
 - maintain required production output and product quality
- Complete a minimum of:
 - one (1) installation of a wet wall resilient wall covering installation using a horizontal installation system, including internal and external corners to walls, the covering of window reveals, and sealing to door frames and fittings
 - one (1) installation of a wet wall resilient wall covering installation using a vertical installation system, including internal and external corners to walls, the covering of window reveals and sealing to door frames and fittings
- Use mathematical ideas and techniques to correctly complete measurements, calculate area and estimate material requirements
- Communicate ideas and information to enable confirmation of work requirements and specifications and the reporting of work outcomes and problems, interpret basic plans and follow safety procedures
- Avoid backtracking, work flow interruptions or wastage
- Work with others and in a team by recognising dependencies and using cooperative approaches to optimise work flow and productivity

Knowledge Evidence

- State or territory WHS legislation, regulations, standards and codes of practice relevant to installing resilient sheet to walls
- Organisational and site standards, requirements, policies and procedures for installing resilient sheet to walls
- Environmental protection requirements
- Established communication channels and protocols
- Relevant problem identification and resolution
- Types of tools and equipment and procedures for their safe use, operation and maintenance
- Characteristics of materials, products and defects
- Set-up and operation of equipment
- Products assembly techniques
- Procedures for the recording, reporting and maintenance of workplace records and information
- Appropriate mathematical procedures for estimation and measurement
- Type, characteristics, uses and limitations of:
 - weldable resilient wall coverings
 - resilient wall covering installation adhesives
- Types and uses of resilient wall covering installation tools and equipment
- Workplace safety system requirements related to resilient wall covering installation
- Characteristics and requirements of substrate preparation for wall coverings
- Work flow in relation to fixing, welding and finishing of resilient wall coverings

Assessment Conditions

- Assessors must:
 - hold training and assessment competencies as determined by the National Skills Standards Council (NSSC) or its successors
 - have vocational competency in the furnishing industry at least to the level being assessed with broad industry knowledge and experience, usually combined with a relevant industry qualification
 - be familiar with the current skills and knowledge used and have relevant, current experience in the furnishing industry.
- Assessment methods must confirm consistency of performance over time rather than a single assessment event and in a range of workplace relevant contexts.
- Assessment must be by observation of relevant tasks with questioning on underpinning knowledge and, where applicable, multimedia evidence, supervisor's reports, projects and work samples.
- Assessment is to be conducted on single units of competency or in conjunction with other related units of competency. Foundation skills are integral to competent performance in the unit and should not be assessed separately.
- Assessment must occur on the job or in a workplace simulated facility with relevant process, equipment, materials, work instructions and deadlines.
- Access is required to materials, equipment and specifications relevant to installing resilient sheet to walls.

Links

Companion Volume implementation guides are found in VETNet -
<https://vetnet.education.gov.au/Pages/TrainingDocs.aspx?q=0601ab95-583a-4e93-b2d4-cfb27b03ed73>