



Australian Government

Assessment Requirements for MSFFL3065

Install resilient tiles

Release: 1

Assessment Requirements for MSFFL3065 Install resilient tiles

Modification History

Release 1. Supersedes and is not equivalent to MSFFL2022 Install resilient tiles using standard installation procedures, and, MSFFL3015 Install resilient tiles using custom designs and decorative finishes.

Performance Evidence

There must be evidence the candidate has completed the tasks outlined in the elements and performance criteria of this unit, and:

- installed the following resilient tiles where cutting and fixing is required, on either a timber or concrete subfloor in accordance with job requirements:
 - 1 resilient tile and/or plank installation of connecting rooms using multi-directional patterns
 - 1 resilient tile and/or plank installation that includes a 45 degree set out with borders
 - 1 resilient tile and/or plank installation that includes a custom design or feature strips.
 -

Knowledge Evidence

There must be evidence the candidate has knowledge of:

- mathematical procedures for estimation and measurement, including calculation of area, angles and estimation of material requirements
- resilient tile installation:
 - Australian Standards requirements
 - workplace safety system requirements
 - environmental protection and sustainability requirements
 - how to access manufacturer instructions
 - work flow
 - characteristics and requirements of subfloor preparation
 - types, characteristics, uses and limitations of different resilient tiles, including:
 - homogenous and heterogeneous
 - linoleum
 - planks
 - rigid
 - rubber
 - semi-rigid
 - types, characteristics, uses and limitations of different adhesives, including:
 - double sided tape

- pressure sensitive and wet acrylics
- water and solvent-based contacts
- two-part epoxy
- polyurethane contact adhesive
- types, characteristics, safe use, maintenance and limitations of tools, equipment and materials
- techniques for set out, laying, cutting and fixing, the types of problems that may occur and how to avoid and respond:
 - 45 degrees set out
 - borders
 - feature strips
 - herringbone
- quality indicators for completed work
- procedures for the recording, reporting and maintenance of workplace records and information.
-

Assessment Conditions

Skills must have been demonstrated in the workplace or in a simulated environment that reflects workplace conditions and contingencies.

The following conditions must be met for this unit:

- use of suitable facilities, equipment and resources, including:
 - locations requiring resilient tile installation
 - resilient tiles
 - equipment, tools and materials to complete tasks in the Performance Evidence, including safety and personal protective equipment
 - work orders
 - workplace procedures.

Assessors must satisfy the NVR/AQTF mandatory competency requirements for assessors.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=0601ab95-583a-4e93-b2d4-cfb27b03ed73>