



Australian Government

Assessment Requirements for MSFFL3120 Install timber flooring on joists

Release: 1

Assessment Requirements for MSFFL3120 Install timber flooring on joists

Modification History

Release 1. New unit.

Performance Evidence

There must be evidence the candidate has completed the tasks in the elements and performance criteria of this unit of competency and has demonstrated the ability to complete according to job instructions:

- one installation of 19 mm strip timber flooring directly onto joists to an area of at least five joist spaces and at least one metre wide
- one installation of a ply or reconstituted timber sheet product directly onto joists an area of at least five joist spaces and at least one metre wide
- one installation of 19 mm decking directly onto joists comprising an area of at least five joist spaces and at least one metre wide
- the removal and replacement of a board in an existing timber floor directly onto joists.

Knowledge Evidence

There must be evidence the candidate has knowledge of:

- AS 1684 Residential Timber Framed Construction as it applies to the installation of timber flooring
- manufacturer installation instructions for:
 - strip timber flooring (19 mm or thicker)
 - decking boards
 - plywood
 - particleboard
- manufacturer use instructions for polyurethane and polymer adhesives
- the safe and correct use of, and maintenance requirements for tools and equipment for, installing timber flooring on joists
- the most common issues that can arise when installing timber flooring on joists and how to avoid and respond to them
- workplace policies and procedures relevant to their job role and responsibilities including for:
 - installing timber flooring on joists
 - communication and reporting
 - environmental protection and sustainability, including maximising resource utilisation and minimising waste
 - quality indicators for completed work and process improvements

- work health and safety, including the use of personal protective equipment and safety data sheets
- work planning
- how to identify if joists are suitable for installing timber flooring
- how to identify if timber flooring is installed correctly on joists.

Assessment Conditions

Skills must have been demonstrated in the workplace or in a simulated environment that reflects workplace conditions and contingencies. The following conditions must be met for this unit:

- use of suitable facilities, equipment and resources, including:
 - locations with joists on which to install timber flooring
 - timber flooring and other materials required by job instructions
 - equipment and tools required for the activities set out in the elements and performance criteria, including those to control hazards
 - job instructions and workplace procedures.

Assessors must satisfy the NVR/AQTF mandatory competency requirements for assessors.

Links

Companion Volume Implementation Guides are found in VETNet --

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=0601ab95-583a-4e93-b2d4-cfb27b03ed73>