

RIICRC202D Install signs

Release: 2

RIICRC202D Install signs

Modification History

Release	Comment
1	This unit replaces RIICRC202A Install signs
2	Required frequency and volume of evidence amended in Performance evidence.
	Substantial amendments made in Assessment Conditions field, including: references to Industry Sectors, assessor and subject matter expert experience requirements, how assessment should be conducted and what it should confirm.

Application

This unit describes a participant's skills and knowledge required to install signs in Civil Construction.

This unit is appropriate for those working in operational roles.

Licensing, legislative, regulatory and certification requirements that apply to this unit can vary between states, territories, and Industry sectors. Relevant information much be sourced prior to application of this unit.

Unit Sector

Civil construction

Elements and Performance Criteria

1. Plan and prepare for installing	1.1 and en	Access, interpret and apply sign installation documentation is used the work activity is compliant
signs	1.2	Obtain, read, interpret, clarify and confirm work requirements
	1.3 environ	Identify and address potential risks, hazards and mmental issues, and implement control measures
	1.4 approp	Select and wear correct personal protective equipment priate for work activities
	1.5	Identify, obtain, confirm and implement signage requirements
	1.6 carry	Select and check for faults all plant, tools and equipment to out tasks
	1.7	Clarify and confirm permits and clearances in accordance with

Approved Page 2 of 4

	regulatory authority requirements
2. Transport sign and materials to the site	2.1 Survey location of the site in accordance with job drawings and specifications
	2.2 Arrange site access in accordance with safe working procedures
	2.3 Prepare delivery site for risk control
	2.4 Determine availability of loading/unloading equipment
	2.5 Arrange transportation of signage
	2.6 Protect signs appropriately and pack them securely for transportation
	2.7 Load, transport and off-load signs and equipment correctly
3. Assemble sign	3.1 Lay out and check sign components prior to assembly
	3.2 Confirm correct signage against specifications
	3.3 Assemble sign on or off site as appropriate
4. Erect sign	4.1 Determine method of erection according to job requirements
	4.2 Prepare support materials according to drawings and specifications
	4.3 Install fastenings to manufacturer's recommendations
	4.4 Brace support structure safely
	4.5 Erect sign efficiently and safely
5. Clean up	5.1 Clear work area and recycle or dispose of materials
	5.2 Clean, check, maintain and store plant and equipment

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit. Further information is available in the Resources and Infrastructure Industry Training Package Companion Volume.

Unit Mapping Information

RIICRC202A Install signs

Approved Page 3 of 4

Links

Companion Volume implementation guides are found in VETNet - https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272

Approved Page 4 of 4