

# **RIIOGD204D Perform rig floor operations**

Release: 2



# **RIIOGD204D Perform rig floor operations**

## **Modification History**

Release	Comment
1	This unit replaces RIIOGD204 Perform rig floor operations
2	Required frequency and volume of evidence amended in Performance evidence.  Substantial amendments made in Assessment Conditions field, including: references to Industry Sectors, assessor and subject matter expert experience requirements, how assessment should be conducted and what it should confirm.

## **Application**

This unit describes a participant's skills and knowledge required to perform rig floor operations in Drilling.

This unit is appropriate for those working in assistant roles.

Licensing, legislative, regulatory and certification requirements that apply to this unit can vary between states, territories, and industry sectors. Relevant information must be sourced prior to application of the unit.

#### **Unit Sector**

Drilling

Approved Page 2 of 5

# **Elements and Performance Criteria**

	·			
1. Plan and prepare equipment	1.1 Access, interpret and apply rig floor operations documentation and ensure the work activity is compliant			
	1.2 Obtain, read, interpret, clarify and confirm work requirements			
	1.3 Identify and address potential risks, hazards and environmental issues and implement control measures			
	1.4 Select the personal protective equipment appropriate for the work activity			
	1.5 Conform to safe working practices and current legislative and operational requirements			
	1.6 Resolve coordination requirements with others at the site prior to commencing and during work activities			
	1.7 Confirm availability of required quantities and type of consumables			
	1.8 Identify errors, omissions and shortages and take appropriate remedial action within functional responsibility			
2. Select handling equipment	2.1 Identify and select equipment appropriate for the work to be performed and conforming to operational requirements			
	2.2 Confirm equipment is functional and fit for the purpose and the environment in which it will be used			
	2.3 Identify faults in the equipment and take appropriate remedial action taken within functional responsibility			
3. Handle tubulars and equipment	3.1 Position tubulars and equipment according to operational requirements			
	3.2 Make and break connections safely			
	3.3 Identify faults and defects accurately and take appropriate remedial action within functional responsibility			
	3.4 Handle equipment using safe lifting and handling techniques			
	3.5 Record data accurately at appropriate times and frequencies			
4. Prepare and run drill	4.1 Obtain and wear personal protective equipment, appropriate to task			
	4.2 Measure and record all down hole tools and pipe to assist driller			
	4.3 Convey pipe and tools to drill floor with protectors fitted and in accordance with company safety operating procedures			
	4.4 Check tongs and slip dies for cleanliness and sharpness and secure long lines			

Approved Page 3 of 5

	4.5	Inspect, service and operate manual slips correctly	
	4.6	Operate make-up and break-out manual tongs correctly	
	4.7 with o	Move drill floor drilling tools and equipment in accordance perating procedures	
	4.8	Apply correct manual handling techniques	
	4.9	Conduct thread cleaning, inspection and lubrication safely	
	4.10 tongs,	Make up and run drill string, applying correct use of chain safety clamps, rig tongs, slips and elevators	
5. Prepare, run and	5.1	Prepare casing in accordance with rig operating procedures	
cement casing	5.2 manufa	Prepare shoe joints in accordance with company and acturer's requirements	
	5.3	Prepare well heads/casing hangers	
	5.4	Prepare running tools and cementing equipment	
	5.5	Check lifting appliances, identify and report faults	
	5.6	Check and prepare handling equipment	
	5.7	Prepare casing centralisers correctly	
	5.8	Prepare and install guide frames as required	
	5.9 control	Prepare appropriate well control equipment and mitigation equipment in accordance with site requirements	
	5.10	Run casing in correct sequence	
	5.11	Fill casing safely	
	5.12	Connect appropriate cement line as per company procedure	
	5.13	Carry out cementing room duties while mixing	
	5.14 cemen	Assist as directed in preparing, running and cementing of ting casings	
6. Run cement stinger	6.1	Land casing at appropriate joint	
assembly (non standard)	6.2	Assemble appropriate equipment to run cement stinger	
(non-standard)	6.3 operati	Run drill pipe stringer inside casing as per rig specific ing procedure	
7. Assist in preparation and running	7.1 Prepare running BOP equipment in accordance with rig operating procedures		
of blow out prevention (BOP) stack, riser and	7.2	Position BOP over the wellhead using the appropriate system	
diverter package	7.3	Assemble and check riser running equipment	
	7.4	Assemble and check appropriate pressure test caps	
	7.5	Assemble and check appropriate handling equipment	
L	<u> </u>		

Approved Page 4 of 5

	7.6	Assemble and check riser angle beacon and hole
8. Examine and	8.1	Read, interpret and apply lubrication schedules
service drill floor equipment	8.2 manuf	Carry out lubrication in accordance with company and acturer's requirements
	8.3 applica	Identify and use correct types and quantities of lubricants for ations
	_	Check drawworks, rotary table, swivel, all valves, including ipe and choke and kill valves, wirelines and hoists and identify, and rectify faults as appropriate
9. Maintain a high	9.1	Maintain drill floor and equipment to company standard
standard of rig husbandry	9.2 correct	Keep tools and portable equipment clean, well maintained and ly stowed
	9.3 manuf	Seal and stow flammable substances according to acturer's and statutory requirements
	9.4	Keep covers and gratings in place, except when in use
	9.5	Maintain tongs, slips and dies in a clean and sharp condition
	9.6	Maintain non skid surfaces clean and free from oil and grease

#### **Foundation Skills**

Foundation skills essential to performance are explicit in the performance criteria of this unit. Further information is available in the Resources and Infrastructure Industry Training Package Companion Volume.

## **Unit Mapping Information**

RIIOGD203A Perform rig floor operations

#### Links

SkillsDMC RII Companion Volumes - http://www.skillsdmc.com.au/

Approved Page 5 of 5