

Australian Government

Department of Education, Employment and Workplace Relations

RIICRM207A Install raised pavement markers

Release: 1



RIICRM207A Install raised pavement markers

Modification History

Not applicable.

Unit Descriptor

This unit covers the installation of raised pavement markers in the civil construction industry. It includes planning and preparing, preparing surface and set out, preparing marking materials, applying raised pavement markers, measuring work, and cleaning up. Licensing, legislative, regulatory and certification requirements that apply to this unit can vary between states, territories, and industry sectors. Relevant information must be sourced prior to application of the unit.

Application of the Unit

This unit is appropriate for those working in an assistant role at worksites within:

Civil construction

Licensing/Regulatory Information

Refer to Unit Descriptor.

Pre-Requisites

Not applicable.

Employability Skills Information

This unit contains employability skills.

Elements and Performance Criteria Pre-Content

| Elements describe the essential outcomes of a unit of competency. Performance criteria describe the performance needed to demonstrate achievement of the element. Where bold italicised text is used, further information is detailed in required skills and knowledge section and the range statement. Assessment of performance is to be consisted with the evidence guide. | the |
|---|-----|
|---|-----|

| Elements and | Performance | Criteria |
|---------------------|-------------|----------|
|---------------------|-------------|----------|

| ELEMENT | PERFORMANCE CRITERIA |
|---|---|
| 1. Plan and prepare | 1.1. Access, interpret and apply <i>compliance</i> <i>documentation</i> relevant to the work activity 1.2. Obtain and confirm <i>safety requirements</i> from the <i>site</i> safety plan and organisational policies and procedures, and apply to the allotted task |
| | 1.3. Identify, obtain and implement <i>signage</i> <i>requirements</i> from the project <i>traffic</i> management plan |
| | 1.4. Select plant, <i>tools and equipment</i> to carry out tasks consistent with the requirements of the job, check for serviceability and rectify or report any faults |
| | 1.5. Identify <i>environmental protection</i> <i>requirements</i> from the project environmental management plan, and confirm and apply to the allotted task |
| 2. Prepare surface and set out | 2.1. Clear <i>area</i> of dirt, debris and other contaminants |
| | 2.2. Identify <i>location</i> for <i>raised pavement</i> <i>markers</i> and position to control point requirements or specifications 2.3. Remove defective raised pavement markers |
| | where required |
| | 2.4. Prime marked location for raised pavement markers in readiness for road marking application |
| 3. Prepare marking materials | 3.1. Mix or prepare marking material in accordance with manufacturer's and job specifications |
| | 3.2. Adjust additives and consistency of material to allow easy application and appropriate curing time |
| | 3.3. Transfer marking material carefully to applicator container |
| Apply raised pavement markers | 4.1.Select equipment relevant to the task and prepare for operation 4.2 Use equipment with the correct movement |
| | 4.2. Use equipment with the correct movement and pressure4.3. Apply material to job specification |

| | 4.4. Identify and correct defects with the material4.5. Maintain equipment in accordance with manufacturer's specifications |
|-----------------|---|
| 5. Measure work | 5.1. Assess, record and report work to comply with job specification5.2. Calculate and quantify amount of raised pavement markers completed5.3. Identify and report non conforming work |
| 6. Clean up | 6.1. Clear work area and dispose of or recycle <i>materials</i> in accordance with project environmental management plan 6.2. Clean, check, maintain and store plant, tools and equipment |

Required Skills and Knowledge

This section describes the skills and knowledge required for this unit.

Required skills

Specific skills are required to achieve the Performance Criteria of this unit, particularly for its application in the various circumstances in which this unit may be used. This includes the ability to carry out the following, as required to install raised pavement markers:

- apply legislative, organisation and site requirements and procedures for installation of raised pavement markers
- organise work activities
- select and use relevant tools and equipment safely
- identify and report on hazards related to the worksite and work activity
- communicate effectively to receive and clarify work instructions

Required knowledge

Specific knowledge is required to achieve the Performance Criteria of this unit, particularly for its application in the various circumstances in which this unit may be used. This includes knowledge of the following, as required to install raised pavement markers:

- site and equipment safety requirements
- raised pavement marking activities and techniques
- road markings
- raised pavement markers
- equipment types, characteristics, technical capabilities and limitations
- operational, maintenance and basic diagnostic procedures
- site isolation and traffic control responsibilities and authorities
- processes for the calculation of marker requirements, placement rates and travel speed
- materials safety data sheets and materials handling methods
- project quality requirements
- civil construction terminology
- JSAs/safe work method statements

Evidence Guide

The evidence guide provides advice on assessment and must be read in conjunction with the performance criteria, required skills and knowledge, range statement and the Assessment Guidelines for the Training Package.

| | 1 |
|---|--|
| Overview of assessment | |
| Critical aspects for assessment and evidence required to demonstrate competency in this unit | The evidence required to demonstrate competency in this unit must be relevant to worksite operations and satisfy all of the requirements of the performance criteria, required skills and knowledge and the range statement of this unit and include evidence of the following: |
| | • knowledge of the requirements, procedures and instructions for installing raised pavement markers |
| | • implementation of requirements, procedures and techniques for the safe, effective and efficient completion of installation of raised pavement markers |
| | • working with others to undertake and complete the installation of raised pavement markers that meets all of the required outcomes |
| | • consistent timely completion of the installation of raised pavement markers that safely, effectively and efficiently meet the required outcomes |
| | • installation of 200 permanent reflective or non reflective raised pavement markers on the various line configurations |
| Context of and specific resources for assessment | • This unit must be assessed in the context of the work environment. Where personal safety or environmental damage are limiting factors, assessment may occur in a simulated environment provided it is realistic and sufficiently rigorous to cover all aspects of workplace performance, including task skills, task management skills, contingency management skills and job role environment skills. |
| | Assessment of this competency requires typical resources normally used in a resources and infrastructure sector environment. Selection and use of resources for particular worksites may differ due to the site circumstances. The assessment environment should not |

| | disadvantage the participant. For example, language, literacy and numeracy demands of assessment should not be greater than those required on the job. Customisation of assessment and delivery environment to sensitively accommodate cultural diversity. Aboriginal people and other people from a non English speaking background may have second language issues. Where applicable, physical resources should include equipment modified for people with disabilities. Access must be provided to appropriate learning and/or assessment support when required. |
|-------------------------------------|--|
| Method of assessment | This unit may be assessed in a holistic way with other units of competency. The assessment strategy for this unit must verify required knowledge and skill and practical application using more than one of the following assessment methods: |
| | written and/or oral assessment of the candidate's required knowledge observed, documented and/or first hand testimonial evidence of the candidate's: implementation of appropriate requirement, procedures and techniques for the safe, effective and efficient achievement of required outcomes consistent achievement of required outcomes |
| | first hand testimonial evidence of the candidate's: working with others to undertake and complete the installation of raised pavement markers |
| Guidance information for assessment | Consult the SkillsDMC User Guide for further information on assessment including access and equity issues. |

Range Statement

The range statement relates to the unit of competency as a whole. It allows for different work environments and situations that may affect performance. Bold italicised wording, if used in the performance criteria, is detailed below. Essential operating conditions that may be present with training and assessment (depending on the work situation, needs of the candidate, accessibility of the item, and local industry and regional contexts) may also be included.

| Relevant compliance documentation may include: | legislative, organisational and site requirements and procedures manufacturer's guidelines and specifications Australian standards Employment and workplace relations legislation Equal Employment Opportunity and Disability Discrimination legislation |
|---|--|
| Safety requirements may include: | OHS requirements in accordance with state or territory legislation and regulations, organisational safety policies and procedures, and project safety plan, including protective clothing and equipment, use of tools and equipment, workplace environment and safety, handling of materials, use of fire fighting equipment, use of First Aid equipment, hazard control and hazardous materials and substances |
| | • safe parking practices including ensuring access ways are clear, equipment/machinery is away from overhangs and refuelling sites, safe distance are kept from excavations, and areas secured from unauthorised access or movement |
| | safe operating procedures including recognising and preventing hazards associated with uneven/unstable terrain, trees, pits, poles, trip hazards, dirt mounds, overhead service lines, bridges, surrounding buildings, obstructions, structures, facilities, dangerous materials, recently filled trenches, other machines, personnel, traffic control, working in proximity to others, worksite visitors and the public |
| | recognising hazards and risks including uneven/unstable terrain, trees, fires, overhead and underground services, bridges, buildings, excavations, traffic, embankments, cuttings, |

| | structures and hazardous materials emergency procedures related to equipment operation including emergency shutdown and stopping, extinguishing equipment fires, organisational First Aid requirements and evacuation |
|---|--|
| Site locations may include: | roads bridges footpaths sports courts and fields car parks cycle paths factories airports walking tracks and similar sealed surfaces |
| Signage requirements may include: | escort vehicle highway traffic signs site safety signage temporary signage for the benefit of motorists and pedestrians traffic conditions signage |
| Traffic conditions may include: | congested urban environments low traffic rural areas off-road un-trafficked areas buildings parking sites pedestrian areas highways |
| Tools and equipment may include: | walk behind pedestrian machines, hand held burners two pack applicators maintenance tools |
| Area may include: | chip seal asphalt concrete new or existing work |
| Location may include: | transverse and longitudinal markings which may include: barrier lines (one direction and both directions) edge lines arrows |

| | shares |
|-----------------------------|---|
| | • shapes |
| | • symbols |
| | • lane lines (broken and unbroken) |
| | • separation lines (broken and unbroken) |
| | continuity lines |
| | • turn lines |
| | • outline |
| | • stop lines |
| | holding lines |
| | • stop and give way lines |
| | pedestrian crosswalk lines |
| | diagonal and chevron markings |
| | • numerals |
| | • parking areas |
| | kerb markings |
| Raised pavement markers may | • permanent |
| include: | • temporary |
| | • reflective |
| | non reflective |
| | detour reflective |
| Materials may include: | hot melt adhesives |
| | burn on pads |
| | • two pack epoxies |

Unit Sector(s)

Road Marking

Competency field

Refer to Unit Sector(s).

Co-requisite units

Not applicable.