



**Australian Government**

# **TLILIC0009 Licence to operate a portal boom crane**

**Release: 2**

# TLILIC0009 Licence to operate a portal boom crane

## Modification History

Release 2. This is the second release of this unit of competency in the TLI Transport and Logistics Training Package:

- Minor statement changes in unit Application
- Minor statement changes in Assessment Conditions.

Release 1. This is the first release of this unit of competency in the TLI Transport and Logistics Training Package.

## Application

This unit specifies the skills and knowledge required to operate a portal boom crane safely. Competence in this unit, does not in itself result in a High-Risk Work Licence (HRWL) to operate this plant.

Portal boom crane means a boom crane or a jib crane that is mounted on a portal frame that, in turn, is supported on runways along which the crane travels.

A person undertaking this unit must hold:

- a current HRWL to perform dogging or a certification for a specific VET course for HRWL to perform dogging.

A person performing this work is required to hold a portal boom crane HRWL.

This unit requires a person operating a portal crane to:

- plan for the work/task
- prepare for the work/task
- perform work/task
- pack up

## Licensing/Regulatory Information

Legislative and regulatory requirements are applicable to this unit of competency.

This unit is based on the licensing requirements of Part 4.5 of the Model Work Health and Safety (WHS) Regulations and meets Commonwealth, State and Territory HRWL requirements.

The National Assessment Instrument (NAI) is the mandated assessment for the HRWL to operate the relevant licencing class as detailed in this unit.

## Pre-requisite Unit

Not applicable

## Competency Field

LIC - Licencing Units

## Unit Sector

Not applicable

## Elements and Performance Criteria

### ELEMENTS

Elements describe the essential outcomes.

#### 1 Plan work/task

### PERFORMANCE CRITERIA

Performance criteria describe the performance needed to demonstrate achievement of the element.

- 1.1 Task requirements are identified from work orders or equivalent and a lift plan is confirmed with associated personnel and a site inspection is conducted in accordance with workplace procedures
- 1.2 Work area operating surface is confirmed to determine the quality of ground suitability for operational use in accordance with workplace procedures
- 1.3 Portal boom crane rated capacity (RC) and the lifting gear Working Load Limit (WLL) are established for the load/s and work/task requirements in accordance with manufacturer requirements and workplace procedures
- 1.4 Appropriate paths for operating the portal boom crane and moving and placing load/s in work area are assessed and determined in accordance with workplace procedures
- 1.5 Relevant hazard identification and risk elimination/control measures are applied and advised to associated personnel in accordance with workplace procedures
- 1.6 Traffic management plan implementation is confirmed and followed in accordance with workplace procedures
- 1.7 Appropriate communication procedures are identified and tested with associated personnel in accordance with workplace procedures

- 1.8** All tasks are confirmed to ensure requirements for the relevant work area in accordance with a lift plan and workplace procedures
- 2 Prepare for work/task**
- 2.1** Consultation with workplace personnel is established and maintained to ensure all crane and lifting operations are clear and consistent with site requirements in accordance with a lift plan and workplace procedures
- 2.2** Risk control measures for hazards identified are checked for implementation in accordance with the lift plan and safe work procedures
- 2.3** Portal boom crane is accessed safely in accordance with manufacturer requirements and safe work procedures
- 2.4** Pre-start portal boom crane checks are carried out and any damage and defects are reported, recorded and appropriate action is taken in accordance with legislative responsibilities and manufacturer requirements
- 2.5** Portal boom crane is set up correctly with any lifting gear as per the lift plan in accordance with relevant manufacturer requirements including load chart/s and safe work procedures
- 2.6** Boom/jib and lifting gear are set up and rigged as required in accordance with specific manufacturer requirements and safe work procedures
- 2.7** Operational checks are carried out and any damage and defects are reported, recorded and appropriate action is taken in accordance with manufacturer requirements and safe work procedures
- 2.8** Crane logbook is checked to confirm current compliance, is correct for the crane type, is completed and signed and required rectifications have been signed off in accordance with manufacturer requirements and safe work procedures
- 2.9** Weather and work environment conditions are assessed to determine any impact on portal boom crane operations in accordance with manufacturer requirements and safe work procedures

### **3 Perform work/task**

- 3.1** Lifts are determined within the RC of the portal boom crane in accordance with the load chart/s and lift plan
- 3.2** Boom/jib and hook block is safely positioned over the load following directions from associated personnel in accordance with the lift plan and safe work procedures
- 3.3** Hook including any lifting gear, where required are connected to the load and used safely in accordance with the lift plan, safe work procedures and manufacturer requirements
- 3.4** Test lift is carried out in accordance with dogging and safe work procedures
- 3.5** Loads are transferred using relevant crane movements and tag lines as required, in accordance with lift plan and safe work procedures
- 3.6** Load and crane movement is monitored constantly and crane is operated safely in accordance with lift plan and safe work procedures
- 3.7** All required communication signals are correctly interpreted and followed whilst crane is operated in accordance with the lift plan and safe work procedures
- 3.8** Load is lowered and landed safely in accordance with lift plan and safe work procedures
- 3.9** Lifting gear is disconnected from load and crane is positioned safely and efficiently for next task in accordance with lift plan and safe work procedures

### **4 Pack up**

- 4.1** Crane boom/jib, lifting gear and associated equipment is stowed and secured as required in accordance with manufacturer requirements and safe work procedures
- 4.2** Relevant motion locks and brakes are applied as required in accordance with manufacturer requirements and safe work procedures

- 4.3 Crane is shut down and secured to prevent unauthorised access/use in accordance with safe work procedures
- 4.4 Shut down crane checks are carried out in accordance with safe work procedures and manufacturer requirements

## Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency

## Range of Conditions

Range is restricted to essential operating conditions and any other variables essential to the work environment.

Non -essential conditions may be found in the Companion Volume Implementation Guide.

## Unit Mapping Information

This unit replaces and is equivalent to TLILIC3007 Licence to operate a portal boom crane

## Links

Companion Volume Implementation Guide -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=df441c6e-213d-43e3-874c-0b3f7036d851>