



Australian Government

UEERA0099 Install, commission, service and maintain air conditioning systems

Release:

UEERA0099 Install, commission, service and maintain air conditioning systems

Modification History

Release 1. This is the first release of this unit of competency in the UEE Electrotechnology Training Package.

Application

This unit involves the skills and knowledge required to safely and effectively install, commission, service and maintain air conditioning systems.

It includes the ability to source relevant data and schematics; install components, pipe work, accessories and controls to create a functional air conditioning system. It covers selecting installing and replacing cables within air conditioning equipment operating at voltages up to 500 volt (V) alternating current (a.c.), according to relevant State/Territory legislation and regulations. Commissioning the system to ensure it operates at the specified design conditions, locating and rectifying faults and carrying out routine maintenance procedures.

The skills and knowledge of this unit of competency will be applied by refrigeration and air conditioning technicians during the installation, commissioning and servicing of air conditioning systems.

To undertake this unit, the learner must have a current Trainee Refrigerant Handling Licence as it includes work on refrigeration and air conditioning equipment that carries the risk of a fluorocarbon refrigerant being emitted.

The skills and knowledge described in this unit require a national Refrigerant Handling Licence as it includes work on refrigeration and air conditioning equipment that carries the risk of a fluorocarbon refrigerant being emitted while decanting the refrigerant or manufacturing, installing, commissioning, servicing, maintaining or decommissioning refrigeration and air conditioning equipment.

The skills and knowledge described in this unit require a licence or permit to practice in the workplace where work is carried out on electrical installations which are designed to operate at voltages greater than 50 V alternating current (a.c.) or 120 V direct current (d.c.).

Competency development activities in this unit are subject to regulations directly related to licensing. Where a licence or permit to practice is not held, skills and knowledge described in this unit require a relevant contract of training, such as an Australian Apprenticeship.

Additional and/or other conditions may apply in some jurisdictions subject to regulations related to refrigeration, air conditioning and electrical work. Practice in the workplace and during training is also subject to work health and safety (WHS)/occupational health and safety (OHS) regulations.

Permits may also be required for some work environments, such as confined spaces, working aloft, near live electrical apparatus and site rehabilitation.

Pre-requisite Unit

UEECD0007 Apply work health and safety regulations, codes and practices in the workplace

UEECD0051 Use drawings, diagrams, schedules, standards, codes and specifications

UEERA0059 Prepare and connect refrigerant tubing and fittings

UEERA0035 Establish the basic operating conditions of air conditioning systems

UEERA0036 Establish the basic operating conditions of vapour compression systems

UEERA0050 Install refrigerant pipe work, flow controls and accessories

UEERA0062 Recover and charge refrigerants

UEERL0004 Disconnect - reconnect electrical equipment connected to low voltage (LV) installation wiring

UEERL0005 Locate and rectify faults in low voltage (LV) electrical equipment using set procedures

Competency Field

Refrigeration and air-conditioning

Unit Sector

Electrotechnology

Elements and Performance Criteria

ELEMENTS

Elements describe the essential outcomes.

1 Prepare to install air conditioning systems

PERFORMANCE CRITERIA

Performance criteria describe the performance needed to demonstrate achievement of the element.

- 1.1** WHS/OHS risk control measures and procedures for carrying out the work are obtained and implemented in accordance with workplace procedures
- 1.2** Work details are determined from documentation and/or supervisor to establish scope of work to be completed in accordance with workplace procedures
- 1.3** Components, piping, accessories, controls and consumables for the installation work are obtained and

- checked against job requirements in accordance with industry standards and codes of practice
- 1.4** Tools, equipment and testing devices to complete work are obtained in accordance with workplace procedures and checked for operational safety in accordance with workplace procedures
- 2 Select, install, replace and terminate low voltage (LV) and extra-low voltage (ELV) cables within air conditioning equipment.**
- 2.1** Cable conductor sizes are selected to meet the equipment manufacturer specifications, current-carrying capacity requirements
- 2.2** Reasons for selections made are documented in accordance with established procedures
- 2.3** Cables are installed and replaced to comply with technical standards, job specifications and relevant State/Territory legislation and regulations and with sufficient access to affect terminations
- 2.4** Cables and conductors are terminated at accessories in accordance with manufacturer specifications and regulatory requirements
- 2.5** Safety inspection of installed cables and testing of installed circuits are undertaken and any defects are rectified
- 2.6** 'As-installed' cables/wiring are documented and appropriate person/s notified in accordance with established procedures
- 3 Install non-ducted split air conditioning systems**
- 3.1** All required major components are securely mounted in the locations identified by the documentation or the supervisor in accordance with workplace procedures
- 3.2** Refrigerant pipe work and associated components are installed according to specifications ensuring all connections and tube cleanliness are in accordance with requirements and workplace procedures

- 3.3** Pressure testing of the installed components and pipe work is conducted to the required level for the type of refrigerant being used in accordance relevant codes of practice and industry standards
 - 3.4** Leaks are located and rectified employing appropriate methods in accordance with relevant codes of practice and industry standards
 - 3.5** Air conditioning system is evacuated to remove moisture and other contaminants in accordance with relevant codes of practice and industry standards
 - 3.6** Vacuum drop test is carried out to verify all moisture and other contaminants have been removed from the system in accordance with relevant codes of practice and industry standards
 - 3.7** Power and control circuit wiring is checked to ensure it conforms to circuit diagram specifications and system is electrically safe to energise in accordance with relevant codes of practice and industry standards
- 4 Install ducted split air conditioning systems**
 - 4.1** Major components are securely mounted in the locations identified by the documentation or the supervisor in accordance with workplace procedures
 - 4.2** Flexible ductwork, associated fittings and flow control devices are installed according to specifications ensuring all connections are in accordance with workplace procedures and industry standards
 - 4.3** Refrigerant pipework and associated components are installed ensuring all connections and tube cleanliness is maintained at all times in accordance with workplace procedures and manufacturer specifications
 - 4.4** Pressure testing of the installed components and pipe work is conducted to the required level for the type of refrigerant being used in accordance with relevant industry standards and workplace procedures
 - 4.5** Leaks are located and rectified employing appropriate methods in accordance with industry standards and codes of practices

- | | | |
|--|------------|---|
| | 4.6 | Air conditioning system is evacuated to remove moisture and other contaminants in accordance with industry standards, relevant codes of practices and workplace procedures |
| | 4.7 | Vacuum drop test is carried out to verify all moisture and other contaminants have been removed from the system in accordance with industry standards, relevant codes of practices and workplace procedures |
| | 4.8 | Power and control circuit wiring is checked to ensure it conforms to circuit diagram specifications and system is electrically safe to energise in accordance with industry standards, relevant codes of practices and workplace procedures |
| 5 Commission air conditioning systems | 5.1 | Air conditioning system is charged with the appropriate type and quantity of refrigerant in accordance with industry standards, relevant codes of practices and workplace procedures |
| | 5.2 | Measurements are obtained and recorded to confirm that the refrigerant charge is optimal in accordance with the system's design and manufacturer specifications |
| | 5.3 | Control devices installed in the air stream for air flow quantity and distribution control are adjusted in accordance with the system's design and manufacturer specifications |
| | 5.4 | Measurements are obtained and recorded to confirm that air flow quantities and distribution is optimal in accordance with the system's design and manufacturer specifications |
| 6 Locate and rectify faults and carry out maintenance on air conditioning systems | 6.1 | Fault diagnosis is carried out in accordance with industry standards, relevant codes of practices and workplace procedures |
| | 6.2 | Fault-finding and rectification processes are carried out effectively without damage to the system and components in accordance with relevant codes of practice, industry standards and workplace procedures |

- | | | |
|--|------------|---|
| | 6.3 | System is returned to an operational state in accordance with workplace procedures and manufacturer specifications |
| | 6.4 | Components that require routine maintenance are identified and regularly maintained in accordance with relevant timeframes, industry standards and workplace procedures |
| 7 Complete work and report activities | 7.1 | WHS/OHS risk control measures continue to be applied in accordance with workplace procedures |
| | 7.2 | Worksite and equipment are cleaned and made safe in accordance with workplace procedures |
| | 7.3 | Refrigerant usage is recorded in accordance with relevant industry regulations and codes of practice |
| | 7.4 | Supervisor is notified of task completion in accordance with workplace procedures |

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Range of Conditions

Range is restricted to essential operating conditions and any other variables essential to the work environment.

Non-essential conditions may be found in the UEE Electrotechnology Training Package Companion Volume Implementation Guide.

Selecting, installing and terminating LV cables within air conditioning equipment must include the following applications:

- replacing damaged cables within air conditioning equipment operating at voltages up to 500 V a.c., according to manufacturer's advice and relevant State/Territory legislation and regulations
- types of cables required – circular thermoplastic sheathed (TPS), flat TPS,

Selecting, installing, replacing and terminating ELV cables on air conditioning installations must include the following applications and cable types	- flexible cables and thermoplastic insulated (TPI) - interconnecting and controller cables between the sensor/s, controller/s, indoor and outdoor units of residential and small commercial air conditioning equipment. - types of cable required – data and shielded cables
Installing, commissioning, servicing and maintaining split air conditioning systems must include at least one of the following:	- high wall split air conditioning system - ceiling cassette split air conditioning system - ceiling suspended split air conditioning system
Installing, commissioning, servicing and maintaining ducted air conditioning systems must include at least one of the following:	- ducted split air conditioning system - ducted package air conditioning system
Electrical supply to the installed air conditioning system must include one of the following:	- single phase 230 V - three phase 400 V
Fault finding and rectification of an air conditioning system must include at least two of the following mechanical faults:	- incorrect refrigerant charge - restriction within refrigerant circuit, including filter drier and refrigerant metering device (RMD) - non-condensables - incorrect low side superheat - incorrect high side sub-cooling - component failure, including compressor not pumping
Fault finding and rectification of an air conditioning system must include at least two of the following electrical faults:	- open circuit, including load, conductor and/or control - incorrect circuit wiring - earthing short, including load circuit has connected with casing and/or frame - shunted short, including load is internally shorted causing lower resistance - incorrect phase rotation
Carrying out maintenance on air conditioning systems must include all of the following	- high wall split air conditioning system - ducted split air conditioning system - ducted package unit air conditioning system

Unit Mapping Information

This unit replaces and is equivalent to UEERA0051 Install, commission, service and maintain air

conditioning systems.

Links

Companion Volume implementation guides are found in VETNet - -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=b8a8f136-5421-4ce1-92e0-2b50341431b6>