



Australian Government

UEGNSG053 Install and commission stationary gas fuelled turbine engines

Release: 1

UEGNSG053 Install and commission stationary gas fuelled turbine engines

Modification History

Release 1. This is the first release of this unit of competency in the UEG Gas Industry Training Package.

Application

This unit involves the skills and knowledge required to install and commission stationary gas fuelled turbine engines, up to a capacity of 5 gigajoule per hour (GJ/hr) (1,300 kilowatt).

It includes installing and commissioning stationary gas fuelled turbine engines to installation industry standards matching the plant/equipment, location, components and fuel train pipework to given specifications. Commissioning gas fuelled turbine engine plant and equipment includes pre-commissioning tests, start up, adjusting components and controls to safe and efficient operation, and completing all necessary installation and commissioning documentation.

The application of the skills and knowledge described in this unit may require a licence or permit to practice in the workplace.

Other conditions may apply under state and territory legislative and regulatory licensing requirements which must be confirmed prior to commencing this unit.

Pre-requisite Unit

CPCWHS1001 Prepare to work safely in the construction industry

HLTAID009 Provide cardiopulmonary resuscitation

Competency Field

Gas Transmission

Unit Sector

Gas Industry

Elements and Performance Criteria

ELEMENTS

Elements describe the

PERFORMANCE CRITERIA

Performance criteria describe the performance needed to

essential outcomes.

demonstrate achievement of the element.

1 Prepare to install stationary gas fuelled turbine engine

- 1.1** Workplace safety, environmental and sustainable energy practices for the site are identified, obtained and understood
- 1.2** Job requirements are obtained and interpreted from plans, specifications and instructions
- 1.3** Relevant job requirements and workplace procedures for work activities are discussed with relevant person/s, including third parties, to determine and confirm work schedule and respective responsibilities
- 1.4** Hazards are identified, workplace safety and environmental risks are assessed, and control measures are prioritised, implemented and monitored in accordance with workplace procedures
- 1.5** Scope of responsibility under the relevant job requirements, including all work permits and/or relevant notifications, is determined and confirmed to access the services and perform work in accordance with job requirements and workplace procedures
- 1.6** Gas fuelled turbine engine plant, equipment and component specifications and manufacturer manuals are obtained for planned work activity
- 1.7** Locations of plant, equipment, fuel train pipework and components are planned within the constraints of worksite, specifications and requirements
- 1.8** Gas fuelled turbine engine materials needed for the installation work are obtained in accordance with design specification and workplace procedures
- 1.9** Equipment, tools and personal protective equipment (PPE) needed to carry out work activities are identified, obtained and checked for correct operation and safety in accordance with workplace procedures and manufacturer instructions
- 1.10** Materials, plans, diagrams, drawings and resources required for work are confirmed and obtained in accordance with workplace procedures

2 Install stationary gas fuelled turbine engine

- 2.1** Workplace safety and environmental risk control measures, schedule of work and workplace procedures for

carrying out work are followed

- 2.2 Relevant gas regulator and code of practice recording, and reporting requirements are undertaken at appropriate times throughout the work sequence
- 2.3 Gas and electrical circuits/machines/plant are isolated in accordance workplace safety requirements and workplace procedures
- 2.4 Stationary gas fuelled turbine engine components, fuel train and associated pipework and flue/exhaust systems are installed in accordance with design specification, industry technical standards and regulatory requirements, with sufficient access to affect terminations, adjustment and maintenance
- 2.5 Ventilation systems are installed in accordance with design specification
- 2.6 Electrical components, wiring enclosures and wiring terminations are installed in accordance with design and manufacturer specifications, and functional and regulatory requirements
- 2.7 Compliance and safety inspections of installed turbine engine, equipment, pipework, components and accessories are undertaken, and defects are rectified
- 2.8 Work is completed within agreed timeframe and to industry standards in accordance with job requirements and workplace procedures
- 2.9 Unplanned events are referred to the relevant person/s for directions in accordance with workplace procedures

3 Commission stationary gas fuelled turbine engine

- 3.1 Workplace safety risk control measures and workplace procedures for carrying out work activities are followed
- 3.2 Relevant gas regulator and code of practice recording, and reporting requirements are satisfied at appropriate times throughout the work sequence
- 3.3 Gas and electrical safety checks and isolation workplace procedures and purging are completed and recorded to manufacturer and relevant authority requirements before testing and commissioning are commenced

- 3.4 Operational parameters of individual components are tested and adjusted to conform with specifications
 - 3.5 Turbine engine operations are tested, first without and then with fuel, adjustments are completed, as necessary, and results recorded in accordance with approving authority requirements
 - 3.6 Exhaust gases are analysed in accordance with relevant industry practice and authority requirements
 - 3.7 Unplanned situations are responded to in accordance with workplace procedures in a manner that minimises risk to personnel and equipment safely and with the approval of an authorised person
 - 3.8 Commissioning is conducted without waste of materials or damage to apparatus and the surrounding environment or services using sustainable energy practices
- 4 Complete and report installation and commissioning activities**
- 4.1 Workplace safety work completion risk control measures and workplace procedures are followed
 - 4.2 Final check of the installed gas fuelled turbine engine is made to verify compliance with job requirements, certification required by relevant gas authorities and industry standards
 - 4.3 Incidents and injuries are reported and followed up as required in accordance with workplace procedures
 - 4.4 Tools and equipment are cleaned, checked, serviced and stored in accordance with manufacturer recommendations and workplace procedures
 - 4.5 Worksite is cleaned/tidied and made safe in accordance with workplace procedures
 - 4.6 ‘As-installed’ gas fuelled turbine engine equipment, components, pipework, flue/exhaust systems and accessories are documented, accessed and appropriate person/s notified in accordance with workplace procedures

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of

competency.

Range of Conditions

Range is restricted to essential operating conditions and any other variables essential to the work environment.

Non-essential conditions may be found in the UEG Gas Industry Training Package Companion Volume Implementation Guide.

Unit Mapping Information

This unit replaces and is equivalent to UEGNSG138 Install and commission stationary gas fuelled turbine engines.

Links

Companion Volume Implementation Guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=6a6c032e-ffcb-4f3d-8063-415efbd261e8>