



Australian Government

UEGNSG208 Construct and lay large copper gas distribution pipelines

Release: 1

UEGNSG208 Construct and lay large copper gas distribution pipelines

Modification History

Release 1. This is the first release of this unit of competency in the UEG Gas Industry Training Package.

Application

This unit involves the skills and knowledge required to construct and lay copper gas distribution pipelines and services above 20 mm diameter.

It includes using relevant tools and equipment, completing necessary documentation, and working safely in accordance with workplace procedures and relevant legislative, standard and code requirements.

The application of the skills and knowledge described in this unit may require a licence/registration to practise in the workplace.

Other conditions may apply under state and territory legislative and regulatory licensing requirements which must be confirmed prior to commencing this unit.

Pre-requisite Unit

Not applicable

Competency Field

Gas Distribution

Unit Sector

Gas Industry

Elements and Performance Criteria

ELEMENTS

Elements describe the essential outcomes.

1 Prepare to construct and lay large copper gas

PERFORMANCE CRITERIA

Performance criteria describe the performance needed to demonstrate achievement of the element.

1.1 Work health and safety (WHS)/occupational health and safety (OHS) workplace procedures and environmental

- distribution pipelines** measures for the site are identified, obtained and applied
- 1.2** Job requirements and workplace procedures for the site are discussed with relevant person/s to confirm work schedule
 - 1.3** WHS/OHS, environmental and sustainable energy policies and procedures are obtained and applied
 - 1.4** Hazards are identified, WHS/OHS risks are assessed and control measures prioritised, implemented and monitored in accordance with workplace procedures
 - 1.5** Scope of work and level of responsibility under the relevant work permit and/or notification is confirmed with relevant person/s in accordance with job requirements and workplace procedures
 - 1.6** Equipment, plant, tools and personal protective equipment (PPE) required to construct and lay copper gas pipelines and services are identified, obtained and checked for correct operation and safety in accordance with workplace procedures
 - 1.7** Relevant person/s are consulted to ensure work is coordinated effectively with others involved
 - 1.8** Materials, plans, diagrams, drawings and resources required to construct and lay gas distribution pipelines are confirmed, scheduled and obtained in accordance with workplace procedures
 - 1.9** Safety and emergency procedures and responsibilities for an incident at the work site are checked and confirmed with relevant person/s
 - 1.10** Third-party issues are referred to relevant person/s in accordance with workplace procedures
 - 1.11** Site preparation, safety plan and work schedule are confirmed with relevant person/s in accordance with established procedures
- 2 Construct and lay large copper gas distribution pipelines**
- 2.1** WHS/OHS and environmental risk control measures, schedule of work and workplace procedures for carrying out work are followed
 - 2.2** Materials, tools, equipment and measuring devices required for the work are selected and used correctly and safely in accordance with manufacturer instructions and

workplace procedures

- 2.3 Hazardous activities are conducted safely in accordance with WHS/OHS workplace procedures and job instructions
- 2.4 Excavation bed/trench is prepared for laying of large pipe above 20 mm in diameter in accordance with relevant industry standards and workplace procedures
- 2.5 Construction and laying of copper gas pipelines and services are conducted in accordance with relevant industry standards and workplace procedures
- 2.6 Work is carried out to the required standard, without waste of materials or damage to apparatus, equipment, and the surrounding environment or services using sustainable energy principles
- 2.7 WHS/OHS risks, incidents and accidents are reported to authorised person/s for directions in accordance with workplace procedures
- 2.8 Unplanned events are referred to authorised person/s for directions are followed in accordance with workplace procedures
- 2.9 Quality and safety checks of work and testing of pipework is carried out in accordance with industry standards, work instructions and workplace procedures

3 Complete the work and relevant documentation

- 3.1 WHS/OHS and environmental risk control measures for work completion are followed
- 3.2 Relevant person/s are notified of work completion in accordance with workplace procedures
- 3.3 Tools, equipment and any surplus resources and materials are cleaned, checked and securely stored in accordance with workplace procedures
- 3.4 Work site is tidied and made safe in accordance with workplace procedures
- 3.5 Relevant documentation is completed and provided to appropriate person/s in accordance with workplace procedures

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Range of Conditions

Range is restricted to essential operating conditions and any other variables essential to the work environment.

Non-essential conditions may be found in the UEG Gas Industry Training Package Companion Volume Implementation Guide.

competency must be demonstrated by constructing and laying copper gas distribution pipelines and services above 20 mm diameter and include:

- laying and cutting pipes
- joining pipes and fittings
- installing the meter connection to the services users

Unit Mapping Information

This unit replaces and is equivalent to UEGNSG228 Construct and lay large copper gas distribution pipelines.

Links

Companion Volume Implementation Guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=6a6c032e-ffcb-4f3d-8063-415efbd261e8>