

UEPMNT414B Test and commission complex electrical equipment

Release: 1



UEPMNT414B Test and commission complex electrical equipment

Modification History

Not applicable.

Unit Descriptor

Unit Descriptor

1) Scope:

1.1) Descriptor

This unit deals with the skills and knowledge required to conduct testing and commissioning of complex and H.V. electrical wiring systems and equipment.

Application of the Unit

Application of the Unit 2)

This unit is intended to augment formally acquired competencies. It is suitable for employment-based programs under an approved contract of training.

Licensing/Regulatory Information

License to practice

3)

The skills and knowledge described in this unit may require an electrical licence to practise in the workplace. Practice in this unit is subject to regulations directly related to Occupational Health and Safety and where applicable contracts of training such as apprenticeships and the like.

Approved Page 2 of 14

Pre-Requisites

Prerequisite Unit(s) 4)

Competencies 4.1)

Granting of competency in this unit shall be made only after competency in the following unit(s) has/have been confirmed.

Where pre-requisite pathways have been identified. All competencies in the Common Unit Group must be have been completed.

Common Unit Group

Common Unit Group	
Unit Code	Unit Title
UEPMNT351B	Test and commission electrical equipment
UEENEEG108A	Trouble-shoot and repair faults in low voltage electrical apparatus and circuits
UEENEEE101A	Apply Occupational Health Safety regulations, codes and practices in the workplace
UEENEEE102A	Fabricate, dismantle, assemble of utilities industry components
UEENEEE104A	Solve problems in d.c. circuits
UEENEEE105A	Fix and secure electrotechnology equipment
UEENEEE107A	Use drawings, diagrams, schedules, standards, cords and specifications
UEENEEG006A	Solve problems in single and three phase low voltage machines
UEENEEG033A	Solve problems in single and three phase low voltage electrical apparatus and circuits
UEENEEG063A	Arrange circuits, control and protection for general electrical

installations

Solve problems in electromagnetic

Approved Page 3 of 14

UEENEEG101A

Prerequisite Unit(s) 4)

devices and related circuits

UEENEEG102A Solve problems in low voltage a.c.

circuits

UEENEEG106A Terminate cables, cords and

accessories for low voltage circuits

Literacy and numeracy skills

4.2)

Participants are best equipped to achieve this unit if they have reading, writing and numeracy skills indicated by the following levels. A description of what each level entails is provided in Section 2.3.1 Language, Literacy and Numeracy.

Reading 4 Writing 4 Numeracy 4

Employability Skills Information

5)

Employability Skills

The required outcomes described in this unit of competency contain applicable facets of Employability Skills. The Employability Skills Summary of the qualification in which this unit of competency is packaged will assist in identifying Employability Skill requirements.

Elements and Performance Criteria Pre-Content

6) Elements describe the essential outcomes of a competency standard unit

Performance Criteria describe the required performance needed to demonstrate achievement of the element. Assessment of performance is to be consistent with the Evidence Guide.

Approved Page 4 of 14

Elements and Performance Criteria

ELEMENT

PERFORMANCE CRITERIA

- 1 Plan and prepare for the work
- 1.1 Work requirements are identified from request/work orders or equivalent and clarified/confirmed with appropriate parties or by site inspection
- 1.2 Occupational Health and Safety standards, statutory requirements, relevant Australian standards, codes of practice, manufacturers' specifications, environmental requirements and enterprise procedures are identified, applied and monitored throughout the work procedure
- 1.3 Resources required to satisfy the work plan are identified, obtained and inspected for compliance with the job specifications
- 1.4 Relevant plans, drawings and texts are selected and interpreted in accordance with the work plan
- 1.5 Correct size, type and quantity of materials/components are determined, obtained and inspected for compliance with the job specifications
- 1.6 Work is planned in detail including sequencing and prioritising and considerations made, where appropriate, for the maintenance of plant security and capacity in accordance with system/site requirements
- 1.7 Co-ordination requirements, including requests for isolations where appropriate, are resolved with others involved, affected or required by the work
- 1.8 Potential hazards are identified and prevention and/or control measures are selected in accordance with the work plan and site procedures
- 1.9 Work area is prepared in accordance with work requirements and site procedures
- 1.10 Where appropriate, the teams and individuals roles and responsibilities within the team are

Approved Page 5 of 14

ELEMENT PERFORMANCE CRITERIA identified and, where required, assist in the provision of the on-the-job training Test wiring systems 2.1 Required isolations are confirmed where appropriate in accordance with site requirements 2.2 Wiring systems are tested using appropriate plans, drawings and texts in accordance with the work plan 2.3 Wiring systems are tested in conjunction with others involved in, or affected by, the work in accordance with the work plan 2.4 Wiring systems, including enclosures/ supports, are inspected prior to testing to ensure absence of any damage, defects and/or signs of deterioration in accordance with the work plan 2.5 Fixed wiring is tested as appropriate and results/observations are interpreted and documented to confirm compliance with job specifications Test the equipment 3.1 Required isolations are confirmed where appropriate in accordance with site requirements 3.2 Equipment is tested using appropriate plans, drawings and texts in accordance with the work plan 3.3 Equipment is tested in conjunction with other involved in, or affected by, the work in accordance with the work plan 3.4 Required test conditions are confirmed and the equipment is inspected to ensure absence of any damage, defects and/or signs of deterioration in accordance with the work plan 3.5 Equipment is tested using appropriate test techniques in accordance with the work plan 3.6 Equipment test results/observations are interpreted and documented to confirm compliance with job specifications

Approved Page 6 of 14

ELEMENT

PERFORMANCE CRITERIA

4	Commission the
	equipment

- 4.1 Required isolations are confirmed where appropriate in accordance with site requirements
- 4.2 Equipment is commissioned using appropriate plans, drawings and texts in accordance with the work plan
- 4.3 Equipment is commissioned in conjunction with others involved in, or affected by, the work in accordance with the work plan
- 4.4 Equipment is set up in accordance with operational requirements/manufacturer specifications
- 4.5 Testing and monitoring procedures are followed and results monitored, interpreted and documented to ensure equipment operates/functions within specifications
- 4.6 Equipment is commissioned with due regard being paid to plant security and capacity in accordance with the work plan
- 4.7 Final job inspection is carried out and permits relinquished as required in accordance with the work plan

5 Complete the work

- 5.1 Work is completed and appropriate personnel notified in accordance with site/enterprise requirements
- 5.2 Work area is cleared of waste, cleaned, restored and secured in accordance with site/enterprise procedures
- 5.3 Plant, tools and equipment are maintained and stored in accordance with site/enterprise procedures
- 5.4 Work completion details are finalised in accordance with site/enterprise procedures

Approved Page 7 of 14

Required Skills and Knowledge

REQUIRED SKILLS AND KNOWLEDGE

8) This describes the Essential Skills and Knowledge and their level, required for this unit.

Evidence shall show that knowledge has been acquired testing and commissioning complex electrical equipment.

All knowledge and skills detailed in this unit should be contextualised to current industry practices and technologies.

The extent of the Essential Knowledge and Associated Skills required follows:

KS01-PM414B Test and commission complex electrical equipment

T1 Evidence shall show that knowledge has been acquired for safe working practices of:

- Relevant Environmental, Occupational Health and Safety legislation and regulations
- Relevant plant and equipment, its location and operation
- Technical drawings and manufacturers manuals
- Introduction to and typical arrangements of power production plant
- Relevant state and territory regulations
- Relevant Australian standards;
- Equipment and material required to perform the work;
- Isolation procedures;
- Testing and commissioning techniques and procedures;
- Operational requirements of the equipment;
- Complex electrical equipment;
- Regulatory procedures;
- Electrical principles;
- Test and measurement instruments;
- Engineering and electronic workshop practice;

T2 Specific skills needed to achieve the Performance Criteria:

- Apply Relevant Environmental, Occupational Health and Safety legislation and regulations
- Interpret Technical drawings and manufacturers manuals
- Apply relevant state and territory regulations
- Apply relevant Australian standards;
- Use tools and relevant equipment;
- Use test and measurement instruments;
- Inspect and test the wiring systems;
- Inspect, test and monitor equipment;
- Commission complex electrical equipment;
- Select materials for the job;
- Apply regulatory procedures;

Approved Page 8 of 14

REQUIRED SKILLS AND KNOWLEDGE

- · Apply electrical principles;
- Communicate effectively;
- Apply data analysis techniques and tools;
- Apply engineering and electronic workshop practices.

Evidence Guide

EVIDENCE GUIDE

9) This provides essential advice for assessment of the competency standard unit and must be read in conjunction with the Performance Criteria and the Range Statement of unit and the Training Package Assessment Guidelines.

The Evidence Guide forms an integral part of this competency standard unit and shall be used in conjunction with all components parts of this unit and, performed in accordance with the Assessment Guidelines of this Training Package.

Overview of Assessment

9.1)

Longitude competency development approaches to assessment, such as Profiling, require data to be reliably gathered in a form that can be consistently interpreted over time. This approach is best utilised in Apprenticeship programs and reduces assessment intervention. It is the Industry's preferred model for apprenticeships. However, where summative (or final) assessment is used it is to include the application of the competency in the normal work environment or in a realistically simulated work environment. It is recognised that, in some circumstances, assessment in part or full can occur outside the workplace. However, it must be in accord with Industry and regulatory policy. Methods chosen for a particular assessment will be influenced by various factors. These include the extent of the assessment, the most effective locations for the assessment activities to take place, access to physical resources, additional safety measures that may be required and the critical nature of the competencies being assessed.

The critical safety nature of working with electricity, electrical equipment, gas or any other hazardous substance/material carries risk in deeming a person competent. Hence, sources of evidence need to be 'rich' in nature so as to minimise error in judgment. Activities associated with normal every day work have a bearing on the decision as to how much and how detailed the data gathered will contribute to its 'richness'. Some skills are more critical to

Approved Page 9 of 14

safety and operational requirements while the same skills may be more or less frequently practiced. These points are raised for the assessors to consider when choosing an assessment method and developing assessment instruments. Sample assessment instruments are included in the Assessment Guidelines of this Training Package.

Critical aspects of evidence required to demonstrate competency in this unit 9.2)

Before the critical aspects of evidence are considered all prerequisites shall be met.

Evidence for competence in this unit shall be considered holistically. Each element and associated Performance Criteria shall be demonstrated on at least two occasions in accordance with the "Assessment Guidelines – UEP12". Evidence shall also comprise:

- A representative body of work performance demonstrated within the timeframes typically expected of the discipline, work function and industrial environment. In particular this shall incorporate evidence that shows a candidate is able to:
 - Implement Occupational Health and Safety workplace procedures and practices including the use of risk control measures as specified in the Performance Criteria and Range Statement
 - Apply sustainable energy principles and practices as specified in the Performance Criteria and Range Statement
 - Demonstrate an understanding of the essential knowledge and associated skills as described in 6) of this unit
 - Demonstrate an appropriate level of employability skills
 - Conduct work observing the relevant Anti Discrimination legislation, regulations, polices and workplace procedures
- Demonstrated performance across a representative range of contexts from the prescribed items below:
 - The knowledge and application of relevant sections of: Occupational Health and Safety legislation; Statutory legislation; Enterprise/site safety procedures; Enterprise/site emergency procedures
 - Where appropriate attainment of an appropriate electrical licence, deeming competency associated with electrical work

Approved Page 10 of 14

- Preparation and planning of work
- Testing techniques
- Commissioning procedures
- Completion of work procedures
- Dealing with an unplanned event by drawing on essential knowledge and skills to provide appropriate solutions incorporated in the holistic assessment with the above listed items.

Context of and specific resources for assessment

9.3)

This unit should be assessed as it relates to normal work practice using procedures, information and resources typical of a workplace. This should include:

- OHS policy and work procedures and instructions.
- Suitable work environment, facilities, equipment and materials to undertake actual work as prescribed by this unit.

Competency Standards should be assessed in the workplace or simulated workplace and under the normal range of workplace conditions.

Assessment of this unit will be supported with documentary evidence, by means of endorsement stating type and application of work.

In addition to the resources listed above in Context of assessment', evidence should show competency working, in limited spaces, with different types of plant and equipment as well as different structural/construction types and methods and in a variety of environments.

Method of assessment

9.4)

This unit shall be assessed by methods given in 1.3.00 Assessment Guidelines.

Note:

Competent performance with inherent safe working practices is expected in the Industry to which this unit applies. This requires that the specified essential knowledge and associated skills are assessed in a structured environment which is primarily intended for learning/assessment and incorporates all necessary equipment and facilities for learners to develop and demonstrate the essential

Approved Page 11 of 14

knowledge and skills described in this unit.

Concurrent assessment and relationship with other units

9.5)

There are no recommended concurrent assessments with this unit, however in some cases efficiencies may be gained in terms of learning and assessment effort being concurrently managed with allied competency standard units where listed. Nil

Approved Page 12 of 14

Range Statement

RANGE STATEMENT

10) This relates to the competency standard unit as a whole providing the range of contexts and conditions to which the Performance Criteria apply. It allows for different work environments and situations that will affect performance. Inspection should be planned with the appropriate parties to determine access, conditions and work requirements.

Equipment may include HV transformers, tap changers, switchgear and associated control panels, alarms, alternators, igniters, flame scanners, unit control panels, mimic panels, conveyors, alternator cooling systems, automatic voltage regulators, sootblowers, vibratory feeders, battery chargers, precipitators and overhead cranes. Materials may include masonry anchors, bolts, nuts, washers, screws, rivets, saddles, clips, brackets, solvents, adhesives, insulation tapes, heat shrink, sleeving, spiral binding, cable ties, solder, lubricants, oil, greases, sealants, lugs, connectors, terminal blocks, cable markers, identification labels, transformer oil, jointing compound, cable compounds and phase markers.

Components may include fuses/circuit breakers, timers, contactors, contacts, coils, relays, solenoids, overloads, switches, plugs, busbar, cable, fans, thermostats, elements, seals and motor bearings and brush gear.

Fixed wiring tests may include polarity, loop impedance, insulation resistance/continuity tests.

Monitoring equipment may include stopwatch, indication lamps, tachometer/rev counter, LED displays, VDUs, thermometers, mimic panels, position indicators, audio indicators and chart recorders.

Work may be performed with equipment on line.

Work completion details may include plant and maintenance records, job cards, check sheets and on device labelling updates.

Work site environment may be affected by nearby plant or processes, e.g. heat, noise, dust, oil, water and chemical. Isolations can refer to electrical/mechanical or other associated processes.

Generic terms are used throughout this Training Package for vocational standard shall be regarded as part of the Range Statement in which competency is demonstrated. The definition of these and other terms are given in Section 2.1 Preliminary Information and Glossaries.

Unit Sector(s)

Not applicable.

Approved Page 13 of 14

Competency Field

Competency Field 11)

Maintenance.

Approved Page 14 of 14