



Australian Government

Assessment Requirements for CPCCDE3018 Select and use small plant and equipment for demolition tasks

Release: 2

Assessment Requirements for CPCCDE3018 Select and use small plant and equipment for demolition tasks

Modification History

Release 2 Updated reference to general construction induction training program.

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and is equivalent to CPCCDE3018A Select and use small plant and equipment for demolition tasks. Updated to meet the Standards for Training Packages 2012.

Performance Evidence

To demonstrate competency in this unit, a candidate must select and use small plant and equipment to complete three of the following on-site demolition tasks:

- break a minimum of two square metres of concrete
- dismantle 20 square metres of purlins and wall or roof sheeting
- demolish 10 lineal metres of three-metre high masonry wall
- identify services infrastructure in a minimum 20 square-metre section of a building, and remove the infrastructure (ducting, cabling, pipework) for one service
- remove wall cladding and floor coverings from a minimum 10 square-metre section of a building
- remove a ceiling from a 20 square-metre section of a building.

In doing this, the candidate must meet the performance criteria for this unit.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- the compliance requirements of the relevant Australian Standards, Building Code of Australia (BCA), model codes of practice, environmental and work health and safety (WHS) legislation
- general construction terminology
- hazards that may exist or arise on demolition sites, including those associated with the use of demolition small plant and equipment
- procedures for:
 - environmentally friendly waste management
 - managing risks and hazards on demolition sites
 - sorting and storing reusable and recyclable materials

- types of information required to plan and prepare for safe and effective completion of demolition tasks
- types of small plant and equipment applicable to demolition tasks:
 - applications of each type of small plant or piece of equipment
 - maintenance requirements
 - safe methods of operation for different demolition tasks.

Assessment Conditions

Assessors must satisfy the requirements for assessors contained in the Standards for Registered Training Organisations.

Assessment of performance must be undertaken in the workplace or in a simulated workplace environment.

Assessors are responsible for ensuring that the candidate demonstrating competency has access to:

- worksite/s and specifications for selecting and using small plant and equipment for demolition tasks
- appropriate documents, materials, tools, equipment and personal protective equipment (PPE) currently used in industry
- requirements of workplace policies, procedures and demolition plans.

Links

Companion volumes to this training package are available at the VETNet website -
<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>