



**Australian Government**

# **CPCCPB3004 Fix wet area sheets**

**Release: 2**

# CPCCPB3004 Fix wet area sheets

## Modification History

Release 2 Updated reference to general construction induction training program.

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and equivalent to CPCCPB3004A Fix wet area sheets. Updated to meet the Standards for Training Packages 2012.

## Application

This unit of competency specifies the skills and knowledge required to fix wet area sheets to comply with manufacturer and job specifications.

A person working at this level would be expected to take responsibility for organising and completing tasks assigned to them without close supervision.

Completion of the general construction induction training program specified by the model Code of Practice for Construction Work is required for any person who is to carry out construction work. Achievement of *CPCWHS1001 Prepare to work safely in the construction industry* meets this requirement.

No licensing, legislative or certification requirements apply to this unit at the time of publication.

## Pre-requisite Unit

CPCCWHS2001 Apply WHS requirements, policies and procedures in the construction industry.

## Unit Sector

Plasterboard

## Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

1 Plan and prepare.

1.1 Read and interpret work instructions and plan sequence of work.

1.2 Plan all work to comply with laws and regulations, the

- National Construction Code (NCC), Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, and workplace requirements.
- 1.3 Select and use personal protective equipment (PPE) for each stage of the task.
  - 1.4 Inspect work site, assess hazards and apply risk controls, including required signage and barricades.
  - 1.5 Select tools and equipment, check for serviceability and report any faults that may affect the safe operation of the equipment, tag equipment and set aside.
  - 1.6 Select materials required for task, calculate quantities, handle safely and prepare and position ready for use.
- 2 Plan and cut wet area sheets.
- 2.1 Determine work sequences, fixing processes from manufacturers' specifications and AS/NZS2589 Gypsum linings - application and finishing.
  - 2.2 Match sheet size to wall dimensions.
  - 2.3 Plan cutting process to minimise dust exposure for others.
  - 2.4 Follow manufacturers' specifications for cutting process and provision for penetrations.
  - 2.5 Cut sheets to minimise waste and number of joints and maximise board use.
- 3 Fix wet area sheets.
- 3.1 Hang and fix sheets using manual handling techniques and following manufacturer's specifications, ensuring the sheets have appropriate gap from the floor and flashing are installed to specification.
  - 3.2 Check completed work to ensure stop-up activities can be easily completed.
- 4 Clean up.
- 4.1 Clear work area and dispose of, reuse or recycle materials.

- 4.2 Clean, check, maintain and store tools and equipment in accordance with manufacturers' specifications

## Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

## Unit Mapping Information

Supersedes and equivalent to CPCCPB3004A Fix wet area sheets

## Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>

# Assessment Requirements for CPCCPB3004 Fix wet area sheets

## Modification History

- Release 2 Updated reference to general construction induction training program.
- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.
- Supersedes and equivalent to CPCCPB3004A Fix wet area sheets. Updated to meet the Standards for Training Packages 2012.

## Performance Evidence

To demonstrate competency, a candidate must satisfy all of the elements, performance criteria and foundation skills of this unit by hanging and fixing 15 square metres of wet area sheets.

All work must be performed to the standard required in the workplace and must comply with Commonwealth and state/territory laws and regulations, the National Construction Code, Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, and workplace requirements.

## Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of the National Construction Code and Australian Standards for fixing wet area sheets, including AS/NZS2589 Gypsum linings - application and finishing
- quality policies and standards for fixing wet area sheets
- requirements for wet areas that will be tiled, and for wet areas that will be non-tiled
- safety requirements for fixing wet area sheets, including personal protective equipment (PPE), job safety analyses, safe work method statements and safety data sheets
- processes for safe handling and lifting of wet area sheets
- environmental requirements for fixing wet area sheets
- manufacturers' specifications for fixing wet area sheets
- types and uses of adhesives and fasteners for fixing wet area plasterboard sheets
- wet area plasterboard materials
- installing flashings to specification
- materials storage and environmentally friendly waste management
- plans, drawings and specifications for fixing wet area plasterboard sheets
- plasterboard fixing techniques for wet area plasterboard sheets
- processes for the calculation of material requirements for fixing wet area plasterboard sheets
- types of tools and equipment for fixing wet area plasterboard sheets.

## Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

This unit must be assessed:

- in the workplace or a close simulation of the workplace environment, provided that simulated or project-based assessment techniques replicate construction workplace conditions, materials, activities, responsibilities and procedures
- using realistic tasks or simulated tasks, relevant specifications and work instructions, standard work practices, safety requirements and environmental constraints.

## Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>