



Australian Government

CPCCPB3014 Install bulk insulation and pliable membrane products

Release: 1

CPCCPB3014 Install bulk insulation and pliable membrane products

Modification History

Release 1. This version first released with CPC Construction, Plumbing and Services Training Package Version 3.0

Application

This unit specifies the outcomes required to safely undertake floor, wall and ceiling insulation installation work using bulk insulation and pliable membrane products. The unit includes identifying legislative, regulatory, and job requirements; planning and preparing to install insulation; installing insulation; and, completing installation, including preparation of a Statement of Insulation Installation.

The unit requires a person undertaking this work to comply with legislative, regulatory, safety and technical, organisational and site requirements while planning and carrying out the work.

The unit applies to insulation installers working primarily in residential buildings, although there may be application in some instances in commercial buildings.

The work context involves working at heights, working in enclosed areas, dust control and mitigation of risk from asbestos.

At the time of endorsement there was no requirement by any state or territory regulator for insulation installers to complete this unit for licensing or registration purposes.

Pre-requisite Unit

Nil

Competency Field

Plasterboard

Unit Sector

Construction

Elements and Performance Criteria

ELEMENTS

Elements describe the essential outcomes.

1. Define job

PERFORMANCE CRITERIA

Performance criteria describe the performance needed to demonstrate achievement of the element.

1.1. Identify scope of required installation activities through review

Requirements	of job requirements and inspection of work site.
	1.2. Assess and control site risks and hazards and communicate and clarify any issues with supervisor.
	1.3. Identify requirements of workplace procedures for responding to the presence of vermin, asbestos, and dust within the workspace.
	1.4. Identify required safety equipment and processes by review of work order, risk assessment, safety data sheets (SDS), safe use instruction sheet (SUIS) and safety legislation .
	1.5. Identify and review requirements of Australian Standards (AS) AS 4200.2 for pliable membrane wall insulation and AS 3999 relating to electrical inspections, safety and installation activities.
	1.6. Identify and review workplace environmental requirements that relate to the installation activities.
	1.7. Identify and review workplace emergency response and evacuation procedures as they apply to the site of the installation activities.
	1.8. Identify and review work instructions and specifications that relate to the installation activities.
2. Plan and prepare for installing insulation.	2.1. Undertake an electrical risk assessment and prepare an electrical risk assessment report.
	2.2. Document and submit for approval a Safe Work Method Statement (SWMS) for the worksite, incorporating identified risks and hazards, the outcomes of the electrical risk assessment, electrical isolation procedure and the hazard hierarchy of control.
	2.3. Plan job incorporating identified requirements of work order, work site, safety legislation, AS 3999, environmental requirements, work instructions and specifications and SWMS.
	2.4. Confirm that insulating material and insulation requirements meet work instructions and thermal and acoustic performance specifications.
	2.5. Put in place all requirements of the SWMS.
	2.6. Select personal protective equipment (PPE), tools, equipment and associated materials , check for serviceability and report for

repair or replacement where unserviceable.

3. Install floor, wall and ceiling insulation.
 - 3.1. Isolate worksite electrical circuits and install safety signage and lock-out tag in accordance with the SWMS.
 - 3.2. Undertake installation work in accordance with the SWMS.
 - 3.3. Undertake installation work using approved methods of measurement and cutting of insulating material.
 - 3.4. Undertake installation work in accordance with requirements of AS 3999 for recessed luminaries and electrical cable and AS 4200.2 for wall applications where pliable building membranes are required.
 - 3.5. Undertake installation work in accordance with manufacturers' specifications and minimise waste.
 - 3.6. Install insulation without damage or distortion of the surrounding environment, electrical and other services and in a manner that maximises safety of self and others.
 - 3.7. Conduct final inspection to ensure installed floor, wall and ceiling insulation conforms to work instructions, AS 3999 and manufacturers' specifications.
4. Complete installation.
 - 4.1. Clean work area and dispose of, re-use or re-cycle **materials** following workplace and environmental procedures.
 - 4.2. Clean, check, maintain, and store tools and equipment in accordance with manufacturer specifications.
 - 4.3. Document details of malfunctions, faults, wear or damage to tools and equipment and report for repair or replacement.
 - 4.4. Document, distribute, and store Statement of Insulation Installation.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Range of Conditions

Not Applicable

Unit Mapping Information

Supersedes and is not equivalent to CPCCPB3014A - Install batt insulation products

Links

An Implementation Guide to this Training Package is available at the VETNet website -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>

Assessment Requirements for CPCCPB3014 Install bulk insulation and pliable membrane products

Modification History

Release 1. This Version first released with CPC Construction, Plumbing and Services Training Package Version 3.0

Performance Evidence

A person who demonstrates competency in this unit must;

1. Conduct an electrical risk assessment and prepare an electrical risk assessment report.
2. Plan and install:
 - a) bulk insulation in:
 - a floor space with a minimum area of 9 square metres;
 - wall frames a minimum of 2400mm high by 3 lineal metres; and
 - a ceiling space with a minimum area of 9 square metres.
 - b) pliable membrane to:
 - wall frames a minimum of 2400mm high by 3 lineal metres.

The person must provide evidence from each of the above activities that:

- satisfies the elements and associated performance criteria and foundation skills of this unit; and
- confirms the activities to be in accordance with legislative and workplace requirements specified in Knowledge Evidence.

Knowledge Evidence

A person demonstrating competency in this unit must provide evidence to demonstrate knowledge and understanding of the following knowledge evidence items.

Each item defines the type and depth of the knowledge required to meet the demands of one or more performance criteria:

- Jurisdictional Workplace Health and Safety and environmental legislation and regulations
- Workplace requirements for undertaking all aspects of insulation and pliable membrane installation, including interpreting work orders and reporting problems
- Procedures to safely use equipment, shift and handle products and materials, and work at heights and in enclosed areas to install floor, wall and ceiling insulation in common situations
- Organisational procedures for responding to the presence of pests/vermin, asbestos and dust within an installation workspace
- Risks of asbestos containing materials (ACM), and their use in common building materials used in floor, wall and ceiling spaces

- Key requirements of legislation, regulation and building codes related to floor, wall and ceiling insulation
- Tools and equipment prohibited for use near identified asbestos-containing materials (ACM)
- Appropriate PPE and its use in floor, wall and ceiling insulation installation
- Safety data sheets (SDS) and Safe Work Method Statements (SWMS) commonly used in floor, wall and ceiling insulation installation
- Common health and safety risks associated with handling floor, wall and ceiling insulation products
- Emergency response and evacuation procedures relating to floor, wall and ceiling insulation installation
- Work instructions and specifications relating to floor, wall and ceiling insulation installation
- Electrical risk assessment process, hazard identification and reporting as per Australian Standard (AS) AS 3999 for common floor, wall and ceiling insulation installation
- Hierarchy of hazard control as it relates to floor, wall and ceiling insulation installation
- Organisational requirements and procedures relating to floor, wall and ceiling insulation installation, including requirements for a systematic approach to planning own work
- Key requirements of Australian Standards - relating to floor, wall and ceiling information, including:
 - AS/NZS 4859.1 Materials for the thermal insulation of buildings - Testing and labelling of insulation;
 - AS 4200.2 Pliable building membranes – Installation; and
 - AS/NZS 3000 (with Amd 1) Wiring Rules, in particular Clause 4.5.2.3.
- Requirements relating to floor, wall and ceiling insulation installation from AS 3999 for:
 - personal safety;
 - electrical risk assessment;
 - approved processes; and
 - energy efficiency – new products and technologies.
- Specifications of common floor, wall and ceiling installation materials, including R rating and dimensions
- Types, safety, characteristics, uses and limitations of common floor, wall and ceiling insulation installation tools and equipment
- Type and purpose of lock out tags in floor, wall and ceiling insulation installation
- Requirements of AS 3999 for recessed luminaires and electrical cable, in floor, wall and ceiling insulation installation including:
 - operating temperature limit of electrical cables;
 - effect on cables partially surrounded by thermal insulation and fully surrounded by thermal insulation;
 - common wiring systems used in domestic premises indicating the age of the installation;

- clearance and restraint methods to retain thermal insulation from recessed down lights and ancillary equipment; and
- electrical hazards in floor, wall and roof spaces, including unenclosed connections, unenclosed conductors, damaged cable sheaths and exposed conductors.
- Product and process knowledge to identify common problems and predict consequences in floor, wall and ceiling insulation installation
- Quality requirements for installation of floor, wall and ceiling insulation material including thermal and acoustic performance
- Energy efficiency of common floor, wall and ceiling insulation material types
- Methods for measuring and cutting floor, wall and ceiling insulation material
- Procedures for conducting a final inspection of a floor, wall and ceiling insulation installation
- Workplace procedures for environmental requirements for waste, including waste management and recycling relating to floor, wall and ceiling insulation installation
- Procedures for cleaning, checking and maintaining tools and equipment used for floor, wall and ceiling insulation installation
- Procedures for dealing with faulty floor, wall and ceiling insulation installation tools and equipment
- Procedures for documenting, distributing and storing Statements of Insulation Installation incorporating the format and required information as defined in AS 3999 – Appendix D

Assessment Conditions

As a minimum, assessors must satisfy the requirements for assessors in applicable vocational education and training legislation, frameworks and/or standards.

Assessment of performance must be undertaken in the workplace and/or under realistic workplace conditions which typically reflect:

- the use of industry standard equipment;
- performing tasks/activities to the level of proficiency and within timelines that would be expected in a workplace; and
- following standard and authorised work practices, safety requirements and environmental constraints.

Assessment must include work in enclosed areas with an access/egress point (e.g. manhole) and ceiling space obstructions including roof framing, electrical cabling and recessed luminaries.

Assessors are responsible for ensuring that candidates have access to specifications for:

- conducting an electrical risk assessment and preparing an electrical risk assessment report;
- a floor installation task in a floor space with a minimum area of 9 square metres;
- a wall installation task with wall frames a minimum of 2400mm high by 3 lineal

metres;

- a ceiling installation task in a ceiling space with a minimum area of 9 square metres ; and
- a wall-wrap installation task for pliable membrane to wall frames a minimum of 2400mm high by 3 lineal metres.
- floor spaces;
- wall frames;
- ceiling spaces;
- materials and tools;
- relevant sections of the Australian Standards/National Construction Code;
- relevant sections of WHS/OHS legislation;
- electrical risk assessment report;
- SWMS template;
- Statement of Insulation Installation template;
- PPE; and
- technical documentation.

Links

An Implementation Guide to this Training Package is available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>