



Australian Government

Assessment Requirements for CPCCPB3018 Use vacuum and electric sanding equipment to finish plaster work

Release: 2

Assessment Requirements for CPCCPB3018 Use vacuum and electric sanding equipment to finish plaster work

Modification History

- Release 2 Updated reference to general construction induction training program.
- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.
- Supersedes and equivalent to CPCCPB3018A Use vacuum and electric sanding equipment to finish plaster work. Updated to meet the Standards for Training Packages 2012.

Performance Evidence

To demonstrate competency, a candidate must satisfy all of the elements, performance criteria and foundation skills of this unit by using vacuum and electric sanding equipment to finish plaster work in a minimum 12 square metre room with plastering to all four walls and the ceiling, with at least one door and one window, and plaster to internal and external corner joints.

All work must be performed to the standard required in the workplace and must comply with Commonwealth and state/territory laws and regulations, Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, and workplace requirements.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of Australian Standards for using vacuum and electric sanding equipment to finish plaster work
- quality policies and standards for using vacuum and electric sanding equipment to finish plaster work
- safety requirements for using vacuum and electric sanding equipment to finish plaster work, including personal protective equipment (PPE), job safety analyses, safe work method statements and safety data sheets
- environmental requirements for using vacuum and electric sanding equipment to finish plaster work
- reasons for use of P1 rating (protection against mechanically generated particles) or P2 rating (protection against mechanically and thermally generated particles) mask and protective clothing when emptying and cleaning equipment and disposing of dust
- effects of glancing light on plasterboard joints when paint is applied
- factors that influence level of finish

- manufacturers' specifications for using vacuum and electric sanding equipment to finish plaster work.

Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

This unit must be assessed:

- in the workplace or a close simulation of the workplace environment, provided that simulated or project-based assessment techniques replicate construction workplace conditions, materials, activities, responsibilities and procedures
- using realistic tasks or simulated tasks, relevant specifications and work instructions, standard work practices, safety requirements and environmental constraints.

Links

Companion volumes to this training package are available at the VETNet website -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>