



Australian Government

Assessment Requirements for CPCCPB3026 Erect and maintain trestle and plank systems

Release: 3

Assessment Requirements for CPCCPB3026 Erect and maintain trestle and plank systems

Modification History

- Release 3 Updated reference to general construction induction training program.
- Release 2 This version first released with CPC Construction, Plumbing and Services Training Package Release 6.5.
- This version updated to reflect the latest Australian Standard.
 - Amended Performance Criteria 2.5 and 3.2.
 - Amended Performance Evidence.
- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.
- Supersedes and equivalent to CPCCPB3026B Erect and maintain trestle and plank systems. Updated to meet the Standards for Training Packages 2012.

Performance Evidence

To demonstrate competency, a candidate must satisfy all of the elements, performance criteria and foundation skills of this unit by erecting two trestle systems of a minimum 450mm width platform and 3m length with handrail system.

All work must be performed to the standard required in the workplace and must comply with Commonwealth and state/territory laws and regulations, national construction codes, Australian Standards, work health and safety (WHS) and environmental requirements, manufacturer's specifications, and workplace requirements.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of the National Construction Code and Australian Standards for erecting and maintaining trestle and plank systems, including Australian standards, AS/NZS4576 Guidelines for Scaffolding
- quality policies and standards for erecting and maintaining trestle and plank systems
- safety requirements for erecting and maintaining trestle and plank systems, including personal protective equipment (PPE), job safety analyses, safe work method statements and safety data sheets
- environmental requirements for erecting and maintaining trestle and plank systems
- faults in operation of equipment, including:
 - loose components

- damage to trestles or planks
- displacement of components
- identifying potential for health and safety risks from workplace information and labels
- identifying the purpose of tags and logs of use for equipment
- job safety analysis (JSA) and safe work method statements
- manufacturers' specifications for tools and equipment
- types of tools and equipment for erecting and maintaining trestle and plank systems.

Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

This unit must be assessed:

- in the workplace or a close simulation of the workplace environment, provided that simulated or project-based assessment techniques replicate construction workplace conditions, materials, activities, responsibilities and procedures
- using realistic tasks or simulated tasks, relevant specifications and work instructions, standard work practices, safety requirements and environmental constraints.

Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>