



Australian Government

Assessment Requirements for CPCCSH3003 Assemble and install shopfront structures

Release: 1

Assessment Requirements for CPCCSH3003 Assemble and install shopfront structures

Modification History

Release 1.

This version first released with CPC Construction, Plumbing and Services Training Package Version 2.

Revised unit of competency. Replaces superseded equivalent CPCCSH3003A Assemble and install shopfront commercial entries bulkheads and components.

Performance Evidence

A person who demonstrates competency in this unit must satisfy all of the elements, performance criteria and foundation skills of this unit, and must assemble and install a shopfront structure, including bulkhead.

In doing the above work, the person must:

- comply with safety requirements and health and safety regulations applicable to workplace operations
- apply organisational quality procedures and processes in the context of assembling and installing a shopfront
- identify design required for assembly and installation of shopfront, including:
 - shopfront design
 - design of delivered assemblies, components and fittings
 - component and shopfront assembly diagram
- identify and select components and fittings to match locations in assembled shopfront
- select and use processes, tools and equipment to assemble and install nominated shopfront structure
- prepare building structure to receive installation of shopfront
- safely and efficiently:
 - assemble sections, components and fittings
 - install bulkhead into position
 - locate and install assembly into place
 - install components and fittings and, where applicable, check that assembled shopfront operates as specified
- identify typical faults and problems that occur and action required to rectify them
- communicate with others to ensure safe and effective workplace operations.

Knowledge Evidence

A person demonstrating competency in this unit must demonstrate knowledge of:

- Australian standards, including AS 2047 Windows and external glazed doors in buildings
- basic structures and components of walls and ceiling
- content of and terms and symbols used in relevant drawings and specifications
- contents of and terms used in job safety analyses (JSA) and safe work method statements (SWMS)
- design and construction processes for shopfronts
- organisation's quality assurance requirements relating to assembling and installing shopfront structures
- workplace and equipment safety requirements relating to assembling and installing shopfront structures.

Assessment Conditions

Suitable assessment of performance requires:

- equipment and tools:
 - as listed in the range of conditions
 - scaffolding erected in place
- materials:
 - prefabricated shopfront and bulkhead components, sections and fittings
- specifications:
 - AS 2047 Windows and external glazed doors in buildings
 - job requirements
 - JSA
 - safety data sheets (SDS)
 - SWMS
- physical conditions:
 - shopfront opening suitable for fitting the shopfront structure and bulkhead
- relationship with client:
 - liaison with client may be required
- relationships with team members and supervisor:
 - work may be completed as part of a team
- timeframe:
 - according to job requirements.

Assessor requirements

As a minimum, assessors must satisfy the assessor requirements in the Standards for Registered Training Organisations (RTOs) current at the time of assessment.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.education.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>