



Australian Government

Assessment Requirements for CPCCSH3009 Demolish shopfronts and bulkheads

Release: 1

Assessment Requirements for CPCCSH3009 Demolish shopfronts and bulkheads

Modification History

Release 1.

This version first released with CPC Construction, Plumbing and Services Training Package Version 2.

New unit of competency.

Performance Evidence

A person demonstrating competency in this unit must satisfy all of the elements, performance criteria and foundation skills of this unit, and must demolish:

- one shopfront that is at least 3.6 metres high and that includes:
 - glazing
 - bulkheads
 - door closure
 - joinery
- one internal cabinet or fixture that is at least 3.6 metres high and 2.4 metres wide and attached to the building structure.

In doing the above work, the person must:

- locate, interpret and apply information, standards and specifications relevant to the demolition
- comply with site safety plan, health and safety regulations, and state and territory legislation applicable to workplace operations
- comply with organisational policies and procedures, including quality requirements
- safely and effectively use tools, plant and equipment
- communicate and work effectively and safely with others.

Knowledge Evidence

A person demonstrating competency in this unit must demonstrate knowledge of:

- construction terminology used in shopfitting
- demolition and building materials and their characteristics
- procedures and techniques relevant to demolishing shopfronts
- identification and handling requirements for hazardous substances, including lead, fibreglass and asbestos
- contents of and terms used in:
 - safety data sheets (SDS) and safe work method statements (SWMS) for tasks

- plans, specifications and drawings relating to demolishing shopfronts and bulkheads
- materials storage requirements and processes and environmentally friendly waste management
- types, characteristics, uses and limitations of plant, tools and equipment used to demolish shopfronts and bulkheads
- processes for calculating volumes of material for removal
- safe procedures for the use of scaffolding
- workplace and equipment safety requirements relating to demolishing shopfronts and bulkheads.

Assessment Conditions

Suitable assessment of performance requires:

- equipment:
 - as listed in the range of conditions
- contingencies:
 - potential for undiscovered hazards on site
- specifications:
 - as listed in job requirements in the range of conditions
- physical conditions:
 - retail site with shopfront and bulkhead requiring demolition
- relationship with client:
 - consultation with client may be required
- relationships with team members and supervisor:
 - work must be completed as part of a team and supervision must be provided
- timeframe:
 - according to job requirements.

Assessor requirements

As a minimum, assessors must satisfy the assessor requirements in the Standards for Registered Training Organisations (RTOs) current at the time of assessment.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.education.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>