



Australian Government

Assessment Requirements for CPCCSP3006 Install cast plaster blockwork and wall sheet panels

Release: 2

Assessment Requirements for CPCCSP3006 Install cast plaster blockwork and wall sheet panels

Modification History

- Release 2 Updated reference to general construction induction training program.
- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.
- Supersedes and equivalent to CPCCSP3006A Install cast plaster brickwork.
Change to title. Updated to meet the Standards for Training Packages 2012.

Performance Evidence

To demonstrate competency, a candidate must satisfy all of the elements, performance criteria and foundation skills of this unit by installing a minimum:

- 3.6m long X 1.8m high pre-cast plaster blockwork
- three sheet panelled wall.

All work must be performed to the standard required in the workplace and must comply with laws and regulations, the National Construction Code (NCC), Australian Standards work health and safety (WHS) and environmental requirements, manufacturers' specifications, workplace requirements, drawings and specifications.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of the NCC and Australian Standards for installing cast plaster blockwork and wall sheet panels
- workplace quality policies and standards for installing cast plaster blockwork and wall sheet panels
- safety requirements installing cast plaster blockwork and wall sheet panels, including:
 - job safety analyses and/or safe work method statements in accordance with Safe Work Australia *Code of Practice for Construction Work* or state and/or territory equivalent
 - safety data sheets (SDS)
 - personal protective equipment (PPE)
- environmental requirements for installing cast plaster blockwork and wall sheet panels
- processes, procedures and techniques for:
 - checking substrates for suitability
 - cutting for openings
 - plaster blockwork

- installing, fixing wall sheet panelling
- beading
- solid plastering and finishing
- calculating material requirements
- types and uses of tools and equipment for installing cast plaster blockwork and wall sheet panels
- types and uses of plans, drawings and specifications for installing cast plaster blockwork and wall sheet panels.

Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

This unit must be assessed in the workplace or a close simulation using realistic workplace conditions, materials, activities, responsibilities, procedures, safety requirements and environmental considerations.

Links

Companion volumes to this training package are available at the VETNet website -
<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>