



Australian Government

CPCCS3008 Carry out concrete construction and wall sheet panning

Release: 2

CPC CSP3008 Carry out conite construction and wall sheet panelling

Modification History

- Release 2 Updated reference to general construction induction training program.
- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.
New unit.

Application

This unit specifies the skills and knowledge required to carry out conite construction and wall sheet panelling.

It includes preparing the surface by fixing building paper and securing lathing to wall framing.

A person working at this level would be expected to take responsibility for organising and completing tasks assigned to them, without close supervision.

Licensing, legislative or certification requirements may apply to this unit.

Completion of the general construction induction training program specified by the model Code of Practice for Construction Work is required for any person who is to carry out construction work. Achievement of unit *CPCWHS1001 Prepare to work safely in the construction industry* meets this requirement.

Pre-requisite Unit

CPCWHS2001 Apply WHS requirements, policies and procedures in the construction industry.

Unit Sector

Plastering

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

- | | |
|--|---|
| 1 Plan and prepare to carry out conite | 1.1 Read and interpret work instructions and plan sequence of work. |
|--|---|

- | | | |
|--|--------------------|--|
| construction and wall sheet panelling. | 1.2 | Plan all work to comply with laws and regulations, the National Construction Code (NCC), Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, and workplace requirements. |
| | 1.3 | Select and use personal protective equipment (PPE) for each stage of the task. |
| | 1.4 | Inspect work site, assess hazards and apply risk controls, including required signage and barricades. |
| | 1.5 | Select tools and equipment, check for serviceability and report any faults. |
| | 1.6 | Select materials required for task, calculate quantities, handle safely and prepare and position ready for use. |
| | 1.7 | Erect and brace scaffolding to required height in accordance with licensing requirements. |
| | 2 Prepare surface. | 2.1 |
| | 2.2 | Fix building paper taut to face of frame in compliance with NCC. |
| | 2.3 | Fit and fix expanded metal lathing (ELP). |
| | 2.4 | Fix wall sheet panel to framing in compliance with NCC. |
| 3 Apply concrete finish. | 3.1 | Apply sand, cement and lime scratch coat. |
| | 3.2 | Apply floating coat. |
| | 3.3 | Screed and trowel to specified finish. |
| 4 Clean up. | 4.1 | Clear work area, dispose of materials, and reuse or recycle in compliance with legislation, regulations and codes of practice. |
| | 4.2 | Clean, check, maintain and store tools and equipment in accordance with manufacturers' specifications. |

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

No equivalent unit.

Links

Companion volumes to this training package are available at the VETNet website -
<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>

Assessment Requirements for CPCSP3008 Carry out conite construction and wall sheet panelling

Modification History

Release 2 Updated reference to general construction induction training program.

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

New unit.

Performance Evidence

To demonstrate competency, a candidate must satisfy all of the elements, performance criteria and foundation skills of this unit by applying conite construction, including wall sheet panels, to a minimum of 4 square metres of timber or metal frame wall, including applying a three coat finish system.

All work must be performed to the standard required in the workplace and must comply with laws and regulations, the National Construction Code (NCC), Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications, workplace requirements, drawings and specifications.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of the NCC and Australian Standards for carrying out conite construction and wall sheet panelling
- workplace quality policies and standards for conite construction/wall sheet panels
- safety requirements for carrying out conite construction and wall sheet panelling, including:
 - job safety analyses and/or safe work method statements in accordance with Safe Work Australia *Code of Practice for Construction Work* or state and/or territory equivalent
 - safety data sheets (SDS)
 - personal protective equipment (PPE)
- environmental requirements for carrying out conite construction and wall sheet panelling
- processes, procedures and techniques for carrying out conite construction and wall sheet panelling
- types and uses of tools and equipment for carrying out conite construction and wall sheet panelling
- types and uses of plans, drawings and specifications for carrying out conite construction and wall sheet panelling.

Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

This unit must be assessed in the workplace or a close simulation using realistic workplace conditions, materials, activities, responsibilities, procedures, safety requirements and environmental considerations.

Links

Companion volumes to this training package are available at the VETNet website -
<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>