



Australian Government

Assessment Requirements for CPCCWF3003 Install wall tiles

Release: 2

Assessment Requirements for CPCCWF3003 Install wall tiles

Modification History

Release 2 Updated reference to general construction induction training program.

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0.

Supersedes and equivalent to CPCCWF3003A Fix wall tiles. Change to title.
Updated to meet the Standards for Training Packages 2012.

Performance Evidence

To demonstrate competency, a candidate must satisfy all of the elements, performance criteria and foundation skills of this unit by preparing the substrate and tiling a minimum of:

- the front and surrounds of a bath, at least 1500 millimetres long
- four square metres of wall that includes a door opening and a niche
- one lineal metre mitred hob
- one lineal metre trim installed to an external corner.

All work must be performed to the standard required in the workplace and must comply with Commonwealth and state/territory laws and regulations, Australian Standards, work health and safety (WHS) and environmental requirements, manufacturers' specifications and workplace requirements.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of Australian Standards for installing wall tiles
- workplace quality policies and standards for installing wall tiles
- safety requirements for installing wall tiles, including:
 - job safety analyses and/or safe work method statements in accordance with Safe Work Australia *Code of Practice for Construction Work* or state and/or territory equivalent
 - personal protective equipment (PPE)
- environmental requirements for installing wall tiles
- placement and design of movement joints
- types and uses of materials storage and environmentally friendly waste management
- plans, drawings and specifications for installing wall tiles
- types and uses of tools and equipment for installing wall tiles
- processes for calculation of material requirements for installing wall tiles
- techniques in installing tiles to walls and corners:

- preparation of structures and substrates
- types of substrates
- types and uses of waterproofing systems
- cutting and installing types of tiles in common use:
 - large format tiles
- tiling material qualities, characteristics, preparation requirements, techniques, applications and limitations:
 - adhesive types and classifications
 - grout types, including epoxy grout.

Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

This unit must be assessed in the workplace or a close simulation using realistic workplace conditions, materials, activities, responsibilities, procedures, safety requirements and environmental considerations.

Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>