



Australian Government

CPCPRE2002 Remove temporary supports from prefabricated concrete elements

Release: 1

CPCPRE2002 Remove temporary supports from prefabricated concrete elements

Modification History

Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 9.0.
Newly created unit.

Application

This unit of competency specifies the skills and knowledge required to remove temporary bracing and propping supports from prefabricated concrete elements. It requires using appropriate tools, equipment, materials and working in a team environment to remove temporary supports.

A person who has achieved this unit of competency would be expected to follow safety regulations and relevant specifications.

Completion of the general construction induction training program, specified in the Safe Work Australia model Code of Practice: Construction Work, is required by anyone carrying out construction work. Achievement of CPCWHS1001 Prepare to work safely in the construction industry meets this requirement.

Licensing, legislative, regulatory or certification requirements apply to this unit of competency in some states and territories. For further information, check with the relevant regulatory authority.

Pre-requisite Unit

CPCCWHS2001 Apply WHS requirements policies and procedures in the construction industry

Unit Sector

Prefabricated concrete

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

1. Access the requirements to remove temporary

1.1 Check the erection design documentation, review task specifications and seek written approval of the project design engineer for the removal of temporary supports

- | | | |
|--|-----|---|
| supports from prefabricated concrete elements. | | from relevant personnel. |
| | 1.2 | Review work health and safety (WHS) requirements for the task in accordance with safety plans and policies. |
| | 1.3 | Conduct working at heights risk assessment and follow appropriate WHS processes. |
| | 1.4 | Identify safety signage and barricade requirements. |
| | 1.5 | Review environmental requirements for the task in accordance with environmental plans and legislative requirements. |
| | 1.6 | Access plant, tools and equipment required to carry out task. |
| | 1.7 | Verify the location of prefabricated concrete elements in accordance with design documentation. |
| 2. Prepare to remove temporary supports from prefabricated concrete elements. | 2.1 | Erect identified safety signage and barricade requirements, and fit personal protective equipment (PPE). |
| | 2.2 | Obtain plant, tools, equipment, check for serviceability and rectify or report any faults. |
| | 2.3 | Ensure the structural work is complete and that written approval from the in-service design engineer has been obtained so that removal of temporary supports can commence. |
| 3. Conduct the removal of temporary supports from prefabricated concrete elements. | 3.1 | Review the approved removal plan and access information on job sequencing and team roles. |
| | 3.2 | Assemble and erect lifting/handling devices for movement of loads. |
| | 3.3 | Follow load slinging and shifting requirements and conduct removal activity in accordance with erection design documentation, job safety and environmental analysis (JSEA) and safe work method statement (SWMS). |
| | 3.4 | Maintain stability of the braces and props during lifting and transportation. |

- 3.5 Systematically remove braces and associated parts from prefabricated concrete elements and footings in accordance with the erection design documentation, the JSEA and SWMS.
 - 3.6 Systematically dismantle and remove props and associated parts from prefabricated concrete elements in accordance with the erection design documentation, the JSEA and SWMS.
- 4. Clean up.
 - 4.1 Clear work area and dispose of, reuse or recycle materials in accordance with regulatory and workplace requirements.
 - 4.2 Clean, check, maintain and store tools and equipment in accordance with manufacturer and workplace requirements.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

No equivalent unit.

Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>

Assessment Requirements for CPCPRE2002 Remove temporary supports from prefabricated concrete elements

Modification History

- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 9.0.
Newly created unit.

Performance Evidence

To demonstrate competency, a candidate must meet the elements and performance criteria of this unit by:

- removing bracing and propping supports from two prefabricated concrete elements one of which must be a prefabricated concrete wall panel element of a height not less than 7 metres and width 3 metres.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of codes and Australian Standards relevant to joint caulking of prefabricated concrete elements:
 - AS 3850.1, 2 & 3 Prefabricated concrete elements
 - environmental protection and waste disposal
- work health and safety (WHS) regulations, including:
 - Safe Work Australia 'Guide to managing risk in construction: prefabricated concrete' 2019
 - use of personal protective equipment (PPE) as specified on the safety data sheet (SDS)
 - risk when working at heights/on ladders
 - fall protection
 - drop zones
 - hazardous substances
 - safe manual handling techniques
- faulty manufacturing and concrete defects which could compromise the strength of the prefabricated elements and pose a potential safety issue for lifting and handling
- types of drawings and specifications used to interpret concrete installation requirements
- erection design documentation
- prefabricated concrete brace and prop specifications, including:
 - erection sequence

- orientation of prefabricated concrete elements
- bracing details, including type and angle
- requirement for erection brace and prop footings
- levelling shims
- drawings
- types of bracing, including:
 - single storey (drop-in) panel propping
 - double storey (spin-up) panel propping
 - panel to panel propping
 - beam propping
 - spandrels propping
 - column bracing
 - lateral bracing
 - end bracing
 - main bracing
 - knee bracing
 - deadman bracing
- associated brace parts, including:
 - bolts
 - anchors
 - knee braces
- types of propping, including:
 - single props (Acrow)
 - single frame
 - continuous frame
- associated prop parts, including:
 - scaffold
 - acrow props
 - frames
 - bolts
 - bracing
- types of concrete prefabricated elements, including:
 - panels
 - columns
 - beams
 - planks
 - stairs
 - barriers
- workplace requirements when working with prefabricated concrete elements:
 - cleaning up the work area

- maintaining and storing plant, labelling, tools and equipment
- adhering to manufacturer specifications
- reporting problems
- quality
- types of prefabricated concrete elements
- fire rating requirements relevant to prefabricated concrete elements
- workplace procedures related to communication protocols
- principles of sustainability relevant to material reuse
- work planning and logical task sequencing
- types, characteristics and limitations of tools, equipment and materials required for propping and bracing prefabricated concrete elements, including:
 - chain slings
 - flexible steel wire rope (FSWR) slings
 - air winches
 - chain blocks
 - chain blocks
 - drifts
 - eye bolts
 - hammers
 - jacks
 - podgers
 - pulley blocks
 - shackles
 - spanners
 - spirit levels and automatic levels
 - tape measures
 - trolleys
 - turn buckles
 - wedges
 - wrenches.

Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

Assessment must be conducted in the workplace or a simulated workplace using realistic conditions, materials, activities, responsibilities, procedures, safety requirements and environmental considerations.

Candidates must have access to erection design documentation, materials, plant, manufacturer specifications, tools and equipment required to achieve the performance evidence.

Links

Companion volumes to this training package are available at the VETNet website -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>