



Australian Government

CPCPRE2003 Grout prefabricated concrete elements

Release: 1

CPCPRE2003 Grout prefabricated concrete elements

Modification History

- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 9.0.
Newly created unit.

Application

This unit of competency specifies the skills and knowledge required to grout load bearing and non-load bearing prefabricated concrete elements according to specified requirements.

It requires using tools and equipment appropriate for grouting.

A person who has achieved this unit of competency would be expected to apply grouting techniques to load bearing and non-load bearing vertical and horizontal joints between prefabricated concrete elements.

Completion of the general construction induction training program, specified in the Safe Work Australia model Code of Practice: Construction Work, is required by anyone carrying out construction work. Achievement of CPCWHS1001 Prepare to work safely in the construction industry meets this requirement.

Licensing, legislative, regulatory or certification requirements apply to this unit of competency in some states and territories. For further information, check with the relevant regulatory authority.

Pre-requisite Unit

- CPCCWHS2001 Apply WHS requirements policies and procedures in the construction industry
- CPCCCM2012 Work safely at heights

Unit Sector

Prefabricated Concrete

Elements and Performance Criteria

Elements describe the essential outcomes.

Performance criteria describe what needs to be done to demonstrate achievement of the element.

- | | | |
|---|-----|--|
| 1. Access requirements to grout prefabricated | 1.1 | Review and clarify grouting task and accessibility to enable the grouting to be placed in accordance with the erection prefabricated design documentation and material |
|---|-----|--|

concrete elements.		data sheets.
	1.2	Review erection design documentation for task specifications and check to make sure they are in accordance with regulations, standards and codes of practice.
	1.3	Review work health and safety (WHS) requirements for the task in accordance with safety plans and policies.
	1.4	Identify safety signage and barricade requirements.
	1.5	Review environmental requirements for the task in accordance with environmental plans and legislative requirements.
	1.6	Access plant, tools, equipment and materials required to carry out task.
	1.7	Locate the joints and confirm safety requirements, including working aloft, fall protection
2. Prepare to grout prefabricated concrete elements.	2.1	Erect identified safety signage and barricade requirements, and fit personal protective equipment (PPE).
	2.2	Obtain plant, tools, equipment, check for serviceability and rectify or report any faults.
	2.3	Identify materials and associated quantities/measurements required for grouting according to specifications and material data sheets.
	2.4	Review the erection design documentation and the material data sheets and check if removal of shims or levelling packers are required after initial grouting has cured.
	2.5	Review the erection design documentation and the material data sheets to verify which gaps are to be grouted.
3. Mix dry pack or trowelable grout.	3.1	Check the erection design documentation and the material data sheets to confirm compliance with compressive and tensile strength grout requirements.

- 3.2 Establish the volume of dry pack grout required and mix in accordance with specifications and material data sheet to ensure it is the desired consistency.
- 4. Mix flowable grout.
 - 4.1 Establish the volume of flowable grout required and mix in accordance with specifications and material data sheet to ensure it is the desired consistency so as to be free flowing and bleed from grout breathers and/or flow tubes.
 - 4.2 Check that all grout tubes, breathers and areas to be grout filled are clear and free from debris, contaminants and/or loose materials.
 - 4.3 Check the grout mixture for the desired consistency and flow property and adjust accordingly in accordance with the erection design documentation and the material data sheets.
- 5. Prepare prefabricated concrete joint and apply grouting.
 - 5.1 Ensure that all prefabricated concrete joint surfaces are prepared in accordance with the specifications and material data sheets.
 - 5.2 Ensure all surfaces are clean, sound and free from dust, oils or other contaminants.
 - 5.3 Prepare the grouting surface in accordance with the erection design documentation and the material data sheets.
 - 5.4 Seal perimeter of the area to be grouted in accordance with specifications.
 - 5.5 Apply grout in accordance with the project specifications.
 - 5.6 Ensure that dry pack or trowelable grout is placed in a manner that ensures consolidation by tamping/rodding to eliminate any air voids.
 - 5.7 Once complete, compare the actual volume of grout to the calculated volume of grout required to ensure no blockage and/or air voids have formed.

- 6. Clean up.
 - 6.1 Clear work area and dispose of, reuse or recycle materials in accordance with regulatory and workplace requirements.
 - 6.2 Clean, check, maintain and store tools and equipment in accordance with manufacturer and workplace requirements.

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Unit Mapping Information

No equivalent unit.

Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=6f3f9672-30e8-4835-b348-205dfcf13d9b>

Assessment Requirements for CPCPRE2003 Grout prefabricated concrete elements

Modification History

- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 9.0.
Newly created unit.

Performance Evidence

To demonstrate competency, a candidate must meet the elements and performance criteria of this unit by:

- grouting two prefabricated concrete elements, either horizontal or vertical including:
 - grouting a 25 mm gap below a 150 mm thick prefabricated concrete element for a length of 3 m, using dry-pack or trowelable grout, and
 - grout filling 3 grout tubes within a prefabricated concrete element, each being at least 50 mm diameter x 500 mm high, using flowable grout.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- compliance requirements of legislation, regulations, codes and Australian Standards relevant to grouting of prefabricated concrete elements, including:
 - environmental protection and waste disposal
 - work health and safety (WHS) regulations, including:
 - use of personal protective equipment (PPE)
 - fall protection
 - drop zones
 - hazardous substances
 - safe manual handling techniques
 - respirable crystalline silica
- erection design documentation
- material data sheets
- effects of temperature, wind and low humidity on the properties of prefabricated concrete:
 - detrimental effect of water addition to concrete properties
 - precautions that should be taken to minimise any potential adverse effects when finishing concrete
- health risks associated with silica dust exposure

- types of drawings and specifications used to interpret concrete installation requirements
- characteristics of grouting materials and the difference between grouting materials properties, including:
 - dry pack
 - plastic
 - trowelable
 - flowable
- grouting process, including:
 - use of anchor bolts in preformed pockets
 - formwork installation
 - pre-soaking the substrate when using cement-based grout
 - use of suitable equipment to mix the grout to dry pack or trowelable consistency
 - shrinkage
 - placement of grout
 - curing and protecting the grout to prevent loss of moisture which could lead to shrinkage and loss of strength
- grouting requirements, including:
 - use of pre-packaged, dry powder blend of cements, graded fillers and chemical additives of proprietary grout
 - mixing with clean water to required consistency according to manufacturer specifications
 - fluid consistency for application
- grouting tool types and their purpose, including:
 - wire brush
 - soft brush
 - scraper
 - sander/grinder
 - spatula
 - roller
 - putty knife
 - grouting gun
 - power leads
 - testing equipment (moisture meter)
- workplace requirements for grouting prefabricated concrete elements:
 - cleaning up the work area
 - maintaining and storing plant, labelling, tools and equipment
 - reporting problems
 - quality
- terminology used for grouting
- specifications used for grouting
- fire rating requirements relevant to prefabricated concrete element rectification

- workplace procedures related to communication protocols
- problems associated with the use of donuts
- principles of sustainability relevant to material reuse
- work planning and logical task sequencing
- types of concrete surface variables that reduce optimal sealant adhesion
- prefabricated concrete release agent residue
- laitance
- dirt and dust
- processes for calculating material measurements and quantities.

Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

Assessment must be conducted in the workplace or a simulated workplace using realistic conditions, materials, activities, responsibilities, procedures, safety requirements and environmental considerations.

Candidates must have access to erection design documentation, material data sheets, materials, manufacturer specifications, plant, tools and equipment required to achieve the performance evidence.

Links

Companion volumes to this training package are available at the VETNet website - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=6f3f9672-30e8-4835-b348-205dfcf13d9b>