



Australian Government

Assessment Requirements for CPCSH3009 Demolish shopfronts and bulkheads

Release: 3

Assessment Requirements for CPCSH3009 Demolish shopfronts and bulkheads

Modification History

- Release 3 Updated reference to general construction induction training program.
- Release 2 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.1.
Performance Criteria numbering rectified and Modification History rectified.
- Release 1 This version first released with CPC Construction, Plumbing and Services Training Package Release 5.0
Supersedes and is equivalent to CPCSH3009 Demolish shopfronts and bulkheads.

Performance Evidence

To demonstrate competency, a candidate must meet the performance criteria of this unit by dismantling and demolishing a shopfront and internal cabinet.

In doing this, the candidate must:

- dismantle and demolish a shopfront of a minimum of 3.6 metres high and 3.6 metres wide, including a bulkhead, glazing, door closure and joinery
- dismantle one internal cabinet or fixture of a minimum of 3.6 metres high and 2.4 metres wide, which is attached to the building structure
- protect surrounding structure, floor covering, existing furniture and fixtures from damage
- plan and schedule the demolition work to maintain continuity of business operations.

Knowledge Evidence

To be competent in this unit, a candidate must demonstrate knowledge of:

- shopfitting regulations, codes and standards relating to shopfront and bulkhead demolition
- organisation's quality assurance requirements relating to demolition of shopfronts and bulkheads
- sustainable shopfitting practices
- construction and demolition terminology used in shopfitting
- content of and terms, symbols and conventions used in working drawings and specifications
- characteristics, applications and limitations of materials used in shopfitting components:
 - acrylic

- glass
- laminates
- manufactured board
- solid timber
- procedures and techniques relevant to demolishing shopfronts:
 - calculating volumes of material for removal
 - non-load-bearing external walls
 - suspended ceilings
 - shopfronts and glazed sections
 - joinery and fixtures
 - high-level bulkheads
 - maintaining operation of existing services
- workplace safety:
 - job safety and environmental analysis (JSEA)
 - safe work method statements (SWMSs)
 - hierarchy of control
 - how to identify potential hazards
 - safety data sheets (SDSs)
 - hazardous manual tasks
 - exposure to excessive noise
 - removal of asbestos
 - exposure to dust
 - hazardous substances:
 - lead
 - fibreglass
 - working at heights
 - falling objects
 - vibration
 - electrical safety
 - emergency procedures (evacuation, location and use of firefighting equipment, first aid)
 - safety of public, visitors and others in the workplace
- functional and operational features of tools and equipment:
 - air compressors and pneumatic tools
 - angle grinders
 - elevated work platforms (EWPs)
 - scaffolding
 - power saws
 - power drills.

Assessment Conditions

Assessors must meet the requirements for assessors contained in the Standards for Registered Training Organisations.

Assessment must be conducted in the workplace or a simulated workplace using realistic conditions, materials, activities, responsibilities, procedures, safety requirements and environmental considerations.

Candidates must have access to:

- relevant shopfitting regulations, codes and Australian Standards
- current workplace procedures, workplace safety and environmental documentation relating to demolition
- shopfitting drawings and specifications, organisational policies, procedures and equipment to undertake the performance criteria and assessment requirements
- digital technology, devices and software to communicate with others and to develop and save documents electronically.

Links

Companion volumes to this training package are available at the VETNet website -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=7e15fa6a-68b8-4097-b099-030a5569b1ad>