



Australian Government

Department of Education, Employment and Workplace Relations

CPCCCO2003A Carry out concreting to simple forms

Release: 1

Modification History

Not Available

INTRODUCTION

Unit descriptor This unit of competency specifies the outcomes required to safely install formwork, reinforcement and place and finish concrete for the construction of minor slabs, pathways and other minor works to a specified design finish.

The unit includes positioning the truck, placing concrete from truck to work area, spreading concrete and cleaning up site.

Employability skills This unit contains employability skills.

Prerequisite units CPCCOHS1001A - Work safely in the construction industry

Co-requisite units This unit of competency supports the attainment of the understanding and skills to use concrete tools, equipment and materials with simple forms, which may include working with others and as a member of a team.

Application of the unit This unit of competency supports the attainment of the understanding and skills to use concrete tools, equipment and materials with simple forms, which may include working with others and as a member of a team.

Functional Area

Unit Sector Construction

ELEMENT

PERFORMANCE CRITERIA

Elements describe the essential outcomes of a unit of competency

Performance criteria describe the performance needed to demonstrate achievement of the element. Where bold italicised text is used, further information is detailed in the required skills and knowledge section and the range statement. Assessment of performance is to be consistent with the evidence guide.

- | | |
|----------------------------------|--|
| Plan and prepare | <ul style="list-style-type: none">• Work instructions and operational details are obtained using relevant information , confirmed and applied for planning and preparation purposes.• Safety (OHS) requirements are followed in accordance with safety plans and policies.• Signage and barricade requirements are identified and implemented.• Plant, tools and equipment selected to carry out tasks are consistent with the requirements of the job, checked for serviceability and any faults are rectified or reported prior to commencement.• Materials quantity requirements are calculated in accordance with plans, specifications and quality requirements .• Materials appropriate to the work application are identified, obtained, prepared, safely handled and located ready for use.• Environmental requirements are identified for the project in accordance with environmental plans and regulatory obligations and applied.• |
| Erect and strip simple formwork. | <ul style="list-style-type: none">• Subgrade is prepared.• Formwork design is identified from drawings.• Formwork is erected safely on commencement.• Form release agent is applied to erected formwork where specified.• Timber components are de-nailed following stripping of formwork.• Components are cleaned, stacked and stored for reuse or bundled for removal.• Formwork components are removed from site.• |
| Place and tie reinforcement. | <ul style="list-style-type: none">• Reinforcing components are handled and positioned safely.• Reinforcing bars and mesh are positioned.• Bar chairs and spacers are positioned, with minimum edge cover.• |
| Place concrete | <ul style="list-style-type: none">• Formwork or excavation is cleaned of excess material and debris prior to concrete placement.• Concrete is safely transported by wheelbarrow.• Pump line/chute is controlled and concrete placed.• Concrete is placed in formwork to specified depth.• Concrete is screeded to the alignment of formwork and project specified datums.• Surface of concrete is finished in accordance with specifications.• |

Clean up.

- Work area is cleared and materials disposed of, reused or recycled in accordance with legislation, regulations and codes of practice and job specification.
- Plant, tools and equipment are cleaned, checked, maintained and stored in accordance with manufacturer recommendations and standard work practices.
-

REQUIRED SKILLS AND KNOWLEDGE

This section describes the skills and knowledge required for this unit.

Required skills	Required skills for this unit are: • communication skills to: • evaluating own actions and making judgments about performance and necessary improvements • identifying and accurately reporting to appropriate personnel any faults in tools, equipment or materials • organisational skills, including the ability to plan and set out work • recognising procedures, following instructions, responding to change and contributing to workplace responsibilities, such as current work site environmental and sustainability frameworks or management systems • teamwork skills to coordinate own work with others to action tasks and relate to people from a range of cultural and ethnic backgrounds and with varying physical and mental abilities • technological skills to: • determine requirements • enable clear and direct communication, using questioning to identify and confirm requirements, share information, listen and understand • follow instructions • read and interpret: • report faults • use language and concepts appropriate to cultural differences • use and interpret non-verbal communication, such as hand signals • documentation from a variety of sources • drawings and specifications • use a range of mobile technology, such as two-way radio and mobile phones • voice and hand signals to access and understand site-specific instructions
Required knowledge	Required knowledge for this unit is: • concrete materials • concreting techniques • general construction terminology • job safety analysis (JSA) and safe work method statements • levelling techniques • material safety data sheets (MSDS) • materials storage and environmentally friendly waste management

- plans, drawings and specifications
- processes for the calculation of material requirements
- quality requirements
- simple formwork and reinforcing componentry
- types, characteristics, uses and limitations of plant, tools and equipment
- workplace and equipment safety requirements.
-

RANGE STATEMENT

The range statement relates to the unit of competency as a whole. It allows for different work environments and situations that may affect performance. Bold italicised wording, if used in the performance criteria, is detailed below. Essential operating conditions that may be present with training and assessment (depending on the work situation, needs of the candidate, accessibility of the item, and local industry and regional contexts) may also be included.

Information includes:

- diagrams or sketches
- instructions issued by authorised organisational or external personnel
- manufacturer specifications and instructions, where specified
- MSDS
- memos
- regulatory and legislative requirements pertaining to concreting
- relevant Australian standards
- safe work procedures relating to concreting
- signage
- verbal, written and graphical instructions
- work bulletins
- work schedules, plans and specifications
-

Planning and preparation include:

- assessment of conditions and hazards
- determination of work requirements and safety plans and policies
- equipment defect identification
- work site inspection
-

Safety (OHS) is to be in accordance with state and territory legislation and regulations and project safety plan and may include:

- emergency procedures, including extinguishing fires, organisational first aid requirements and evacuation
- handling activities that may require the assistance of others or the use of manual or mechanical lifting devices where size, weight or other issues, such as a disability are a factor
- hazard control
- hazardous materials and substances
- organisational first aid
- PPE prescribed under legislation, regulations and workplace policies and practices

- safe operating procedures, including the conduct of operational risk assessment and treatments associated with:
- use of firefighting equipment
- use of tools and equipment
- workplace environmental requirements and safety.
 - earth leakage boxes
 - lighting
 - power cables, including overhead service trays, cables and conduits
 - restricted access barriers
 - surrounding structures
 - traffic control
 - trip hazards
 - work site visitors and the public
 - working at heights
 - working in confined spaces
 - working in proximity to others

Tools and equipment :

-
- include:
- may include:
 - brooms
 - chutes
 - edging tools
 - shovels
 - trowels
 - wheelbarrows
 - bull floats
 - hand floats
 - kibbles
 - line pumps
 - stipple devices
 - trowelling machines.

Quality requirements include:

-
- internal company quality policy and standards
- manufacturer specifications where specified
- relevant regulations, including Australian standards
- workplace operations and procedures.

Materials :

-
- include:

- may include reinforcing bars.
 - bar chairs
 - bracing
 - edge form/boards
 - fabric sheet mesh
 - pegs
 - spacers
-
- Environmental requirements include
 - clean-up management
 - dust and noise
 - stormwater management
 - vibration
 - waste management.
-
- Simple formwork includes:
 - timber or steel edge form to a maximum of 100mm in depth.
-
- Simple reinforcing :
 - includes:
 - may include:
 - bar chairs
 - fabric sheet mesh
 - spacers
 - reinforcing bars
 - trench mesh.
-
- Simple forms of concrete :
 - include slabs (not requiring internal beams and piers)
 - may include:
 - beam thickeners
 - channels
 - garden edges
 - pathways
 - post holes
 - simple concrete aprons.
-
- Concreting includes:
 - finishing of concrete
 - floating of the concrete
 - placing of concrete
 - screeding, limited to include a hand screed.
-

Placing of concrete involves movement of concrete from the truck to the work and:

- includes:
- may include:
 - chutes
 - wheelbarrows
 - kibbles
 - pump lines.

Finishing of concrete includes:

-
- broomed
- hand floating
- power floating
- sponged
- stipple device finish
- trowelled
- trowelling machine finish
- wood floated
- other project specified finish.
-

EVIDENCE GUIDE

The evidence guide provides advice on assessment and must be read in conjunction with the performance criteria, required skills and knowledge, range statement and the Assessment Guidelines for the Training Package.

Overview of assessment	This unit of competency could be assessed in the workplace or a close simulation of the workplace environment, provided that simulated or project-based assessment techniques fully replicate construction workplace conditions, materials, activities, responsibilities and procedures.
Critical aspects for assessment and evidence required to demonstrate competency in this unit	A person who demonstrates competency in this unit must be able to provide evidence of the ability to: • locate, interpret and apply relevant information, standards and specifications • comply with site safety plan and OHS legislation, regulations and codes of practice applicable to workplace operations • comply with organisational policies and procedures including quality requirements • safely and effectively operate and use tools, plant and equipment • communicate and work effectively and safely with others • prepare subgrade; erect formwork; cut, place and tie reinforcement; place and hand screed concrete for a slab of (4 square metres is recommended) and a minimum depth of 100mm to the required finished level and job specification.
Context of and specific resources for assessment	This competency is to be assessed using standard and authorised work practices, safety requirements and environmental constraints. Assessment of essential underpinning knowledge will usually be conducted in an off-site context. Assessment is to comply with relevant regulatory or Australian standards' requirements. Resource implications for assessment include: • an induction procedure and requirement • realistic tasks or simulated tasks covering the mandatory task requirements • relevant specifications and work instructions • tools and equipment appropriate to applying safe work practices

- support materials appropriate to activity
- workplace instructions relating to safe work practices and addressing hazards and emergencies
- material safety data sheets
- research resources, including industry related systems information.

Reasonable adjustments for people with disabilities must be made to assessment processes where required. This could include access to modified equipment and other physical resources, and the provision of appropriate assessment support.

Method of assessment Assessment methods must:

- satisfy the endorsed Assessment Guidelines of the Construction, Plumbing and Services Integrated Framework Training Package
- include direct observation of tasks in real or simulated work conditions, with questioning to confirm the ability to consistently identify and correctly interpret the essential underpinning knowledge required for practical application
- reinforce the integration of employability skills with workplace tasks and job roles
- confirm that competency is verified and able to be transferred to other circumstances and environments.

Validity and sufficiency of evidence requires that:

- competency will need to be demonstrated over a period of time reflecting the scope of the role and the practical requirements of the workplace
- where the assessment is part of a structured learning experience the evidence collected must relate to a number of performances assessed at different points in time and separated by further learning and practice, with a decision on competency only taken at the point when the assessor has complete confidence in the person's demonstrated ability and applied knowledge
- all assessment that is part of a structured learning experience must include a combination of direct, indirect and supplementary evidence.

Assessment processes and techniques should as far as is practical take into account the language, literacy and numeracy capacity of the candidate in relation to the competency being assessed.

Supplementary evidence of competency may be obtained from relevant authenticated documentation from third parties, such as existing supervisors, team leaders or specialist training staff.

