



Australian Government

Assessment Requirements for MSFFL3051 Install timber flooring to joists

Release: 1

Assessment Requirements for MSFFL3051 Install timber flooring to joists

Modification History

Release 1. New unit

Performance Evidence

Evidence required to demonstrate competence in this unit must be relevant to and satisfy the requirements of the elements and performance criteria and include:

- following work instructions, SOPs and safe work practices
- identifying and interpreting specifications, drawings, standards and other relevant information to install timber flooring to joists
- complying with site safety plan, WHS regulations, state/territory legislation, and organisational policies and procedures, including quality requirements
- using tools, plant and equipment in a safe and effective manner
- completing a minimum of:
 - one (1) installation of 19 mm strip timber flooring direct to joists to a full sized one bedroom home or equivalent (including a bedroom, lounge, kitchen and bathroom not less than 30 sqm)
 - one (1) installation of a ply or reconstituted timber sheet product directly to joists to a full sized one bedroom home or equivalent (including a bedroom, lounge, kitchen and bathroom not less than 30 sqm)
 - one (1) installation of 19 mm decking direct to joists (not less than 30 sqm)
 - removal and replacement of a board in an existing timber floor direct on joists
- communicating and working effectively and safely with others.

Knowledge Evidence

Evidence required to demonstrate the required knowledge for this unit must be relevant to and satisfy the requirements of the elements and performance criteria and include knowledge of:

- safe work practices and procedures and use of PPE
- workplace and equipment safety requirements
- job safety analysis (JSA's)/safe work method statement (SWMS)
- quality requirements
- general timber flooring industry terminology
- plant, tools and equipment types, characteristics, uses and limitations
- timber flooring types, characteristics, uses and limitations
- setting out and levelling techniques
- timber flooring installation methods
- processes for the calculations of material requirements
- material safety data sheets (MSDS)
- plans, drawings and specifications
- materials handling, storage and environmentally friendly waste management

Assessment Conditions

- Assessors must:
 - satisfy the assessor competency requirements that are in place at the time of the assessment as set by the VET regulator
 - have vocational competency in installing timber flooring to joists at least to the level being assessed with relevant industry knowledge and experience
- Where possible assessment must occur in operational workplace situations. Where this is not possible or where personal safety or environmental damage are limiting factors, assessment must occur in a sufficiently rigorous simulated environment that reflects realistic operational workplace conditions that cover all aspects of workplace performance, including environment, task skills, task management skills, contingency management skills and job role environment skills.
- Conditions for assessment must include access to all tools, equipment, materials and documentation required, including relevant workplace procedures, product and manufacturing specifications.
- Assessment processes and techniques must be appropriate to the language, literacy and numeracy requirements of the work being performed and the needs of the candidate.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.education.gov.au/Pages/TrainingDocs.aspx?q=0601ab95-583a-4e93-b2d4-cfb27b03ed73>