



Australian Government

Assessment Requirements for MSFFL3088 Install timber flooring to joists

Release: 1

Assessment Requirements for MSFFL3088 Install timber flooring to joists

Modification History

Release 1. Supersedes and is equivalent to MSFFL3051 Install timber flooring to joists.

Performance Evidence

There must be evidence the candidate has completed the tasks outlined in the elements and performance criteria of this unit, and

- completed the following installations in accordance with job requirements:
 - 1 installation of 19 mm strip timber flooring direct to joists to an area of at least 30m², which includes at least 1 complete room
 - 1 installation of a ply or reconstituted timber sheet product directly to joists to an area of at least 30m², which includes at least 1 complete room.
 - 1 installation of 19 mm decking direct to joists (not less than 30 sqm)
 - removal and replacement of a board in an existing timber floor direct on joists.
 -

Knowledge Evidence

There must be evidence the candidate has knowledge of:

- mathematical procedures for estimation and measurement, including calculation of area and estimation of material requirements
- installation of timber flooring to joists:
 - Australian Standards requirements
 - workplace safety system requirements
 - work flow
 - environmental protection and sustainability requirements
 - how to access manufacturer instructions
 - how to interpret building plans and specifications
 - types, characteristics, uses and limitations of different timber flooring types, including:
 - strip timber flooring (19mm or thicker)
 - decking boards
 - plywood
 - particleboard
 - characteristics and requirements of sub
 - floor preparation
 - types, characteristics, uses and limitations of different adhesives, including:
 - polyurethane

- polymer
- types, characteristics, safe use, maintenance and limitations of tools, equipment and materials
- techniques for set out, laying and cutting and fixing, the types of problems that may occur and how to avoid and respond
- quality indicators for completed work
- procedures and protocols for the recording, reporting and maintenance of workplace records and information.
-

Assessment Conditions

Skills must have been demonstrated in the workplace or in a simulated environment that reflects workplace conditions and contingencies.

The following conditions must be met for this unit:

- use of suitable facilities, equipment and resources, including:
 - location requiring installation of timber flooring to joists
 - timber flooring
 - equipment, tools and materials to complete tasks in the Performance Evidence, including safety and personal protective equipment
 - work order
 - workplace procedures.

Assessors must satisfy the NVR/AQTF mandatory competency requirements for assessors.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=0601ab95-583a-4e93-b2d4-cfb27b03ed73>