



Australian Government

Assessment Requirements for MSFFL3111 Install commercial carpet

Release: 1

Assessment Requirements for MSFFL3111 Install commercial carpet

Modification History

Release 1. Supersedes and is equivalent to MSFFL3061 Install commercial carpet. Changes to application, elements and performance criteria to improve clarity and consistency across MSFFL units. Changes to assessment requirements.

Performance Evidence

There must be evidence the candidate has completed the tasks in the elements and performance criteria of this unit of competency and has demonstrated the ability to complete according to job instructions:

- at least three commercial carpet installations — where the subfloor has been adequately prepared — that include every one of the following at least once, in any combination:
 - carpet:
 - commercial woven carpet
 - commercial tufted carpet
 - areas:
 - an area containing at least two rooms connected by a common corridor
 - an area containing at least seven lineal metres of carpet in length that must be split and joined
 - an area with an obstacle that requires the carpet to be stretched up to it (such as a lift lobby, reception area or column)
 - three seam joins and three cross joins
 - a box step stairway with at least three steps including the installation of commercial-grade stair nosing
 - a kite winder treads stairway with at least three steps
 - a bullnose step.
 -

Knowledge Evidence

There must be evidence the candidate has knowledge of:

- manufacturer installation instructions and the relevant Australian standards for commercial carpet
- the safe and correct use of and maintenance requirements for tools and equipment including power stretchers for installing commercial carpet
- the safe and correct handling of heavy carpet loads
- the most common issues that can arise when installing commercial carpet and how to avoid and respond to them

- workplace policies and procedures relevant to their job role and responsibilities including for:
 - installing commercial carpet
 - communication and reporting
 - environmental protection and sustainability, including maximising resource utilisation and minimising waste
 - quality indicators for completed work and process improvements
 - work health and safety, including the use of personal protective equipment and safety data sheets
 - work planning
- how to identify if a subfloor is suitable for installing commercial carpet
- how to identify if carpet underlay, grippers and commercial carpet are installed correctly.
-

Assessment Conditions

Skills must have been demonstrated in the workplace or in a simulated environment that reflects workplace conditions and contingencies. The following conditions must be met for this unit:

- use of suitable facilities, equipment and resources, including:
 - locations in which to install commercial carpet and which already have underlay and grippers installed
 - commercial carpet
 - equipment and tools required for the activities set out in the elements and performance criteria, including those to control hazards
 - job instructions and workplace procedures.

Assessors must satisfy the NVR/AQTF mandatory competency requirements for assessors.

Links

Companion Volume implementation guides are found in VETNet – -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=0601ab95-583a-4e93-b2d4-cfb27b03ed73>