



Australian Government

Assessment Requirements for MSFFL3114 Install resilient tiles and planks

Release: 1

Assessment Requirements for MSFFL3114 Install resilient tiles and planks

Modification History

Release 1. Supersedes and is equivalent to MSFFL3065 Install resilient tiles. Changes to title, application, elements and performance criteria to improve clarity and consistency across MSFFL units. Changes to assessment requirements.

Performance Evidence

There must be evidence the candidate has completed the tasks in the elements and performance criteria of this unit of competency and has demonstrated the ability to complete according to job instructions:

- on a timber or concrete subfloor including cutting and fastening of the resilient tiles or planks:
 - at least one resilient tile and/or plank installation of connecting rooms using multi-directional patterns
 - at least one resilient tile and/or plank installation that includes a 45-degree set-out with borders
 - at least one resilient tile and/or plank installation that includes a custom design or feature strips.

Note: the above installations must include at least one resilient tile installation and one resilient plank installation.

Knowledge Evidence

There must be evidence the candidate has knowledge of:

- manufacturer installation instructions and the relevant Australian standards for resilient tiles and planks, including:
 - homogenous and heterogeneous
 - linoleum
 - rigid
 - rubber
 - semi-rigid
- manufacturer use instructions for adhesives for fastening resilient tiles and planks including:
 - double-sided tape
 - polyurethane contact adhesive
 - pressure sensitive and wet acrylic adhesive
 - two-part epoxy
 - water and solvent-based contact adhesive

- manufacturer installation instructions and the relevant Australian standards for finishing strips
- the safe and correct use of, and maintenance requirements for tools and equipment for, installing resilient tiles and planks
- the most common issues that can arise when installing resilient tiles and planks and how to avoid and respond to them
- workplace policies and procedures relevant to their job role and responsibilities including for:
 - installing resilient tiles and planks
 - communication and reporting
 - environmental protection and sustainability, including maximising resource utilisation and minimising waste
 - quality indicators for completed work and process improvements
 - work health and safety, including the use of personal protective equipment and safety data sheets
 - work planning
- how to identify if a subfloor is prepared, clean and otherwise suitable for installing resilient tiles and planks
- how to identify if resilient tiles and planks have been installed correctly.

Assessment Conditions

Skills must have been demonstrated in the workplace or in a simulated environment that reflects workplace conditions and contingencies. The following conditions must be met for this unit:

- use of suitable facilities, equipment and resources, including:
 - locations in which to install resilient tiles and planks
 - resilient tiles and planks, adhesives, finishing strips and other materials required by job instructions
 - equipment and tools required for the activities set out in the elements and performance criteria, including those to control hazards
 - job instructions and workplace procedures.

Assessors must satisfy the NVR/AQTF mandatory competency requirements for assessors.

Links

Companion Volume implementation guides are found in VETNet – -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=0601ab95-583a-4e93-b2d4-cfb27b03ed73>