



Australian Government

Assessment Requirements for MSFFL3115 Install commercial sheet vinyl flooring

Release: 1

Assessment Requirements for MSFFL3115 Install commercial sheet vinyl flooring

Modification History

Release 1. Supersedes and is equivalent to MSFFL3067 Complete large scale and complex vinyl flooring installations. Changes to title, application, elements and performance criteria to improve clarity and consistency across MSFFL units. Changes to assessment requirements.

Performance Evidence

There must be evidence the candidate has completed the tasks in the elements and performance criteria of this unit of competency and has demonstrated the ability to complete according to job instructions:

- at least four vinyl sheet flooring installations — two using heterogeneous vinyl sheet and two using homogeneous vinyl sheet — that cover at least once, in any combination:
 - all of the following installation types:
 - cove installation
 - flat installation
 - stair installations with a metal stair nosing
 - all of the following characteristics:
 - pencil cove
 - cove fillet
 - border cove
 - internal and external mitred corners
 - more than two widths of vinyl
 - hallway or passage with connecting room
 - all the following techniques:
 - trimming selvages
 - bar scribing
 - direct scribing
 - template scribing
 - under scribing
 - pattern matching
 - heat weld joins
 - cold (chemical) weld joins.
-

Knowledge Evidence

There must be evidence the candidate has knowledge of:

- the characteristics of box and recessed steps
- manufacturer installation instructions and the relevant Australian standards for vinyl sheet flooring including:
 - homogenous vinyl sheet
 - heterogeneous vinyl sheet (including encapsulated glass fibre)
- manufacturer use instructions for adhesives for fastening vinyl sheet flooring including:
 - water-based acrylic
 - two-part epoxy
 - two-part polyurethane
 - single pack polyurethane
 - water-based and solvent-based contact adhesive
- the safe and correct use of, and maintenance requirements for tools and equipment for, installing vinyl sheet flooring
- the most common issues that can arise when installing vinyl sheet flooring and how to avoid and respond to them
- workplace policies and procedures relevant to their job role and responsibilities including for:
 - installing vinyl sheet flooring
 - communication and reporting
 - environmental protection and sustainability, including maximising resource utilisation and minimising waste
 - quality indicators for completed work and process improvements
 - work health and safety, including the use of personal protective equipment and safety data sheets
 - work planning
- how to identify if a subfloor is suitable for installing vinyl sheet flooring
- how to identify if vinyl sheet flooring is installed correctly.
-

Assessment Conditions

Skills must have been demonstrated in the workplace or in a simulated environment that reflects workplace conditions and contingencies. The following conditions must be met for this unit:

- use of suitable facilities, equipment and resources, including:
 - locations in which to install vinyl sheet flooring
 - vinyl sheet flooring, adhesives and finishing, joining and other materials required by job instructions
 - equipment and tools required for the activities set out in the elements and performance criteria, including those to control hazards
 - job instructions and workplace procedures.

Assessors must satisfy the NVR/AQTF mandatory competency requirements for assessors.

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=0601ab95-583a-4e93-b2d4-cfb27b03ed73>