



Australian Government

RIICCM211D Erect and dismantle temporary fencing and gates

Release: 3

RIICCM211D Erect and dismantle temporary fencing and gates

Modification History

Release	Comment
1	This unit replaces RIICCM211A Erect and dismantle temporary fencing and gates.
2	Editorial corrections.
3	Required frequency and volume of evidence amended in Performance evidence. Substantial amendments made in Assessment Conditions field, including: references to Industry Sectors, assessor and subject matter expert experience requirements, how assessment should be conducted and what it should confirm.

Application

This unit describes a participant's skills and knowledge required to erect and dismantle temporary fencing and gates in Civil Construction.

This unit is appropriate for those working in operational roles.

Licensing, legislative, regulatory and certification requirements that apply to this unit can vary between states, territories, and Industry sectors. Relevant information must be sourced prior to application of the unit.

Unit Sector

Civil construction

Elements and Performance Criteria

1. Plan and prepare for erecting and dismantling temporary fencing and gates	1.1 Access, interpret and apply temporary fencing and gates documentation, and ensure the work activity is compliant 1.2 Obtain, read, interpret, clarify and confirm work requirements 1.3 Identify and address potential risks, hazards and environmental issues, and implement control measures 1.4 Select and wear personal protective equipment appropriate for work activities 1.5 Identify, obtain and implement traffic signage requirements 1.6 Select, and check for faults, equipment and/or attachments for work activities
--	---

	1.7 Obtain and interpret emergency procedures, and be prepared for fire/accident/emergency
2. Erect fencing	2.1 Set out fence line and anchoring structure positions 2.2 Erect fence posts in place and plumb to alignment 2.3 Fix fence rails and cladding/mesh to posts 2.4 Finish fencing to completed construction requirements
3. Erect gates and signage	3.1 Fit and secure gates 3.2 Install signage at entry gates
4. Remove and make good	4.1 Dismantle gates and fencing and remove from site 4.2 Make area good to work specification
5. Conduct housekeeping activities	5.1 Clear work area and dispose of or recycle materials 5.2 Clean and maintain condition of equipment, ensure suitability for use, and address/report issues 5.3 Manage/report hazards, and maintain a safe working environment 5.4 Process written records

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit. Further information is available in the Resources and Infrastructure Industry Training Package Companion Volume.

Unit Mapping Information

RIICCM211A Erect and dismantle temporary fencing and gates

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272>

Assessment Requirements for RIICCM211D Erect and dismantle temporary fencing and gates

Modification History

Release	Comment
1	This unit replaces RIICCM211A Erect and dismantle temporary fencing and gates.
2	Editorial corrections.
3	Required frequency and volume of evidence amended in Performance evidence. Substantial amendments made in Assessment Conditions field, including: references to Industry Sectors, assessor and subject matter expert experience requirements, how assessment should be conducted and what it should confirm.

Performance Evidence

Evidence is required to be collected that demonstrates a candidate's competency in this unit. Evidence must be relevant to the roles within this sector's work operations and satisfy all of the requirements of the performance criteria of this unit and include evidence that the candidate:

- locates and applies applicable documentation, policies and procedures
- implements the requirements, procedures and techniques for the safe, effective and efficient completion of the erection and dismantling of temporary fencing and gates including:
 - selecting and using relevant tools/equipment
 - using fencing construction systems
 - using anchoring systems
 - communicating effectively to clarify work/plans/specifications
- works effectively with others to undertake and complete the erection and dismantling of temporary fences and gates in a way that meets all of the required outcomes including:
 - using a range of communications techniques and equipment to convey information to others
 - complying with written and verbal reporting requirements and procedures
- demonstrates completion of erecting and dismantling temporary fencing and gates that safely, effectively and efficiently meets all of the required outcomes on more than one (1) occasion including:
 - completion of the erection and dismantling of temporary fencing to enclose an area of at least 100m² including at least one (1) gate to specifications

Knowledge Evidence

The candidate must demonstrate knowledge of the following when erecting and dismantling temporary fencing and gates:

- accessing, interpreting and applying the organisation and site requirements and procedures for:
 - using JSAs/JSEA/safe work methods
 - achieving project quality outcomes
 - identifying and reporting on hazards related to the worksite and work activity
 - applying materials handling methods and using safety data sheets
- organising work activities
- using relevant tools and equipment safely
- equipment types, characteristics, technical capabilities and limitations
- site safety and security isolation techniques
- site isolation and traffic control responsibilities and authorities
- using civil construction terminology
- different fencing and anchoring systems
- completing housekeeping activities

Assessment Conditions

- An assessor of this unit must satisfy the requirements of the NVR/AQTF or their successors; and Industry regulations for certification and licensing; and,
- this unit is best assessed in the context of this sector's work environment;
- where personal safety or environmental damage are limiting factors, assessment may occur in a simulated environment provided it is realistic and sufficiently rigorous to cover all aspects of this sector's workplace performance, including environment, task skills, task management skills, contingency management skills and job role environment skills; and,
- this unit must be assessed in compliance with relevant legislation/regulation and using policies, procedures, processes and operational manuals directly related to the industry sector for which it is being assessed; and,
- assessment may be conducted in conjunction with the assessment of other Units of Competency; and,
- assessment must confirm consistent performance can be applied in a range of relevant workplace circumstances; and,
- assessors must demonstrate the performance evidence, and knowledge evidence as outlined in this Unit of Competency, and through the minimum years of current* work experience specified below in an Industry sector relevant to the outcomes of the unit; or,
- where the assessor does not meet experience requirements a co-assessment or partnership arrangement must exist between the qualified assessor and an Industry subject matter expert. The Industry subject matter expert should hold the unit being assessed (or an equivalent unit) and/or demonstrate equivalence of skills and knowledge at the unit level. An Industry technical expert must also demonstrate skills and knowledge from the minimum years of current work experience specified below in the Industry sector, including time spent in roles related to the unit being assessed; and,

- assessor and Industry subject matter expert requirements differ depending on the Australian Qualifications Framework Level (AQF) of the qualification being assessed and/or Industry Sector as follows:

Industry sector	AQF** Level	Required assessor or Industry subject matter expert experience
Drilling, Metalliferous Mining, Coal Mining, Extractive (Quarrying) and Civil Construction	1	1 Year
	2	2 Years
Drilling, Coal Mining and Extractive (Quarrying)	3-6	3 Years
Metalliferous Mining and Civil Construction	3-6	5 Years
Other sectors	Where this Unit is being assessed outside of the Resources and Infrastructure Sectors assessor and/or Industry subject matter expert experience should be in-line with industry standards for the sector in which it is being assessed and where no Industry standard is specified should comply with any relevant regulation.	

*Assessors can demonstrate current work experience through employment within Industry in a role relevant to the outcomes of the Unit; or, for external assessors this can be demonstrated through exposure to Industry by conducting frequent site assessments across various locations.

**Where a unit is being delivered outside of a Qualification the first numeric character in the Unit code should be considered to indicate the AQF level

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272>