



Australian Government

RIICPL305E Install pre-cast access chambers

Release: 1

RIICPL305E Install pre-cast access chambers

Modification History

Release	Comments
Release 1	This version first released with RII Resources and Infrastructure Industry Training Package Version 6.0.

Application

This unit describes the skills and knowledge required to install pre-cast access chambers in civil construction. This includes determining location and positioning of access chambers, installing the main components of the pre-cast unit, sealing finished surface by rendering and attaching auxiliary components or modifications to the pre-cast unit.

It applies to those working in operational roles. They generally work under minimal supervision to undertake a broad range of tasks in varied work contexts, using some discretion and judgement in selecting equipment, services or contingency measures.

Licensing, legislative and certification requirements that apply to this unit can vary between states, territories, and industry sectors. Users must check requirements with relevant body before applying the unit.

Unit Sector

Civil Construction

Elements and Performance Criteria

ELEMENT	PERFORMANCE CRITERIA
<i>Elements describe the essential outcomes.</i>	<i>Performance criteria describe the performance needed to demonstrate achievement of the element.</i>
1. Plan and prepare to install pre-cast access chambers	1.1 Obtain, interpret, clarify and confirm work plans and specifications requirements 1.2 Access, interpret and apply documentation required to install pre-cast access chambers and confirm work activity is compliant 1.3 Confirm and identify requirements for complying with environmental protection, safety and traffic management signage requirements 1.4 Select equipment and tools required for work activities and check for faults 1.5 Select and wear personal protective equipment according to site

ELEMENT	PERFORMANCE CRITERIA
	requirements 1.6 Identify and address potential risks, hazards and environmental issues, and implement control measures within scope of own role 1.7 Obtain and interpret emergency procedures and identify steps required to respond to emergencies
2. Install access chambers	2.1 Advise plant operator of excavation and base preparation requirements 2.2 Determine location and positioning of access chamber according to job requirements 2.3 Set out work area to design specifications 2.4 Control ingress of water by dewatering 2.5 Position, fabricate or install main components of the pre-cast unit according to job requirements 2.6 Seal by rendering finished surface where specified 2.7 Position auxiliary components or modifications and attach to pre-cast unit according to job requirements 2.8 Inspect and repair new and existing access chambers according to job requirements
3. Conduct clean-up activities	3.1 Clear work area and dispose of or recycle materials according to site requirements 3.2 Clean, check, perform maintenance on and store plant, tools and equipment according to manufacturer specifications and site requirements

Foundation Skills

This section describes those language, literacy, numeracy and employment skills that are essential to performance but not explicit in the performance criteria.

Skill	Description
Numeracy	Calculates basic measurements including mass and dimensions
Self-management	Monitors and minimises own exposure to worksite risks and hazards during work activities
Writing	Completes documentation using sector specific vocabulary, grammatical structures and conventions

Unit Mapping Information

Supersedes and is equivalent to RIICPL305D Install pre-cast access chambers.

Links

Companion Volume Implementation Guide is found on VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272>

Assessment Requirements for RIICPL305E Install pre-cast access chambers

Modification History

Release	Comments
Release 1	This version first released with RII Resources and Infrastructure Industry Training Package Version 6.0.

Performance Evidence

The candidate must demonstrate the ability to complete the tasks outlined in the elements, performance criteria and foundation skills of this unit, including evidence of the ability to:

- install pre-cast access chambers on at least two occasions, including:
 - determining location and positioning of access chamber
 - installing access chambers.

During the above, the candidate must:

- locate and apply required legislation, documentation, policies and procedures
- implement the requirements, procedures and techniques to install pre-cast access chambers, including:
 - applying problem solving and troubleshooting techniques
 - applying diagnostic techniques
- work with others to undertake and complete the installation of pre-cast access chambers that meets all required outcomes, including:
 - communicating with others to confirm work plans and specifications
 - using communication techniques and equipment to convey information to others.

Knowledge Evidence

The candidate must be able to demonstrate knowledge to complete the tasks outlined in the elements, performance criteria and foundation skills of this unit, including knowledge of:

- legislation required to install pre-cast access chambers
- policies, procedures and documentation required to install pre-cast access chambers, including those relating to:
 - hazard identification, risk assessment and response
 - project quality measures

- emergency response
- work health and safety
- environmental protection
- waste management
- communication techniques and equipment
- operational, maintenance and basic diagnostic procedures
- job plans and specifications
- site isolation and traffic control responsibilities and authorities
- manufacturer specifications for required plant and equipment
- workplace recording requirements
- using tools and equipment
- maintaining excavation and trench safety
- confined space entry
- site dewatering
- civil construction terminology relevant to installing pre-cast access chambers
- principles and techniques required to install pre-cast access chambers, including those relating to:
 - using and installing pre-cast access chambers systems
 - identifying mains pipe and utility services
 - using concrete and concrete fabrication
 - using sedimentation and erosion controls
 - working with storm-water systems
 - working with sewerage systems
 - reading and interpreting engineering drawings and design specifications
- types, characteristics, technical capabilities and limitations of plant and equipment required to install pre-cast access chambers
- components of job safety analyses (JSAs), job safety environmental analyses (JSEAs), safe work method statements (SWMS)
- components of safety data sheets (SDS) and materials handling methods.

Assessment Conditions

Mandatory conditions for assessment of this unit are stipulated below. The assessment must:

- include access to:
 - personal protective equipment
 - equipment required to install pre-cast access chambers
- be conducted in a safe environment; and,
- be assessed in the context of this sector's work environment; and,
- be assessed in compliance with relevant legislation/regulation and using policies, procedures and processes directly related to the industry sector for which it is being assessed; and,

- confirm consistent performance can be applied in a range of relevant workplace circumstances.

Where personal safety or environmental damage are limiting factors, assessment may occur in a simulated work environment* provided it is realistic and sufficiently rigorous to cover all aspects of this sector's workplace performance, including environment, task skills, task management skills, contingency management skills and job role environment skills.

- Assessor requirements**

Assessors must be able to clearly demonstrate current and relevant industry knowledge and experience to satisfy the mandatory regulatory standards as set out in the Standards for Registered Training Organisations 2015/Australian Quality Training Framework mandatory requirements for assessors current at the time of assessment and any relevant licensing and certification requirements. This includes:

- vocational competencies at least to the level being delivered and assessed
- current industry skills directly relevant to the training and assessment being provided
- current knowledge and skills in vocational training and learning that informs their training and assessment
- formal relevant qualifications in training and assessment
- having knowledge of and/or experience using the latest techniques and processes
- possessing the required level of RII training product knowledge
- having an understanding and knowledge of legislation and regulations relevant to the industry and to employment and workplaces
- demonstrating the performance evidence, and knowledge evidence outlined in this unit of competency, and
- the minimum years of current** work experience after competency has been obtained as specified below in an industry sector relevant to the outcomes of the unit.

It is also acceptable for the appropriately qualified assessor to work with an industry expert to conduct assessment together and for the industry expert to be involved in the assessment judgement. The industry expert must have current industry skills directly relevant to the training and assessment being provided. This means the industry subject matter expert must demonstrate skills and knowledge from the minimum years of current work experience after competency has been obtained as specified below, including time spent in roles related to the unit being assessed:

Industry sector	AQF indicator level***	Required assessor or industry subject matter expert experience
Drilling, Metalliferous Mining, Coal Mining, Extractive (Quarrying) and Civil Infrastructure	1	1 year
	2	2 years
Drilling, Coal Mining, Extractive (Quarrying), Metalliferous Mining and Civil Infrastructure	3-6	3 years

Other sectors	Where this unit is being assessed outside of the resources and infrastructure sectors assessor and/or industry subject matter expert experience should be in-line with industry standards for the sector in which it is being assessed and where no industry standard is specified should comply with any relevant regulation.
---------------	--

*Guidance on simulated environments has been stipulated in the RII implementation guide located on VETNet.

**Assessors can demonstrate current work experience through employment within industry in a role relevant to the outcomes of the unit; or, for external assessors this can be demonstrated through exposure to industry by conducting a minimum number of site assessments as determined by the relevant industry sector, across various locations.

*** While a unit of competency does not have an AQF level, where a unit is being delivered outside of a qualification the first numeric character in the unit code should be considered as the AQF indicator level for assessment purposes.

Links

Companion Volume Implementation Guide is found on VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272>