



Australian Government

RIICTC301E Install tunnelling constructions services

Release: 1

RIICTC301E Install tunnelling constructions services

Modification History

Release	Comments
Release 1	This version first released with RII Resources and Infrastructure Industry Training Package Version 6.0.

Application

This unit describes the skills and knowledge required to install tunnelling constructions services in civil construction, including air and ventilation ducting, pipelines and road and rail access.

It applies to those working in operational roles. They generally work under minimal supervision to undertake a broad range of tasks in varied work contexts, using some discretion and judgement in selecting equipment, services or contingency measures.

Licensing, legislative and certification requirements that apply to this unit can vary between states, territories, and industry sectors. Users must check requirements with relevant body before applying the unit.

Unit Sector

Civil construction

Elements and Performance Criteria

ELEMENT	PERFORMANCE CRITERIA
<i>Elements describe the essential outcomes.</i>	<i>Performance criteria describe the performance needed to demonstrate achievement of the element.</i>
1. Plan and prepare to install tunnelling construction services	1.1 Obtain, interpret, clarify and confirm work instructions 1.2 Access, interpret and apply documentation required to install and maintain tunnelling construction services and confirm work activity is compliant 1.3 Confirm and identify requirements for complying with environmental protection, safety and traffic management signage requirements 1.4 Select equipment and tools required for work activities and check for faults 1.5 Select and wear personal protective equipment according to site

ELEMENT	PERFORMANCE CRITERIA
	requirements 1.6 Identify and address potential risks, hazards and environmental issues, and implement control measures within scope of own role 1.7 Obtain and interpret emergency procedures and identify steps required to respond to emergencies
2. Install ducting for air and ventilation	2.1 Install pipeline for compressed air to design location and connect to compressor 2.2 Install pipeline for air supply to location and specifications 2.3 Install ventilation ducting to location and specifications
3. Install pipelines	3.1 Install pipelines for drainage and connect to pumping system according to job requirements 3.2 Install pipelines for water supply according to job requirements
4. Install road or rail access	4.1 Lay, spread and compact material to provide surface for vehicular access where required 4.2 Identify and confirm rail track construction from tunnel drawings and specifications 4.3 Lay and install rail track to specifications 4.4 Install warning and directional signage to designed locations
5. Maintain services	5.1 Maintain service ducting and pipelines to operational conditions 5.2 Maintain access facilities to safe working operational requirements 5.3 Inspect and maintain rail track according to job requirements
6. Conduct clean-up activities	6.1 Clear work area and dispose or recycle materials according to site requirements 6.2 Plant, tools and equipment are cleaned, checked, maintained and stored according to manufacturer specifications and site requirements 6.3 Carry out housekeeping activities according to site requirements

Foundation Skills

This section describes those language, literacy, numeracy and employment skills that are essential to performance but not explicit in the performance criteria.

Skill	Description
Numeracy	Calculates basic measurements including mass and dimensions
Self-management	Monitors and minimises own exposure to worksite risks and hazards during work activities

Skill	Description
Writing	Completes documentation using sector specific vocabulary, grammatical structures and conventions

Unit Mapping Information

Supersedes and is equivalent to RIICTC301D Install tunnelling constructions services.

Links

Companion Volume Implementation Guide is found on VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272>

Assessment Requirements for RIICTC301E Install tunnelling constructions services

Modification History

Release	Comments
Release 1	This version first released with RII Resources and Infrastructure Industry Training Package Version 6.0.

Performance Evidence

The candidate must demonstrate the ability to complete the tasks outlined in the elements, performance criteria and foundation skills of this unit, including evidence of the ability to:

- install tunnelling constructions services on at least two occasions, including installing at least:
 - twenty metres of ventilation,
 - twenty metres of drainage, and
 - twenty metres of road or rail access for one project to job specification.

During the above, the candidate must:

- locate and apply required, legislation documentation, policies and procedures
- implement the requirements, procedures and techniques to install tunnelling constructions services, including:
 - applying equipment and manual handling techniques
 - selecting and using required tools and equipment
- work with others to undertake and complete the installation of tunnelling constructions services that meets all required outcomes, including:
 - organising work activities to meet task requirements
 - communicating with others to receive and clarify work instructions
 - using communication techniques and systems to advise others of work activity and exclusion zones.

Knowledge Evidence

The candidate must be able to demonstrate knowledge to complete the tasks outlined in the elements, performance criteria and foundation skills of this unit, including knowledge of:

- legislation required to install tunnelling constructions services

- policies, procedures and documentation required to install tunnelling constructions services, including those relating to:
 - work health and safety
 - emergency response
 - environmental management
 - waste management
 - manufacturer specifications for required plant and equipment
 - site isolation and traffic control responsibilities and authorities
 - warning and directional signage
 - communication techniques and equipment
 - ventilation
 - project quality requirements
 - operational, maintenance and basic diagnostic procedures
 - job plans and specifications
 - housekeeping activities, including:
 - cleaning up work area
 - cleaning, maintaining and storing equipment
 - waste management
 - processing records
- civil construction terminology relevant to installing tunnelling constructions services
- principles and techniques for effective installation of tunnel constructions services, including those relating to:
 - interpreting tunnel drawings and specifications
 - installing ducting for ventilation
 - installing pipelines
 - installing road or rail access
- types, characteristics, technical capabilities and limitations of plant and equipment required to install tunnelling constructions services
- components of safety data sheets (SDS) and materials handling methods.

Assessment Conditions

Mandatory conditions for assessment of this unit are stipulated below. The assessment must:

- include access to:
 - personal protective equipment
 - equipment required to install tunnelling construction services
- be conducted in a safe environment; and,
- be assessed in the context of this sector's work environment; and,
- be assessed in compliance with relevant legislation/regulation and using policies, procedures and processes directly related to the industry sector for which it is being assessed; and,

- confirm consistent performance can be applied in a range of relevant workplace circumstances.

Where personal safety or environmental damage are limiting factors, assessment may occur in a simulated work environment* provided it is realistic and sufficiently rigorous to cover all aspects of this sector's workplace performance, including environment, task skills, task management skills, contingency management skills and job role environment skills.

Assessor requirements

Assessors must be able to clearly demonstrate current and relevant industry knowledge and experience to satisfy the mandatory regulatory standards as set out in the Standards for Registered Training Organisations 2015/Australian Quality Training Framework mandatory requirements for assessors current at the time of assessment and any relevant licensing and certification requirements. This includes:

- vocational competencies at least to the level being delivered and assessed
- current industry skills directly relevant to the training and assessment being provided
- current knowledge and skills in vocational training and learning that informs their training and assessment
- formal relevant qualifications in training and assessment
- having knowledge of and/or experience using the latest techniques and processes
- possessing the required level of RII training product knowledge
- having an understanding and knowledge of legislation and regulations relevant to the industry and to employment and workplaces
- demonstrating the performance evidence, and knowledge evidence outlined in this unit of competency, and
- the minimum years of current** work experience after competency has been obtained as specified below in an industry sector relevant to the outcomes of the unit.

It is also acceptable for the appropriately qualified assessor to work with an industry expert to conduct assessment together and for the industry expert to be involved in the assessment judgement. The industry expert must have current industry skills directly relevant to the training and assessment being provided. This means the industry subject matter expert must demonstrate skills and knowledge from the minimum years of current work experience after competency has been obtained as specified below, including time spent in roles related to the unit being assessed:

Industry sector	AQF indicator level***	Required assessor or industry subject matter expert experience
Drilling, Metalliferous Mining, Coal Mining, Extractive (Quarrying) and Civil Infrastructure	1	1 year
	2	2 years
Drilling, Coal Mining, Extractive (Quarrying), Metalliferous Mining and	3-6	3 years

Civil Infrastructure		
Other sectors	Where this unit is being assessed outside of the resources and infrastructure sectors assessor and/or industry subject matter expert experience should be in-line with industry standards for the sector in which it is being assessed and where no industry standard is specified should comply with any relevant regulation.	

*Guidance on simulated environments has been stipulated in the RII implementation guide located on VETNet.

**Assessors can demonstrate current work experience through employment within industry in a role relevant to the outcomes of the unit; or, for external assessors this can be demonstrated through exposure to industry by conducting a minimum number of site assessments as determined by the relevant industry sector, across various locations.

*** While a unit of competency does not have an AQF level, where a unit is being delivered outside of a qualification the first numeric character in the unit code should be considered as the AQF indicator level for assessment purposes.

Links

Companion Volume Implementation Guide is found on VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272>