



Australian Government

RIIMPO326D Conduct civil construction water cart operations

Release: 3

RIIMPO326D Conduct civil construction water cart operations

Modification History

Release	Comment
1	This unit replaces RIIMPO326A Conduct civil construction water cart operations.
2	Performance Evidence wording amended; removed repetition from Performance Criteria; amend reference to Licensing requirements in Unit Application.
3	Required frequency and volume of evidence amended in Performance evidence. Substantial amendments made in Assessment Conditions field, including: references to Industry Sectors, assessor and subject matter expert experience requirements, how assessment should be conducted and what it should confirm.

Application

This unit describes a participant's skills and knowledge required to conduct civil construction water cart operations in Civil construction.

This unit is appropriate for those working in operational roles.

Licensing, legislative, regulatory and certification requirements that apply to this unit can vary between states, territories, and Industry sectors. Relevant information must be sourced prior to application of the unit.

Unit Sector

Civil construction

Elements and Performance Criteria

1. Plan and prepare for water cart operations	1.1 Access, interpret and apply water cart operations documentation and ensure the work activity is compliant 1.2 Obtain, read, interpret, clarify and confirm work instructions 1.3 Identify and address risks, hazards and environmental issues and implement control measures 1.4 Select and wear personal protective equipment appropriate for work activities 1.5 Obtain, identify and implement traffic management signage requirements 1.6 Select, and check for faults, equipment and/or attachments for
---	--

	work activities 1.7 Obtain and interpret emergency procedures, and be prepared for fire/accident/emergency
2. Operate water cart	2.1 Carry out pre-start, start-up, park, shutdown and secure equipment procedures 2.2 Coordinate activities with others at the site prior to commencement of, and during, the work activity 2.3 Continually monitor hazards and risks , and ensure safety of self, other personnel, plant and equipment 2.4 Manage engine power to ensure efficiency of water cart platform movements and to minimise damage to the engine and gears 2.5 Coordinate engine power with gear selection to ensure smooth transition and operation within torque range 2.6 Drive and operate water cart, and modify the operating technique to meet changing work conditions 2.7 Bring vehicle to a halt smoothly, minimising the wear and tear on vehicle using the engine retarder, gears and brakes
3. Load, transport and distribute water	3.1 Position water cart at load and discharge/distribution points 3.2 Load water cart to within the authorised carrying capacity and to suit the site and task conditions 3.3 Carry out water haulage operations efficiently, safely and smoothly avoiding surge and sway 3.4 Discharge/distribute water efficiently in accordance with requirements and procedures 3.5 Monitor and maintain discharge and distribution systems throughout the operations 3.6 Complete work the workplan within the operating capacity of the equipment
4. Carry out machine operator maintenance	4.1 Prepare machine for maintenance 4.2 Conduct inspection and fault finding 4.3 Carry out scheduled maintenance tasks 4.4 Process written maintenance records
5. Conduct housekeeping activities	5.1 Clear work area and dispose of or recycle materials 5.2 Process records

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit. Further information is available in the Resources and Infrastructure Industry Training Package Companion Volume.

Unit Mapping Information

RIIMPO326A Conduct civil construction water cart operations

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272>

Assessment Requirements for RIIMPO326D Conduct civil construction water cart operations

Modification History

Release	Comment
1	This unit replaces RIIMPO326A Conduct civil construction water cart operations.
2	Performance Evidence wording amended; removed repetition from Performance Criteria; amend reference to Licensing requirements in Unit Application.
3	Required frequency and volume of evidence amended in Performance evidence. Substantial amendments made in Assessment Conditions field, including: references to Industry Sectors, assessor and subject matter expert experience requirements, how assessment should be conducted and what it should confirm.

Performance Evidence

Evidence is required to be collected that demonstrates a candidate's competency in this unit. Evidence must be relevant to the roles within this sector's work operations and satisfy all of the requirements of the performance criteria of this unit and include evidence that the candidate:

- locates and applies relevant documentation, policies and procedures
- implements the requirements, procedures and techniques for the safe, effective and efficient completion of water cart operations including:
 - conducting prestart checks prior to commencing operations and shutdown procedures on completion of operations
 - carrying out vehicle refuelling requirements and procedures
 - driving and operating the equipment to site conditions
 - applying safe work practices and identifying and reporting all potential hazards, risks and environmental issues
 - applying problem solving and troubleshooting techniques
 - applying water distribution techniques
 - selecting and using the required tools and equipment
 - working safely around other machines and personnel
 - safely parking and securing of equipment
- works effectively with others to undertake and complete water cart operations that meet all of the required outcomes including:
 - using a range of communications techniques and equipment to convey information to others

- maintaining written and verbal reporting requirements and procedures
- organising work activities to meet all task requirements
- communicating clearly and concisely with others to receive and clarify work instructions
- demonstrates completion of civil construction water cart operations that safely, effectively and efficiently meets all of the required outcomes on more than one (1) occasion including:
 - completion of the loading, transporting, discharging and distribution of water including:
 - completion of pressure and gravity discharging of water evenly in civil construction compaction operations in a minimum of two different soil types to meet moisture content requirements
 - completion of pressure and gravity distribution of water into two separate water storage facilities/receptacles
 - completion of dust suppression operations

Knowledge Evidence

The candidate must demonstrate knowledge of the following when conducting civil construction water cart operations:

- identifying, interpreting ground conditions
- communicating and performing isolation procedures
- being prepared for fire/accident/emergency
- identifying signs of operator fatigue and how it should be managed
- interpreting drawings and sketches
- identifying site isolation and traffic control responsibilities and authorities
- using civil construction terminology
- complying with project quality requirements
- applying basic principles of soil technology and soil compaction for civil works
- identifying basic soil types and characteristics
- communicating basic soil compaction theory including the effects of moisture content and mechanical interlock
- applying practical field tests for moisture content
- using pumps and pumping system operations
- identifying water distribution systems types, characteristics, technical capabilities and limitations
- describing basic dust suppression theory
- identifying the causes and effects of surge and sway in bulk fluid loads
- using basic earthworks calculations
- using civil construction activity sequences of road construction, earthworks and drainage
- using methods for calculating safe working loads

- applying operational, maintenance and basic diagnostics
- completing housekeeping activities

Assessment Conditions

- An assessor of this unit must satisfy the requirements of the NVR/AQTF or their successors; and Industry regulations for certification and licensing; and,
- this unit must be assessed in the context of this sector's work environment; and,
- this unit must be assessed in compliance with relevant legislation/regulation and using policies, procedures, processes and operational manuals directly related to the industry sector for which it is being assessed; and,
- assessment may be conducted in conjunction with the assessment of other Units of Competency; and,
- assessment must confirm consistent performance can be applied in a range of relevant workplace circumstances; and,
- assessors must demonstrate the performance evidence, and knowledge evidence as outlined in this Unit of Competency, and through the minimum years of current* work experience specified below in an Industry sector relevant to the outcomes of the unit; or,
- where the assessor does not meet experience requirements a co-assessment or partnership arrangement must exist between the qualified assessor and an Industry subject matter expert. The Industry subject matter expert should hold the unit being assessed (or an equivalent unit) and/or demonstrate equivalence of skills and knowledge at the unit level. An Industry technical expert must also demonstrate skills and knowledge from the minimum years of current work experience specified below in the Industry sector, including time spent in roles related to the unit being assessed; and,
- assessor and Industry subject matter expert requirements differ depending on the Australian Qualifications Framework Level (AQF) of the qualification being assessed and/or Industry Sector as follows:

Industry sector	AQF** Level	Required assessor or Industry subject matter expert experience
Drilling, Metalliferous Mining, Coal Mining, Extractive (Quarrying) and Civil Construction	1	1 Year
	2	2 Years
Drilling, Coal Mining and Extractive (Quarrying)	3-6	3 Years
Metalliferous Mining and Civil Construction	3-6	5 Years
Other sectors	Where this Unit is being assessed outside of the Resources and Infrastructure Sectors assessor and/or Industry subject matter expert experience should be in-line with industry standards for the sector in which it is being	

	assessed and where no Industry standard is specified should comply with any relevant regulation.
--	--

*Assessors can demonstrate current work experience through employment within Industry in a role relevant to the outcomes of the Unit; or, for external assessors this can be demonstrated through exposure to Industry by conducting frequent site assessments across various locations.

**Where a unit is being delivered outside of a Qualification the first numeric character in the Unit code should be considered to indicate the AQF level

Links

Companion Volume implementation guides are found in VETNet -

<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=88a61002-9a21-4386-aaf8-69c76e675272>