



Australian Government

Department of Education, Employment and Workplace Relations

RIICTC301A Install tunnelling constructions services

Release: 1

RIICTC301A Install tunnelling constructions services

Modification History

Not applicable.

Unit Descriptor

This unit covers the installation of tunnelling construction services in the civil construction industry. It includes planning and preparing for tunnel construction services, installing ducting for air and ventilation, installing pipelines for construction services, installing road/rail access, maintaining services, and cleaning up. Licensing, legislative, regulatory and certification requirements that apply to this unit can vary between states, territories, and industry sectors. Relevant information must be sourced prior to application of the unit.

Application of the Unit

This unit is appropriate for those working in an operational role at worksites within:

- Civil construction

Licensing/Regulatory Information

Refer to Unit Descriptor.

Pre-Requisites

Not applicable.

Employability Skills Information

This unit contains employability skills.

Elements and Performance Criteria Pre-Content

Elements describe the essential outcomes of a unit of competency.	Performance criteria describe the performance needed to demonstrate achievement of the element. Where bold italicised text is used, further information is detailed in the required skills and knowledge section and the range statement. Assessment of performance is to be consistent with the evidence guide.
---	--

Elements and Performance Criteria

ELEMENT	PERFORMANCE CRITERIA
1 Plan and prepare	1.1. Access, interpret and apply compliance documentation relevant to the work activity 1.2. Obtain and confirm safety requirements from the site safety plan and organisational policies and procedures, and apply to the allotted task 1.3. Identify, obtain and implement signage requirements from the project traffic management plan 1.4. Select plant, tools and equipment to carry out tasks consistent with the requirements of the job, check for serviceability and rectify or report any faults 1.5. Identify environmental protection requirements from the project environmental management plan, and confirm and apply to the allotted task
2. Install ducting for air and ventilation	2.1. Install pipeline for compressed air to design location and connect to compressor 2.2. Install pipeline for air supply to location and specifications 2.3. Install ventilation ducting to location and specifications
3. Install pipelines for construction services	3.1. Install pipelines for drainage and connect to pumping system 3.2. Install pipelines for water supply to relevant water authority requirements
4. Install road/rail access	4.1. Lay, spread and compact material to provide surface for vehicular access where required 4.2. Identify rail track construction from tunnel drawings and specifications 4.3. Lay and install rail track to specifications 4.4. Install warning and directional signage to designed locations
5. Maintain services	5.1. Maintain service ducting and pipelines to operational conditions 5.2. Maintain access facilities to safe working operational requirements 5.3. Inspect and maintain rail track

6. Clean up	6.1. Clear work area and dispose or recycle materials in accordance with project environmental management plan 6.2. Plant, tools and equipment are cleaned, checked, maintained and stored
-------------	---

Required Skills and Knowledge

This section describes the skills and knowledge required for this unit.

Required skills

Specific skills are required to achieve the Performance Criteria of this unit, particularly for its application in the various circumstances in which this unit may be used. This includes the ability to carry out the following, as required to install tunneling construction services:

- apply legislative, organisation and site requirements and procedures for installing tunnelling construction services
- organise work activities
- select and use relevant tools and equipment safely
- identify and report on hazards related to the worksite and work activity
- communicate effectively to receive and clarify work instructions

Required knowledge

Specific knowledge is required to achieve the Performance Criteria of this unit, particularly for its application in the various circumstances in which this unit may be used. This includes knowledge of the following, as required to install tunneling construction services:

- site and equipment safety requirements
- tunnel construction
- tunnel construction services
- construction principles
- equipment types, characteristics, technical capabilities and limitations
- operational, maintenance and basic diagnostic procedures
- site isolation and traffic control responsibilities and authorities
- materials safety data sheets and materials handling methods
- project quality requirements
- civil construction terminology
- JSAs/safe work method statement

Evidence Guide

The evidence guide provides advice on assessment and must be read in conjunction with the performance criteria, required skills and knowledge, range statement and the Assessment Guidelines for the Training Package.

Overview of assessment	
Critical aspects for assessment and evidence required to demonstrate competency in this unit	The evidence required to demonstrate competency in this unit must be relevant to worksite operations and satisfy all of the requirements of the performance criteria, required skills and knowledge and the range statement of this unit and include evidence of the following: • knowledge of the requirements, procedures and instructions for installing tunnelling construction services • implementation of requirements, procedures and techniques for the safe, effective and efficient completion of tunnelling construction services installation • working with others to undertake and complete the installation of tunnelling construction services that meets all of the required outcomes • consistent timely completion of tunnelling construction services installation that safely, effectively and efficiently meets the required outcomes • installation of a minimum of 20 metres of ventilation, 20 metres of drainage and 20 metres of road/rail access for one project, to job specification
Context of and specific resources for assessment	• This unit must be assessed in the context of the work environment. Where personal safety or environmental damage are limiting factors, assessment may occur in a simulated environment provided it is realistic and sufficiently rigorous to cover all aspects of workplace performance, including task skills, task management skills, contingency management skills and job role environment skills. • Assessment of this competency requires typical resources normally used in a resources and infrastructure sector environment. Selection and use of resources for particular worksites may differ due to the site

	circumstances. • The assessment environment should not disadvantage the participant. For example, language, literacy and numeracy demands of assessment should not be greater than those required on the job. • Customisation of assessment and delivery environment to sensitively accommodate cultural diversity. • Aboriginal people and other people from a non English speaking background may have second language issues. • Where applicable, physical resources should include equipment modified for people with disabilities. Access must be provided to appropriate learning and/or assessment support when required.
Method of assessment	This unit may be assessed in a holistic way with other units of competency. The assessment strategy for this unit must verify required knowledge and skill and practical application using more than one of the following assessment methods: • written and/or oral assessment of the candidate's required knowledge • observed, documented and/or first hand testimonial evidence of the candidate's: • implementation of appropriate requirement, procedures and techniques for the safe, effective and efficient achievement of required outcomes • consistent achievement of required outcomes • first hand testimonial evidence of the candidate's: • working with others to undertake and complete the installation of tunnelling construction services
Guidance information for assessment	Consult the SkillsDMC User Guide for further information on assessment including access and equity issues.

Range Statement

The range statement relates to the unit of competency as a whole. It allows for different work environments and situations that may affect performance. Bold italicised wording, if used in the performance criteria, is detailed below. Essential operating conditions that may be present with training and assessment (depending on the work situation, needs of the candidate, accessibility of the item, and local industry and regional contexts) may also be included.

Relevant compliance documentation may include:	• legislative, organisational and site requirements and procedures • site safety plan • manufacturer's guidelines and specifications • Australian standards • Employment and workplace relations legislation • Equal Employment Opportunity and Disability Discrimination legislation
Safety requirements may include:	• OHS requirements in accordance with state or territory legislation and regulations, organisational safety policies and procedures, and project safety plan, including protective clothing and equipment, use of tools and equipment, workplace environment and safety, handling of materials, use of fire fighting equipment, use of First Aid equipment, hazard control and hazardous materials and substances • safe parking practices including ensuring access ways are clear, equipment/machinery is away from overhangs and refuelling sites, safe distance are kept from excavations, and areas secured from unauthorised access or movement • safe operating procedures including recognising and preventing hazards associated with uneven/unstable terrain, trees, pits, poles, trip hazards, dirt mounds, overhead service lines, bridges, surrounding buildings, obstructions, structures, facilities, dangerous materials, recently filled trenches, other machines, personnel, traffic control, working in proximity to others, worksite visitors and the public • recognising hazards and risks including uneven/unstable terrain, trees, fires, overhead and underground services, bridges, buildings, excavations, traffic, embankments, cuttings, structures and hazardous materials

	• emergency procedures related to equipment operation including emergency shutdown and stopping, extinguishing equipment fires, organisational First Aid requirements and evacuation
Signage may include:	• escort vehicle • highway traffic signs • site safety signage • temporary signage for the benefit of motorists and pedestrians • traffic conditions signage
Traffic conditions may include:	• congested urban environments • low traffic rural areas • off-road un-trafficked areas • buildings • parking sites • pedestrian areas
Tools and equipment may include:	• hydraulic pipe jacks • shovels • compressors • generators
Environmental protection requirements may include:	• organisational/project environmental management plan • waste management • water quality protection • noise • vibration • dust and clean-up management
Materials may include:	• reinforced concrete pipes • air ventilation • ducting • strip drainage • drainage conduit

Unit Sector(s)

Tunnel Construction

Competency field

Refer to Unit Sector(s).

Co-requisite units

Not applicable.