



Australian Government

UETDRTO014 Set-up and install transmission structure stubs

Release: 1

UETDRT0014 Set-up and install transmission structure stubs

Modification History

Release 1. This is the first release of this unit of competency in the UET Transmission, Distribution and Rail Sector Training Package Release 2.0.

Application

This unit covers the utilisation of geographical maps and site surveys to set out, excavate, prepare, align and install the foundation footings of a transmission tower and establish the tower stubs to ground level for the erection of transmission towers. Survey processes and operation of survey equipment is associated with this unit.

The application of the skills and knowledge described in this unit may require a licence/registration to practice in the workplace subject to regulations for undertaking of electrical work.

Other conditions may apply under state and territory legislative and regulatory licensing requirements which must be confirmed prior to commencing this unit.

Pre-requisite Unit

UEECD0007 Apply work health and safety regulations, codes and practices in the workplace

UETDREL005 Work safely in the vicinity of live electrical apparatus

Competency Field

Transmission Overhead

Unit Sector

Not applicable.

Elements and Performance Criteria

ELEMENTS

Elements describe the essential outcomes.

1 Prepare for the setting of a transmission tower stub

PERFORMANCE CRITERIA

Performance criteria describe the performance needed to demonstrate achievement of the element.

1.1 Work schedule, including drawings, plans, requirements, established procedures and material lists, are received,

analysed and confirmed, as necessary, by site inspection

- 1.2** Relevant requirements and established procedures for the work are communicated to all personnel and identified for all worksites
- 1.3** Work health and safety (WHS)/occupational health and safety (OHS) policies and procedures related to requirements and established procedures for construction activities are obtained and confirmed for the purposes of the work to be performed and communicated
- 1.4** Work is prioritised and sequenced following consultation with others for completion within acceptable timeframes and in accordance with established procedures
- 1.5** Hazards are identified, WHS/OHS risks assessed and control measures prioritised, implemented and monitored, including emergency exits kept clear according to established procedures
- 1.6** Resources, including personnel, equipment, tools and personal protective equipment (PPE), required for the job are obtained and confirmed in working order
- 1.7** Relevant work permits are obtained to access and perform work according to requirements and/or established procedures
- 1.8** Relevant personnel at worksite are confirmed current in first aid, rescue and other related work procedures according to requirements
- 1.9** Liaison and communication issues with others/authorised personnel, authorities, clients and landowners are resolved to carry out work where necessary
- 1.10** Site is prepared according to the work schedule and to minimise risk and damage to property, commerce and individuals in accordance with established procedures
- 1.11** Personnel participating in the work, including plant operators and contractors, are fully briefed and respective responsibilities confirmed, where applicable, in accordance with established procedures
- 1.12** Traffic management plan is identified and implemented,

where appropriate

2 Carry out the setting of a transmission tower stub

- 2.1** WHS/OHS, sustainable energy and environmental principles and practices to reduce the incidents of accidents and minimise waste are monitored and followed in accordance with requirements and/or established procedures
- 2.2** Hazard warnings and safety signs are recognised and hazards and assessed WHS/OHS risks reported to immediate authorised personnel for directions according to established procedures
- 2.3** Lifting, climbing, working in excavations and use of power tools/equipment, techniques and practices are safely followed, and currency according to requirements confirmed
- 2.4** Essential knowledge and associated skills are applied in the survey and establishment of tower stubs to ensure completion in an agreed timeframe, and to quality standards with a minimum of waste according to requirements
- 2.5** Unplanned events in the establishment of tower stubs are undertaken within the scope of established procedures
- 2.6** Known solutions to a variety of problems are applied using acquired essential knowledge and associated skills
- 2.7** Ongoing checks of quality of the work are undertaken in accordance with instructions and established procedures

3 Complete the setting up of a transmission tower stub

- 3.1** Work undertaken is checked against work schedule for conformance with requirements and anomalies reported in accordance with established procedures
- 3.2** Accidents and/or injuries are reported in accordance with requirements/established procedures, where applicable
- 3.3** Worksite is rehabilitated, cleaned up and made safe in accordance with established procedures
- 3.4** Tools, equipment and any surplus resources and materials are, where appropriate, cleaned, checked and returned to storage or disposed of in accordance with established procedures
- 3.5** Relevant work permits are signed off, where appropriate, and equipment returned to service in accordance with

requirements

- 3.6 Work completion records, reports, as installed/modified drawing and/or documentation and information are finalised and processed and appropriate personnel notified

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Range of Conditions

Range is restricted to essential operating conditions and any other variables essential to the work environment.

Non-essential conditions may be found in the UET Transmission, Distribution and Rail Sector Training Package Companion Volume Implementation Guide.

Unit Mapping Information

This unit replaces and is equivalent to UETTDRT28 Set-up and install transmission structure stubs.

Links

Companion Volume Implementation Guides are found in VETNet -
<https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=229bace1-b7bc-4653-9300-dffb13ecfad7>