



Australian Government

UETTD RTP23 Erect power systems transmission structures

Release: 1

UETTD RTP23 Erect power systems transmission structures

Modification History

Release 1. This is the first release of this unit of competency in the UET Transmission, Distribution and Rail Sector Training Package.

Application

This unit covers the erection of towers, in sections or in parts, in accordance with construction plans and specifications. It includes the correct positioning of road signs, barriers and/or warning devices; the inspection and confirmation that excavation/foundation construction is in accordance with the work order; and the identification of potential hazards and safety risks with recommendations for preventative action being referred to appropriate authorities.

The application of the skills and knowledge described in this unit may require a licence/registration to practice in the workplace subject to regulations for undertaking of electrical work.

Other conditions may apply under state and territory legislative and regulatory licencing requirements which must be confirmed prior to commencing this unit.

Pre-requisite Unit

Common Unit Group

UEENEEE101A Apply Occupational Health and Safety regulations, codes and practices in the workplace

UETTDREL13 Comply with sustainability, environmental and incidental response policies and procedures

Competency Field

Transmission

Unit Sector

Not applicable.

Elements and Performance Criteria

ELEMENTS

PERFORMANCE CRITERIA

Elements describe the essential Performance criteria describe the performance needed to

outcomes.

demonstrate achievement of the element.

1 Prepare to erect transmission towers

- 1.1** Work instructions are received and confirmed
- 1.2** Relevant requirements and established procedures to be followed for the work to be performed are discussed with all personnel to establish and confirm the work schedule
- 1.3** Work health and safety (WHS)/occupational health and safety (OHS) policies and procedures to be followed for the work to be performed are received and confirmed
- 1.4** Suggestions to assist in meeting erection of towers outcomes are made to others involved in the work
- 1.5** Hazards are identified, WHS/OHS risks assessed and emergency exits kept clear according to given instructions and established procedures
- 1.6** Scope of responsibility under the relevant work permit are received and confirmed with relevant personnel according to requirements and established procedures
- 1.7** Resources, including, equipment, tools and personnel protective equipment (PPE), required for the job are obtained and confirmed safe and in working order according to established procedures
- 1.8** Relevant responsibility associated with first aid, tower/pole top rescue and/or other related work safety procedures at the worksite are confirmed in accordance with requirements and established procedures to ensure safety measures are followed in the instance of an incident
- 1.9** Client issues are referred to appropriate personnel in accordance with industry/community standards
- 1.10** Site is prepared according to given instructions and the work schedule for a quality outcome and to minimise risk and damage to property, commerce and individuals in accordance and established procedures
- 1.11** Road signs, barriers and warning devices are positioned in accordance with given instructions and requirements

2 Carry out the erection of

- 2.1** WHS/OHS and sustainable energy principles and practices to reduce the incidents of accidents and

transmission towers		minimise waste are followed in accordance with given instructions, requirements and/or established procedures
	2.2	Lifting, climbing, working aloft, and use of power tools/equipment, techniques and practices are safely followed in accordance with given instructions and according to requirements confirmed to eliminate the prospects of incidents
	2.3	Operational knowledge for the operation of support plant and equipment used for the erection of towers to be applied to the work is confirmed to ensure completion in an agreed timeframe and to quality standards with a minimum of waste according to requirements and established procedures
	2.4	Operation of support plant and equipment used for the erection of towers is carried out in accordance with given instructions and established routines/procedures
	2.5	Hazard warnings and safety signs are recognised and hazards and assessed WHS/OHS risks reported to immediate authorised personnel for directions according to established procedures
	2.6	Non-routine events are referred to immediate authorised personnel for directions according to established procedures
	2.7	Problems associated with operation of support plant and equipment used for the erection of towers are dealt with using acquired known solutions and skills related to routine procedures to ensure work instructions and established procedures are met
	2.8	Ongoing checks of quality of the work are undertaken in accordance with given instructions and established procedures
3 Complete the erection of transmission towers	3.1	Work undertaken is checked against work schedule and anomalies reported to authorised personnel in accordance with established procedures
	3.2	Accidents and/or incidents are actioned and reported to authorised personnel in accordance with established procedures
	3.3	Worksite is rehabilitated, cleaned up and made safe in accordance with given instructions and established

procedures

- 3.4 Tools, equipment and any surplus resources and materials are, where appropriate, cleaned, checked and returned to storage in accordance with established procedures
- 3.5 Appropriate personnel are notified of work completion according to established procedures
- 3.6 Work completion records and report forms/data sheets are completed accurately in accordance with given instructions and established procedures

Foundation Skills

Foundation skills essential to performance are explicit in the performance criteria of this unit of competency.

Range of Conditions

Range is restricted to essential operating conditions and any other variables essential to the work environment.

Non-essential conditions may be found in the Companion Volume Implementation Guide.

Unit Mapping Information

This unit replaces and is equivalent to UETTD RTP23A Erect power systems transmission structures.

Links

UET Training Package Companion Volume Implementation Guide is found in VETNet - <https://vetnet.gov.au/Pages/TrainingDocs.aspx?q=229bace1-b7bc-4653-9300-dffb13ecfad7>